

# FAT CHANCE OIL AND GAS, LLC

January 29, 2001

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

**RE: Confidentiality of information: Crane 6-7**

Attention:

Fat Chance Oil and Gas, LLC formally requests that submitted information on the Crane 6-7 be held confidential.

Your cooperation is appreciated.

Sincerely,

Casey Osborn  
Operations Manager/Agent

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐  
(highlight changes)

APPLICATION FOR PERMIT TO DRILL

1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER <input type="checkbox"/> SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: Fat Chance Oil and Gas, LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: PO Box 7370 CITY Sheridan STATE WY ZIP 82801		8. WELL NAME and NUMBER: Crane 6-7
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 2125' FNL 1936' FWL AT PROPOSED PRODUCING ZONE: same		9. FIELD AND POOL, OR WILDCAT: Wildcat
13. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 5 miles west of Evanston		10. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: 4568509 N 492911 E SE NW 7 T6N R8E
14. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 2875'		11. COUNTY: Rich
15. NUMBER OF ACRES IN LEASE: 52,395		12. STATE: UTAH
16. NUMBER OF ACRES ASSIGNED TO THIS WELL: 160		
17. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 3250'		19. BOND DESCRIPTION: Utah DOGM Surety #885588C
18. PROPOSED DEPTH: 5,000		22. ESTIMATED DURATION: 10 days
20. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 6833' GR		
21. APPROXIMATE DATE WORK WILL START: 4/15/2001		

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
12 1/4"	9 5/8" H-40 32.3#	500	G-Poz 250 sx 1.77 12.5# lead 50sx 1.17 15.8" tail
8 3/4"	7" K-55 20#	5,000	G-35/65 Poz 150 sx 2.34 11# lead 50 sx 1.27 14.2# tail

ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- |  |   |
|--|---|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER     | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN  |
| <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input checked="" type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

NAME (PLEASE PRINT) Casey Osborn

TITLE Operations Manager

SIGNATURE

DATE

1-29-01

(This space for State use only)

API NUMBER ASSIGNED:

43-033-30053

APPROVAL:

RECEIVED

FEB 23 2001

DIVISION OF  
OIL, GAS AND MINING


T6N, R8E, S.L.B.&M.

QUANECO, LLC

Well location, CRANE #6-7, located as shown in the SE 1/4 NW 1/4 of Section 7, T6N, R8E, S.L.B.&M., Rich County, Utah.

# BASIS OF ELEVATION

SPOT ELEVATION LOCATED IN THE SW 1/4 OF SECTION 31, T7N, R8E, S.L.B.&M. TAKEN FROM THE MURPHY RIDGE QUADRANGLE, UTAH-WYOMING, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 7184 FEET.



SCALE


## CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

NO. 161319  
ROBERT L. RAY  
REGISTERED LAND SURVEYOR  
REGISTRATION NO. 161319  
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING  
85 SOUTH 200 EAST - VERNAL, UTAH 84078  
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 1-11-01	DATE DRAWN: 1-19-01
PARTY B.B. J.W D.COX	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE QUANECO, LLC	



U.E.&S.  
1997 Private Alum.  
Cap 0.3' High, Steel  
Post, Scattered Stones  
324872

## LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

LATITUDE = 41°16'12"  
LONGITUDE = 111°05'04"

# QUANECO, LLC.

## CRANE #6-7

LOCATED IN RICH COUNTY, UTAH  
SECTION 7, T6N, R8E, S.L.B.&M.



PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: SOUTHWESTERLY




PHOTO: EXISTING ACCESS AT EDGE OF PAD

CAMERA ANGLE: NORTHWESTERLY



- Since 1964 -

**UELS** Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

### LOCATION PHOTOS

TAKEN BY: B.B.

DRAWN BY: K.G.

**1 18 01**  
MONTH DAY YEAR

REVISED: 00-00-00

PHOTO




# QUANECO, LLC.

## TYPICAL CROSS SECTIONS FOR



CRANE #6-7

SECTION 7, T6N, R8E, S.L.B.&M.

2125' FNL 1936' FWL



DATE: 1-19-01  
Drawn By: D.COX




### APPROXIMATE YARDAGES

(6") Topsoil Stripping	=	750 Cu. Yds.
Remaining Location	=	8,180 Cu. Yds.
<b>TOTAL CUT</b>	<b>=</b>	<b>8,930 CU.YDS.</b>
<b>FILL</b>	<b>=</b>	<b>7,460 CU.YDS.</b>

EXCESS MATERIAL AFTER 5% COMPACTION	=	1,080 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	=	1,080 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	=	0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017



# LEGEND:

○ PROPOSED LOCATION



QUANECO, LLC.

CRANE #6-7

SECTION 7, T6N, R8E, S.L.B.&M.

2125' FNL 1936' FWL



Utah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

TOPOGRAPHIC  
MAP

1 1801  
MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: K.G. REVISED: 00-00-00











# QUANECO, LLC.

## LOCATION LAYOUT FOR

CRANE #6-7  
SECTION 7, T6N, R8E, S.L.B.&M.  
2125' FNL 1936' FWL

Proposed Road  
Re-Route




SCALE: 1" = 50'  
DATE: 1-19-01  
Drawn By: D.COX

**NOTE:**  
Flare Pit is to  
be located a min.  
of 100' from the  
Well Head.

Approx.  
Top of  
Cut Slope

Approx.  
Toe of  
Fill Slope



Elev. Ungraded Ground at Location Stake = 6832.7'  
Elev. Graded Ground at Location Stake = 6829.5'

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017

# Fat Chance Oil and Gas, LLC

P.O. Box 7370  
Sheridan WY 82801  
307-673-1500 Phone  
307-673-1400 Fax

February 22, 2001

Utah Division of Oil, Gas and Mining  
ATTN: Lisha Cordova  
1594 W. North Temple  
Suite 1210  
Salt Lake City UT 84114-5801

Dear Lisha:

This affidavit is to inform your office that a surface owner agreement has been made and entered into as of the 21<sup>st</sup> day of June, 2000, by and between PROPERTY RESERVE, INC., formerly known as DESERET TITLE HOLDING CORPORATION, a Utah corporation (herein referred to as "PRI"), and FAT CHANCE OIL AND GAS, L.L.C.

This agreement pertains to several wells, but for the purposes of this affidavit, specifically addresses Crane 6-7, located in the SE1/4 of the NW1/4, Section 7, T6N, R8E.

If you have any questions, please do not hesitate to call.

Sincerely,



Casey Osborn  
Operations Manager


State of Wyoming       )  
                                  ) ss

County of Sheridan       )

The foregoing instrument was acknowledged before me by Casey Osborn this 22nd day of February, 2001.

  
Notary Public

My commission expires Nov. 17, 03



## RECEIVED

FEB 23 2001

DIVISION OF  
OIL, GAS AND MINING



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 5

DESIGNATION OF AGENT OR OPERATOR

The undersigned is, on record, the holder of oil and gas lease

LEASE NAME: Property Reserve, Skull Valley & Kavanagh

LEASE NUMBER: FEE

and hereby designates

NAME: Fat Chance Oil and Gas, LLC, an Oklahoma Limited Liability Company

ADDRESS: P. O. Box 7370, 850 Val Vista

city Sheridan state WY zip 82801

as his (check one) agent ☐ / operator ☒, with full authority to act in his behalf in complying with the terms of the lease and regulations applicable thereto and on whom the Division Director or Authorized Agent may serve written or oral instructions in securing compliance with the Oil and Gas Conservation General Rules and Procedural Rules of the Board of Oil, Gas and Mining of the State of Utah with respect to:

(Describe acreage to which this designation is applicable. Identify each oil and gas well by API number and name. Attach additional pages as needed.)

See Attached

It is understood that this designation of agent/operator does not relieve the lessee of responsibility for compliance with the terms of the lease and the Oil and Gas Conservation General Rules and Procedural Rules of the Board of Oil, Gas and Mining of the State of Utah. It is also understood that this designation of agent or operator does not constitute an assignment of any interest in the lease.

In case of default on the part of the designated agent/operator, the lessee will make full and prompt compliance with all rules, lease terms or orders of the Board of Oil, Gas and Mining of the State of Utah or its authorized representative.

The lessee agrees to promptly notify the Division Director or Authorized Agent of any change in this designation.

Effective Date of Designation: 01/01/2001

BY: (Name) Billy Jim Palone

OF: (Company) Palone Petroleum

(Signature) [Signature]

(Address) P. O. Box 6

(Title) Owner

city Gillette

(Phone) (307) 682-1621

state WY zip 82717

**Exhibit "A"**

Attached to Oil and Gas Lease between Property Reserve, Inc. and Palone Petroleum

**Tract No. 1**

**Township 9 North, Range 7 East, S.L.M.**

Section 26:	W2	311.00
Section 27:	All	640.00
Section 34:	E2, E2NW	400.00
Section 35:	All	640.00

Section 36:	Beginning at the Southwest corner of Section 36; thence North 2 3/4 degrees East 2698 feet; thence South 89 degrees East to the West boundry line of State Highway; thence South 32 degrees East along said West line 3156 feet more or less, to a point East of beginning; thence West 2210 feet, more or less, to the point of beginning.	84.00
-------------	---	-------

**Tract No. 2**

**Township 8 North, Range 7 East, S.L.M**

Section 1:	All that portion of Section 1 lying South and West of the Highway. Said highway is described as follows: A parcel of land 100 feet wide, 50 feet on each side of the following described centerline: Beginning at a point approximately 2244 feet East from the Northwest corner of said section; thence South 32 degrees 14 minutes East 1921.6 feet; thence 297.9 feet along the arc of a circle to the left whose radius is 1432.7 feet long; thence South 44 degrees 09 minutes East 2370.5 feet to the East line of said section.	489.86
Section 2:	Lot 4	28.00
Section 3:	Lots 1(28.00), 2(28.00), 3(28.00), 4(28.00), S2N2, S2	592.00
Section 10:	NE, E2NW, NESW, NWSE	320.00
Section 11:	All	640.00
Section 13:	All	640.00

**Tract No. 3**

**Township 8 North, Range 7 East, S.L.M**

Section 15:	All	640.00
Section 21:	All	640.00
Section 23:	All	640.00
Section 25:	All	640.00

**Tract No. 4**

**Township 8 North, Range 7 East, S.L.M**

Section 27:	All	640.00
Section 33:	All	640.00
Section 35:	All	640.00
Section 36:	All	640.00

**Tract No. 5**

**Township 8 North, Range 8 East, S.L.M.**

Section 31:	Lots 1(39.86), 2(39.90), 3(39.94), 4(39.98), E2W2, E2	639.68
-------------	---	--------

**Township 7 North, Range 7 East, S.L.M.**

Section 1:	Lots 1(40.22), 2(40.68), 3(41.12), 4(41.58), S2N2, S2	643.60
Section 2:	Lots 1(41.81), 2(41.84), 3(41.86), 4(41.89), S2NW	247.40
Section 3:	Lots 1(41.77), 2(41.58), 3(41.33), 4(41.11), S2N2, S2	645.79

**Tract No. 6**

**Township 7 North, Range 7 East, S.L.M.**

Section 5:	Lots 1(40.59), 2(40.76), 3(40.94), 4(41.11), S2N2, S2	643.40
Section 9:	All	640.00
Section 11:	All	640.00
Section 12:	W2	320.00
Section 13:	All	640.00

**Tract No. 7**

**Township 7 North, Range 7 East, S.L.M.**

Section 15:	All	640.00
Section 16:	W2SE	80.00
Section 17:	All	640.00
Section 19:	Lots 1(41.10), 2(41.10), 3(41.10), 4(40.44), E2W2, E2	643.74
Section 21:	All	640.00

Exhibit "A"

Attached to Oil and Gas Lease between Property Reserve, Inc. and Palone Petroleum

**Tract No. 8**

**Township 7 North, Range 7 East, S.L.M.**

Section 23:	All	640.00
Section 25:	All	640.00
Section 26:	W2W2	160.00
Section 27:	All	640.00
Section 29:	All	640.00

**Tract No. 9**

**Township 7 North, Range 7 East, S.L.M.**

Section 31:	Lots 1(39.82), 2(39.88), 3(39.92), 4(39.98), E2W2, E2	639.60
Section 32:	All	640.00
Section 33:	All	640.00
Section 35:	All	640.00

**Tract No. 10**

**Township 7 North, Range 8 East, S.L.M.**

Section 7:	Lots 1(43.03), 2(42.45), 3(41.87), 4(41.29), E2W2, E2	648.64
Section 9:	Lots 1(40.34), 2(40.34), 3(40.34), 4(40.34)	161.36
Section 17:	All	640.00
Section 19:	Lots 1(39.23), 2(38.88), 3(38.53), 4(38.18), E2W2, E2	634.82

**Tract No. 11**

**Township 7 North, Range 8 East, S.L.M.**

Section 21:	Lots 1(40.34), 2(40.34), 3(40.34), 4(40.34)	161.36
Section 29:	All	640.00
Section 31:	Lots 1(38.95), 2(39.25), 3(39.55), 4(39.85), E2W2, E2	637.60
Section 33:	Lots 1(39.87), 2(39.93), 3(37.97), 4(37.06)	154.83

**Tract No. 12**

**Township 6 North, Range 6 East, S.L.M.**

Section 2:	Lots 1(39.46), 2(39.59), 3(39.71), 4(39.84), S2N2, S2	638.60
Section 12:	All	640.00
Section 14:	All	640.00
Section 22:	All	640.00

**Tract No. 13**

**Township 6 North, Range 6 East, S.L.M.**

Section 24:	All	640.00
Section 26:	All	640.00
Section 28:	N2SE	80.00
Section 32:	All	640.00
Section 34:	N2NE, SENE, W2, SE	600.00

**Tract No. 14**

**Township 6 North, Range 7 East, S.L.M.**

Section 2:	Lots 1(22.77), 2(22.32), 3(21.87), 4(21.42), S2N2, S2	568.38
Section 4:	Lots 1(21.78), 2(26.54), 3(31.40), 4(36.06), S2N2, S2	595.78
Section 6:	Lots 1(40.87), 2(40.62), 3(40.37), 4(43.35), 5(43.06), 6(42.90), 7(42.73), S2NE, SENW, E2SW, SE	653.90
Section 8:	All	640.00

**Tract No. 15**

**Township 6 North, Range 7 East, S.L.M.**

Section 10:	All	640.00
Section 12:	All	640.00
Section 13:	All	640.00
Section 14:	All	640.00

**Tract No. 16**

**Township 6 North, Range 7 East, S.L.M.**

Section 16:	All	640.00
Section 18:	Lots 1(40.11), 2(40.14), 3(40.16), 4(40.19), E2W2, E2	640.60
Section 20:	All	640.00
Section 22:	All	640.00

**Tract No. 17**

**Township 6 North, Range 7 East, S.L.M.**

Section 24:	All	640.00
-------------	-----	--------

**Exhibit "A"**

Attached to Oil and Gas Lease between Property Reserve, Inc. and Palone Petroleum

Section 25:	All of that portion of Section 25 lying North and West of the Union Pacific Railroad Company Right-of-way.	627.00
Section 26:	All	640.00
Section 28:	All	640.00

**Tract No. 18**

**Township 6 North, Range 6 East, S.L.M.**

Section 36:	All	640.00
-------------	-----	--------

**Township 6 North, Range 7 East, S.L.M.**

Section 30:	Lots 1(39.98), 2(40.10), 3(40.22), 4(40.34), E2W2, E2	640.64
Section 32:	All	640.00
Section 34:	All	640.00

**Tract No. 19**

**Township 6 North, Range 8 East, S.L.M.**

Section 4:	Lots 1(30.73), 2(21.10), 3(21.10), 4(21.10), 5(24.67), 6(30.81), 7(36.94)	186.45
Section 6:	Lots 1(29.00), 2(29.00), 3(29.00), 4(29.00), 5(40.00), 6(40.00), 7(40.00), S2NE, SENW, E2SW, SE	596.00
Section 7:	Lots 1(40.17), 2(40.52), 3(40.87), 4(41.22), E2W2, E2	642.78
Section 8:	All	640.00
Section 9:	Lots 1(21.09), 2(21.06), 3(21.03), 4(21.01), W2W2, Less and Except 62.15 acres more or less, as conveyed within that certain Warranty Deed dated February 3, 1999, recorded February 17, 1999 in Book E8 at page 203, with Property Reserve, Inc., a Utah corporation, f/k/a Deseret Title Holding Corporation, as Grantor, and Evanston-Uinta County Airport Joint Powers Board, as Grantee.	182.04

**Tract No. 20**

**Township 6 North, Range 7 East, S.L.M.**

Section 36:	All of that portion of Section 36 lying North and West of the Union Pacific Railroad Company Right-of-way.	375.00
-------------	--	--------

**Township 6 North, Range 8 East, S.L.M.**

Section 16:	All of that portion of Section 16 lying North of the Union Pacific Railroad Company right-of-way.	165.00
Section 17:	All of that portion of Section 17 lying North and West of the Union Pacific Railroad Company right-of-way.	479.00
Section 18:	Lots 1(41.45), 2(41.55), 3(41.65), 4(41.75), E2W2, E2	646.40
Section 19:	All of that portion of Section 19 lying North and West of the Union Pacific Railroad Company right-of-way.	508.00
Section 30:	Lot 1(41.05) and that part of Lot 2 lying North and West of the Union Pacific Railroad Company right-of-way.	65.00

**Tract No. 21**

**Township 5 North, Range 6 East, S.L.M.**

Section 12:	All	640.00
-------------	-----	--------

**Township 5 North, Range 7 East, S.L.M.**

Section 2:	All that part lying North and West of the West Bound Union Pacific Railroad Company right of way	486.32
Section 4:	Lots 1(41.24), 2(41.34), 3(41.42), 4(41.52), S2N2, S2	645.52
Section 6:	Lots 1(41.36), 2(40.98), 3(40.58), 4(40.40), 5(40.40), 6(40.32), 7(40.24), S2NE, SENW, E2SW, SE	644.28
Section 8:	All	640.00
Section 10:	N2NW	80.00
Section 18:	Lots 1(39.97), 2(39.93), 3(39.88), N2NE, SWNE, E2NW, NESW	359.78

**WORKSHEET**  
**APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 02/23/2001

API NO. ASSIGNED: 43-033-30053

WELL NAME: CRANE 6-7

OPERATOR: FAT CHANCE OIL & GAS ( N1395 )

CONTACT: CASEY OSBORN

PHONE NUMBER: 307-673-1500

**PROPOSED LOCATION:**

SENW 07 060N 080E

SURFACE: ~~2125 FNL 1936 FWL~~ 2363 FNL 1970 FWL

BOTTOM: ~~2125 FNL 1936 FWL~~ 2363 FNL 1970 FWL

RICH

WILDCAT ( 1 )

LEASE TYPE: 4-Fee

LEASE NUMBER: FEE

SURFACE OWNER: 4-Fee

PROPOSED FORMATION: KELVN

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	RAM	6/4/01
Geology		
Surface		

**RECEIVED AND/OR REVIEWED:**

☒ Plat  
☒ Bond: Fed[] Ind[] Sta[] Fee[4]  
(No. 885588C )  
☒ Potash (Y/N)  
☒ Oil Shale (Y/N) \*190-5 (B) or 190-3  
☒ Water Permit  
(No. 21-868 )  
☒ RDCC Review (Y/N)  
(Date: Dec 17 2001 Comments) due 3-15-01  
☒ Fee Surf Agreement (Y/N)


**LOCATION AND SITING:**

☐ R649-2-3. Unit \_\_\_\_\_  
☒ ~~R649-3-2. General~~  
Siting: 460 From Qtr/Qtr & 920' Between Wells  
☒ R649-3-3. Exception  
☐ Drilling Unit  
Board Cause No: \_\_\_\_\_  
Eff Date: \_\_\_\_\_  
Siting: \_\_\_\_\_  
☐ R649-3-11. Directional Drill

COMMENTS: Need Presite. (5-25-01)

STIPULATIONS: ① STATEMENT OF BASIS






Utah Oil Gas and Mining

OPERATOR: FAT CHANCE O&G LLC (N1395)

FIELD: WILDCAT (001)

SEC. 6 & 7, T6N, R8E,


COUNTY: RICH SPACING: ~~R649-3-2~~ R649-3-3



PREPARED BY: LCORDOVA  
DATE: 23 FEBRUARY 2001

5-24-01. *lc*

**STATE ACTIONS**  
**State Clearinghouse Coordinator**  
**116 State Capitol, SLC, UT 84114**  
**538-1535**

<b>1. Administering State Agency</b> Oil, Gas and Mining 1594 West North Temple, Suite 1210 Salt Lake City, UT 84114-5801	<b>2. State Application Identifier Number: (assigned by State Clearinghouse)</b>  <b>3. Approximate date project will start:</b> Upon Approval
<b>4. Areawide clearinghouse(s) receiving state action: (to be sent out by agency in block 1)</b>  Bear River Association of Governments	
<b>5. Type of action:</b> / / Lease <input checked="" type="checkbox"/> / Permit    / / License    / / Land Acquisition  / / Land Sale    / / Land Exchange    / / Other _____	
<b>6. Title of proposed action:</b>  Application for Permit to Drill	
<b>7. Description:</b>  Fat Chance Oil and Gas, LLC proposes to drill the Crane 6-7 well (wildcat) on a fee lease, Rich County, Utah. This action is being presented to the RDCC for consideration of resource issues affecting state interests. The Division of Oil, Gas and Mining is the primary administrative agency in this action and must issue approval before operations commence.	
<b>8. Land affected (site location map required) (indicate county)</b>  SE/4, NW/4, Section 7, Township 6 North, Range 8 East, Rich County, Utah	
<b>9. Has the local government(s) been contacted?</b>  No	
<b>10. Possible significant impacts likely to occur:</b>  Degree of impact is based on the discovery of oil or gas in commercial quantities.	
<b>11. Name and phone of district representative from your agency near project site, if applicable:</b>  	
<b>12. For further information, contact:</b>  Lisha Cordova Phone: (801) 538-5296	<b>13. Signature and title of authorized officer</b>    <u>for</u> John R. Baza, Associate Director Date: February 28, 2001

## FORM 3

# APPLICATION FOR PERMIT TO DRILL

**CONFIDENTIAL**

## ATTACHMENTS

RECEIVED  
FEB 23 2001  
DIVISION OF  
OIL, GAS AND MINING


T6N, R8E, S.L.B.&M.

QUANECO, LLC

Well location, CRANE #6-7, located as shown in the SE 1/4 NW 1/4 of Section 7, T6N, R8E, S.L.B.&M., Rich County, Utah.

# BASIS OF ELEVATION

SPOT ELEVATION LOCATED IN THE SW 1/4 OF SECTION 31, T7N, R8E, S.L.B.&M. TAKEN FROM THE MURPHY RIDGE QUADRANGLE, UTAH-WYOMING, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 7184 FEET.



SCALE

# CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR  
REGISTRATION NO. 161319  
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING  
85 SOUTH 200 EAST - VERNAL, UTAH 84078  
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 1-11-01	DATE DRAWN: 1-19-01
PARTY B.B. J.W. D.COX	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE	

Set Stone,  
Steel Post

EAST - 80.00 (G.L.O.)

NORTH - (Basis of Bearings)  
5284.51' - (Measured)

NORTH - (G.L.O.)


U.E.&S.  
1997 Private Alum.  
Cap 0.3' High, Steel  
Post, Scattered Stones  
324872

S89°43'W - 80.70 (G.L.O.)

# LEGEND:

- └─ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

LATITUDE = 41°16'12"  
LONGITUDE = 111°05'04"



# APPLICATION FOR TEMPORARY CHANGE OF WATER

STATE OF UTAH

Rec. by \_\_\_\_\_

Fee Paid \$ \_\_\_\_\_

Receipt # \_\_\_\_\_

Microfilmed \_\_\_\_\_

Roll # \_\_\_\_\_

For the purpose of obtaining permission to make a temporary change of water in the State of Utah, application is hereby made to the State Engineer, based upon the following showing of facts, submitted in accordance with the requirements of Section 73-3-3 Utah Code Annotated 1953, as amended.

CHANGE APPLICATION NUMBER: t25190

WATER RIGHT NUMBER: 21 - 868

\*\*\*\*\*

This Change Application proposes to change the POINT(S) OF DIVERSION, PLACE OF USE, and NATURE OF USE.

\*\*\*\*\*

## 1. OWNERSHIP INFORMATION.

A. NAME: Deseret Livestock Company

INTEREST: 100%

ADDRESS: 531 South State Street, Salt Lake City, UT 84111

B. PRIORITY OF CHANGE: January 16, 2001

FILING DATE: January 16, 2001

C. EVIDENCED BY:

21-868

-----\*

\* DESCRIPTION OF CURRENT WATER RIGHT: \*

-----\*

## 2. SOURCE INFORMATION.

A. QUANTITY OF WATER: 12.0 cfs

B. SOURCE: Unnamed Tributary to Duck Creek

COUNTY: Summit

C. POINT OF DIVERSION -- SURFACE:

(1) N 1290 feet E 300 feet from W $\frac{1}{4}$  corner, Section 12, T 6N, R 7E, SLBM

## 3. STORAGE. Water is diverted for storage into:

(1) Crane Reservoir, from Jan 1 to Dec 31.

CAPACITY: 775.700 ac-ft.

Area inundated includes all or part of the following legal subdivisions:

BASE TOWN	RANG	SEC	NORTH-WEST $\frac{1}{4}$				NORTH-EAST $\frac{1}{4}$				SOUTH-WEST $\frac{1}{4}$				SOUTH-EAST $\frac{1}{4}$			
			NW	NE	SW	SE	NW	NE	SW	SE	NW	NE	SW	SE	NW	NE	SW	SE
SL	6N	7E	10				***			X	***				***			
			11	X	X	X	***	X	X	X	***				***			
			12	X		X	***				***				***			

Temporary Change




## 8. PLACE OF USE. Changed as Follows:

(Which includes all or part of the following legal subdivisions:)

BASE TOWN	RANG	SEC	NORTH-WEST¼					NORTH-EAST¼					SOUTH-WEST¼					SOUTH-EAST¼				
			NW	NE	SW	SE		NW	NE	SW	SE		NW	NE	SW	SE		NW	NE	SW	SE	
SL	6N	8E	4	X	X	X	X	***	X	X	X	X	***	X	X	X	X	***	X	X	X	X
			6	X	X	X	X	***	X	X	X	X	***	X	X	X	X	***	X	X	X	X
			7	X	X	X	X	***	X	X	X	X	***	X	X	X	X	***	X	X	X	X
			8	X	X	X	X	***	X	X	X	X	***	X	X	X	X	***	X	X	X	X
SL	7N	7E	11	X	X	X	X	***	X	X	X	X	***	X	X	X	X	***	X	X	X	X
SL	7N	8E	21	X	X	X	X	***	X	X	X	X	***	X	X	X	X	***	X	X	X	X
			29	X	X	X	X	***	X	X	X	X	***	X	X	X	X	***	X	X	X	X
			33	X	X	X	X	***	X	X	X	X	***	X	X	X	X	***	X	X	X	X
SL	8N	7E	32	X	X	X	X	***	X	X	X	X	***	X	X	X	X	***	X	X	X	X
			35	X	X	X	X	***	X	X	X	X	***	X	X	X	X	***	X	X	X	X

## 9. SIGNATURE OF APPLICANT(S).

The undersigned hereby acknowledges that even though he/she/they may have been assisted in the preparation of the above-numbered application, through the courtesy of the employees of the Division of Water Rights, all responsibility for the accuracy of the information contained herein, at the time of filing, rests with the applicant(s).

  
Signature of Applicant(s)

Sign & return w/  
\$75.00 fee

DIVISION OF WATER RIGHTS  
1780 N. RESEARCH PARKWAY  
SUITE 104  
NORTH LOGAN, UTAH 84341-1941

**From:** Frances Bernards  
**To:** Cordova, Lisha  
**Date:** 3/27/01 12:01PM  
**Subject:** comments on well drilling projects

The following Resource Development Coordinating Committee agenda items for proposed well drilling projects may require a permit from the Utah Division of Air Quality (see comment below): Items #518 (Texaco 05-107 well on state lease ML-48193); #519 (Texaco 05-108 well); #520 (Texaco 05-109 well); #521 (Texaco 05-110 well); #522 (Texaco 06-103 well); #523 (America West Group 15-1126 well); #524 (W.H. Leonard 15-127 well); #539 (Fat Chance Oil & Gas Crane 6-7 well); #540 (Fat Chance Oil & Gas Crane 13-6 well); #541 (Fat Chance Oil & Gas Crane 13-18 well); #542 (Fat Chance Oil & Gas Stacey Hollow 14-35 well).

The following comment applies to all proposed projects: The proposed oil well drilling projects may require a permit, known as an Approval Order, from the Division of Air Quality. If any compressor stations are located at the site, an Approval Order from the DAQ will be required for operation of the equipment. A permit application, known as a Notice of Intent (NOI) should be submitted to the Division of Air Quality for review.

If you have any questions, please contact me at (801) 536-4056.

Frances Bernards, Planner  
Division of Air Quality  
[fbernard@deq.state.ut.us](mailto:fbernard@deq.state.ut.us)

The State Planning Coordinator's Office has reviewed the following projects and has not received any comments from State agencies to date.

Contact: Kevin Carter

#484 Trust Lands Administration - Easement No. 677

Contact: Jan Parmenter

#483 Trust Lands Administration - Easement No. 683

Contact: Scott Chamberlain

#544 Trust Lands Administration - Fire Rehabilitation/Range Improvement Project

Contact: Lisha Cordova

#539 DOGM - Application for Permit to Drill - proposal to drill a wildcat well, Crane 6-7 on a fee lease.

#540 DOGM - Application for Permit to Drill - proposal to drill a wildcat well, Crane 13-6 on a fee lease.

#541 DOGM - Application for Permit to Drill - proposal to drill a wildcat well, Crane 13-18 on a fee lease.

#542 DOGM - Application for Permit to Drill - proposal to drill a wildcat well, Stacey Hollow 14-35 on a fee lease.

PLOT OF AN AREA WITH A RADIUS OF 5280 FEET FROM A POINT  
S 2125 FEET, E 1936 FEET OF THE NW CORNER,  
SECTION 7 TOWNSHIP 6N RANGE 8E SL BASE AND MERIDIAN

PLOT SCALE IS APPROXIMATELY 1 INCH = 2000 FEET

\* \* \* \* \*

\* \* \* \* \*

\* \* \* \* \*

\* \* \* \*

\* \* \*

\* \*

\* \* \*

\* \* \*

\* \*

\* \* \*

\* \* \*

\* \*

\* \* \*

\*

\*

\*

\*

\*

\*

\*

\*

1

3

2

0

1


2

5

4

6

\*



UTAH DIVISION OF WATER RIGHTS  
NWPLAT POINT OF DIVERSION LOCATION PROGRAM

MAP CHAR	WATER RIGHT	QUANTITY CFS	AND/OR AC-FT	SOURCE DESCRIPTION or WELL INFO DIAMETER DEPTH YEAR LOG	POINT OF DIVERSION DESCRIPTION NORTH EAST CNR SEC TWN RNG B&M
0	21 901	.5000	.00	Unnamed Tributary to Duck Cree S	1520 E 470 NW 7 6N 8E SL
				WATER USE(S): IRRIGATION STOCKWATERING	PRIORITY DATE: 00/00/19
				Deseret Livestock Company	Salt Lake City
1	21 900	.5000	.00	Unnamed Tributary to Duck Cree N	680 E 570 W4 7 6N 8E SL
				WATER USE(S): IRRIGATION STOCKWATERING	PRIORITY DATE: 00/00/19
				Deseret Livestock Company	Salt Lake City
2	21 902	.0560	.00	Crane Ranch House Spring N	70 E 825 W4 7 6N 8E SL
				WATER USE(S): DOMESTIC STOCKWATERING	PRIORITY DATE: 00/00/19
				Deseret Livestock Company	Salt Lake City
3	21 870	.2500	.00	Unnamed Tributary to Duck Cree N	20 W 2560 E4 12 6N 7E SL
				WATER USE(S): IRRIGATION STOCKWATERING	PRIORITY DATE: 00/00/19
				Deseret Livestock Company	Salt Lake City



5/23/01 11:01 AM

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☒  
(highlight changes)

APPLICATION FOR PERMIT TO DRILL				5. LEASE DESIGNATION AND SERIAL NUMBER: Fee	
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>				6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>				7. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: Fat Chance Oil & Gas, LLC				8. WELL NAME and NUMBER: Crane 6-7	
3. ADDRESS OF OPERATOR: PO Box 7370 CITY Sheridan STATE WY ZIP 82801			PHONE NUMBER: (307) 673-1500		9. FIELD AND POOL, OR WILDCAT: Wildcat
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 2363' FNL 1970' FWL AT PROPOSED PRODUCING ZONE: same				10. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SE NW Sec. 7 T6N R8E	
13. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 5 miles west of Evanston, Wyoming				11. COUNTY: Rich	12. STATE: UTAH
14. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 3077'		15. NUMBER OF ACRES IN LEASE: 52,395		16. NUMBER OF ACRES ASSIGNED TO THIS WELL: 160	
17. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 3279'		18. PROPOSED DEPTH: 5,000		19. BOND DESCRIPTION: Utah DOGM Surety# 885588C	
20. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 6802' GR		21. APPROXIMATE DATE WORK WILL START: 6/15/2001		22. ESTIMATED DURATION: 10 days	

CONFIDENTIAL

4568437N  
492921E

23. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
12 1/4" (6)	9 5/8"	H-40	32.3#	500	G-Poz	250 sx	1.77 12.5# lead
						50 sx	1.17 15.8" tail
8 3/4" (9)	7"	K-55	20#	5,000	G-35/65 Poz	150 sx	2.34 11# lead
						50 sx	1.27 14.2# tail

24. ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- |  |  |
|--|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | <input type="checkbox"/> COMPLETE DRILLING PLAN  |
| <input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER        | <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

NAME (PLEASE PRINT) Lorna James

TITLE Administrative Assistant

SIGNATURE

*Lorna James*

DATE

5-24-01

(This space for State use only)

API NUMBER ASSIGNED:

43-033-30053

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date:

(See Instructions on Reverse Side)

By:

*[Signature]*

RECEIVED


MAY 25 2001

DIVISION OF  
OIL, GAS AND MINING

T6N, R8E, S.L.B.&M.


QUANECO, LLC

Well location, CRANE #6-7, located as shown in the SE 1/4 NW 1/4 of Section 7, T6N, R8E, S.L.B.&M., Rich County, Utah.



### BASIS OF ELEVATION

SPOT ELEVATION LOCATED IN THE SW 1/4 OF SECTION 31, T7N, R8E, S.L.B.&M. TAKEN FROM THE MURPHY RIDGE QUADRANGLE, UTAH-WYOMING, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 7184 FEET.



### CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

*Robert L. Cox*  
 REGISTERED LAND SURVEYOR  
 REGISTRATION NO. 161319  
 STATE OF UTAH

REVISED: 5-22-01 D.COX

UINTAH ENGINEERING & LAND SURVEYING  
 85 SOUTH 200 EAST - VERNAL, UTAH 84078  
 (435) 789-1017

U.E.&S.  
 1997 Private Alum.  
 Cap 0.3' High, Steel  
 Post, Scattered Stones  
 324872

### LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

LATITUDE = 41°16'09"  
 LONGITUDE = 111°05'04"

SCALE 1" = 1000'	DATE SURVEYED: 1-11-01	DATE DRAWN: 1-19-01
PARTY B.B. J.W. D.COX	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE QUANECO, LLC	

**Fat Chance Oil and Gas, LLC.**

P.O. Box 7370  
850 Val Vista  
Sheridan WY 82801  
307-673-1500 Phone  
307-673-1400 Fax

May 23, 2001

State of Utah  
Department of Natural Resources  
Division of Oil, Gas and Mining  
ATTN: Lisha Cordova  
Box 145801  
Salt Lake City UT 84114-5801

To Whom It May Concern:

The original location of our Crane 6-7 well was not acceptable due to topography. Therefore, we had the site re-surveyed. Per a phone conversation with Bill Courtney on May 23, 2001, we were instructed to complete an amended APD and submit it with a copy of the new survey and a letter of explanation. We understand that if this is an exception location, we will have to forward a letter regarding our lease. The amended APD and survey are enclosed.

If additional information is needed, please contact me at 307-673-1500.

Thank you for your time and consideration in this matter.

Sincerely,



Lorna K. James  
Administrative Assistant

**RECEIVED**

**MAY 25 2001**

**DIVISION OF  
OIL, GAS AND MINING**

# **DRILLING PLAN**

Operator: Fat Chance Oil and Gas, LLC  
Crane 6-7  
T6N R8E, Rich County, Utah

---

## **1. ESTIMATED TOPS OF GEOLOGIC MARKERS**

<u>Formation</u>	<u>Depth</u>	<u>Fluid</u>
Wasatch	Surface – 100'	Potential water sands
Fowkes	100' – 1200'	None
Adaville	1200' – 2500'	Water, Possible Gas
Frontier	2500' – 3500'	Water, Possible Gas
Aspen	3500' – 4000'	None
Bear River	4000' – 4500'	Water, Oil
TD	4500'	

## **2. ESTIMATED DEPTHS OF ANTICIPATED WATER AND GAS FORMATIONS**

The objective formation is the Kelvin formation. Operator intends to evaluate shows in the Adaville, Frontier and Bear River intervals. The anticipated tops are listed in section one of the drilling plan.

## **3. PRESSURE CONTROL EQUIPMENT**

### **Minimum Specifications:**

1. 11" 3M BOP stack consisting of an annular preventer, pipe ram, and blind ram.
2. 2M choke manifold consisting of two adjustable chokes and bleed line.
3. 2" Kill Line
4. 2" Choke Line

---

All components of the BOP stack are to be installed and pressure tested before drilling out from under the 9 5/8" surface casing. Rams, manifold and lines are to be tested to both a low pressure of 250 psi and a high pressure equal to the working pressure rating. The annular preventer is to be tested to 70% of the working pressure.

An adequate accumulator system will be utilized to hydraulically operate all components of the BOP equipment.

The surface casing will be pressure tested to 1000 psi.

## **DRILLING PLAN**

Operator: Fat Chance Oil and Gas, LLC

Crane 6-7

T6N R8E, Rich County, Utah

---

The BOP equipment will be tested once every 30 days and whenever a pressure seal is broken.

Operator will adhere to Utah Oil and Gas Conservation General Rule R649-3-7(Well Control).

### **4. CASING PROGRAM**

#### Surface:

OD: 9 5/8"  
Grade: H-40 or greater  
Wt: 32.30# or greater  
Cement: Cemented to surface with Lite and Tail Cements as required. Centralizers will be utilized to assure proper cement placement.

#### Production:

OD: 7"  
Grade: J-55 or greater  
Wt: 23# or greater  
Cement: Cemented to cover and isolate all zones of interest with Lite and Tail cements as required. Centralizers will be utilized to assure proper cement placement.

Surface casing will be cemented to surface, thus protecting shallow aquifers and the associated water. All zones of interest will be identified and evaluated. After running production casing, cement will be displaced to cover the shallowest zone of interest. As necessary, stages tools will be utilized if hydrostatic heads are excessive. The casing program will consist of setting 9 5/8" surface casing and 7" production casing.

### **5. DRILLING FLUID PROGRAM**

The drilling fluid will be a lightly treated fresh water native mud. Hole conditions will dictate if additives such as chemicals, gel or weighting materials are added. It is anticipated that occasional gel with LCM and/or polymer sweeps will be required to adequately clean the hole. Mud weight will be maintained at 9.5#/gal or less. Adequate quantities of barite to raise the mud weight to 10.5#/gal will be stored and available on location before drilling out the surface casing cement plug.

Mud pits will be visually monitored. The hole will be filled during trips and kept full at all times unless lost circulation is encountered.

## **DRILLING PLAN**

Operator: Fat Chance Oil and Gas, LLC  
Crane 6-7  
T6N R8E, Rich County, Utah

---

### **6. EVALUATION PROGRAM**

#### **Coring:**

Due to the wildcat status of the proposed well, coring is not anticipated.

#### **Logging:**

One-man logging unit during drilling.

Open hole FDC-CNL-GR logs will be run from TD to surface.

### **7. ABNORMAL PRESSURES OR TEMPERATURES**

No abnormal pressures or temperatures are expected. Maximum anticipated bottom hole pressure is 1950 psi or less. The pressure gradient at any depth is expected to be .43 psi/ft or less.

Hydrogen sulfide gas is produced from deeper formations in wells located within close proximity of the proposed well. However, the objective of the proposed well is the Kelvin formation from which no hydrogen sulfide has been encountered nor in any formations above the Kelvin. The presence of hydrogen sulfide in the proposed well is not expected or anticipated.

### **8. ADDITIONAL INFORMATION**

Anticipated spud of the proposed well will be immediately or as soon as practical after State approval.

Fat Chance Oil and Gas, LLC intends to test and evaluate any zone that indicates potential. The testing technique will consist of selectively perforating and flowing each zone of interest. Bridge plugs will be utilized to isolate zones as necessary for independent zone testing. Testing will be accordance with Utah Oil and Gas rule R649-3-19(Well Testing) and results will be submitted in writing to the Division of Oil, Gas and Mining.

## **LIST OF CONTACTS**

### **OPERATOR:**

Casey Osborn  
Operations Manager  
Box 7370  
Sheridan, Wyoming 82801  
Office: 307-673-1500  
Home: 307-673-0842

### **SURFACE LESSEE:**

Bill Hopkin  
Ranch Manager  
Deseret Land and Livestock  
125 Main Ranch Way  
Woodruff, Utah 84086  
Office: 435-793-4288  
Home: 435-793-4558



# QUANECO, LLC.

## CRANE #6-7

LOCATED IN RICH COUNTY, UTAH  
SECTION 7, T6N, R8E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: SOUTHWESTERLY



PHOTO: EXISTING ACCESS AT EDGE OF PAD

CAMERA ANGLE: SOUTHWESTERLY



- Since 1964 -

**U E L S** Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS


1 18 01  
MONTH DAY YEAR

PHOTO

TAKEN BY: C.T.



DRAWN BY: K.G.

REVISED: 5-22-01



# QUANECO, LLC. LOCATION LAYOUT FOR

CRANE #6-7  
 SECTION 7, T6N, R8E, S.L.B.&M.  
 2363' FNL 1970' FWL



Elev. Ungraded Ground at Location Stake = 6802.3'  
 Elev. Graded Ground at Location Stake = 6801.7'

UINTAH ENGINEERING & LAND SURVEYING  
 85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017


# QUANECO, LLC.

## TYPICAL CROSS SECTIONS FOR







CRANE #6-7

SECTION 7, T6N, R8E, S.L.B.&M.

2363' FNL 1970' FWL



DATE: 5-22-01  
Drawn By: D.COX



### NOTE:


Topsoil should not be Stripped Below Finished Grade on Substructure Area.

### APPROXIMATE YARDAGES

(6") Topsoil Stripping	=	750 Cu. Yds.
Remaining Location	=	3,840 Cu. Yds.
<b>TOTAL CUT</b>	<b>=</b>	<b>4,590 CU.YDS.</b>
<b>FILL</b>	<b>=</b>	<b>1,660 CU.YDS.</b>

EXCESS MATERIAL AFTER 5% COMPACTION	=	2,840 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	=	1,080 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	=	1,760 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017



# **LEGEND:**

○ PROPOSED LOCATION

MAY 25 2001

**QUANECO, LLC.**

**CRANE #6-7**

**SECTION 7, T6N, R8E, S.L.B.&M.**

**2363' FNL 1970' FWL**



**Utah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813


**TOPOGRAPHIC**  
**MAP**

**1 18 01**  
MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: K.G. REVISED: 5-22-01







# **LEGEND:**

--- PROPOSED ACCESS ROAD  
--- EXISTING ROAD



**QUANECO, LLC.**

**CRANE #6-7**  
**SECTION 7, T6N, R8E, S.L.B.&M.**  
**2363' FNL 1970' FWL**



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813

**TOPOGRAPHIC**  
**MAP**

**1** **18** **01**  
 MONTH DAY YEAR


SCALE: 1" = 2000' DRAWN BY: K.G. REVISED: 5-22-01






# BOPE SCHEMATIC

API 3M - 11 - SRRA





# KILL LINE – CHOKE LINE/MANIFOLD SCHEMATIC



THREADED CONNECTIONS OPTIONAL FOR 2M RATED WORKING PRESSURE SERVICE

FIGURE K5-1. Typical kill line assembly for 2M and 3M rated working pressure service - surface installation.




FIGURE K4-1. Typical choke manifold assembly for 2M and 3M rated working pressure service - surface installation.

**DIVISION OF OIL, GAS AND MINING**  
**APPLICATION FOR PERMIT TO DRILL**  
**STATEMENT OF BASIS**

OPERATOR: Fat Chance Oil and Gas, LLC

WELL NAME & NUMBER: Crane #6-7

API NUMBER: 43-033-30053

LEASE: Fee (Deseret Land and Livestock) FIELD/UNIT: Wildcat

LOCATION: 1/4, 1/4 SE NW Sec 7 TWP: 6 N RNG: 8 E 2363 FNL 1970 FWL

LEGAL WELL SITING: 460' from the drilling unit boundary and 920' from other wells

GPS COORD (UTM): X = 492,923 E; Y = 4,568,465 N Calculated

SURFACE OWNER: Deseret Land and Livestock

**Geology/Ground Water:**

It is expected that fresh water aquifers containing significant volumes of high quality ground water will be penetrated. A moderately permeable soil is developed on the Tertiary clays of the Wasatch formation. There are 14 active water rights within a mile of this location, Crane Creek is an active water source is within a mile of location. The proposed casing and cementing programs should adequately isolate any zones of fresh water that may be penetrated but the operator must extend the surface casing setting depth as needed to completely contain the USDW's encountered and place cement across all fresh water zones. If the well is plugged and abandoned any zone of fresh water will be protected with cement and cement will be circulated to ground level on the surface casing string. As this location is adjacent to an active water drainage and extra care will be taken to protect any ground or surface water sources.

Reviewer: K. Michael Hebertson

Date: 25-May-2001

**Surface:**

The surface belongs to Deseret Land and Livestock and persons representing Deseret Land and Livestock were invited to the on-site inspection. Those attending the onsite are noted above in the Participants section of the review document. Items of concern at this location are surface use agreement, and winter drilling restrictions not yet specified by the surface owner.

Reviewer: K. Michael Hebertson

Date: 25-May-2001

**Conditions of Approval/Application for Permit to Drill:**

1. A synthetic liner with a minimum thickness of 12 mils shall be properly installed and maintained in the reserve pit.
2. Berms and diversions shall be installed to protect the location and spoil piles.
3. Topsoil and spoil will be placed in low berms rather than tall piles.

# **N-SITE PREDRILL EVALUATION**

## **Division of Oil, Gas and Mining**

OPERATOR: Fat Chance Oil and Gas, LLC

WELL NAME & NUMBER: Crane #6-7

API NUMBER: 43-033-30053

LEASE: Fee (Deseret Land and Livestock) FIELD/UNIT: Wildcat

LOCATION: 1/4, 1/4 SE NW Sec 7 TWP: 6 N RNG: 8 E 2363 FNL 1970 FWL

LEGAL WELL SITING: 460' from the drilling unit boundary and 920' from other wells

GPS COORD (UTM): X = 492,923 E; Y = 4,568,465 N Calculated

SURFACE OWNER: Deseret Land and Livestock

### **PARTICIPANTS**

Mike Hebertson (DOGM), Casey Osborn (Fat Chance), Bill Hopkin (Deseret Land & Livestock)

### **REGIONAL/LOCAL SETTING & TOPOGRAPHY**

This area is located in the Overthrust Belt of eastern Utah and western Wyoming north of the Uinta Mountains. US Highway 80 is about 1.5 miles to the southeast. The Uinta County Wyoming, Airport is located about 1 mile east. Thomas Canyon is the access route to the location, and is also an active drainage with several developed water resources. Crane Creek, which flows eastward out of Thomas Canyon, is active all year long and eventually flows into the Bear River. The City of Evanston is about 5.8 miles to the east. The surface is Paleocene/Eocene age Wasatch formation with possible Evanston formation underlying the area. The land slopes to the southwest and is incised by moderate to shallow drainages with active streams and flowing water.

### **SURFACE USE PLAN**

CURRENT SURFACE USE: Grazing and wildlife habitat.

PROPOSED SURFACE DISTURBANCE: The operator proposes a 270' X 180' pad, outboard soil storage, and a 50' X 70' X 8' outboard attached pit, no new or upgraded road will be required.

LOCATION OF EXISTING WELLS WITHIN A 1-MILE RADIUS: There are no existing wells within 1 mile of this well.

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: All production facilities for this well will remain on the location with exception of the pipelines and utilities for power. The pipeline and utility lines will be buried underground and follow the access road.

SOURCE OF CONSTRUCTION MATERIAL: Gravel location and approach road; soil stored in berm, the location will be made of natural material borrowed from leveling the pad during construction.

ANCILLARY FACILITIES: None

### **WASTE MANAGEMENT PLAN:**

Portable toilets; garbage cans or cages on location will be placed on location and will be emptied into

centralized dumpsters, which will be emptied into an approved land. All human waste generated at the site will be kept in proper sanitary facilities and disposed of according to local rules. Extra precautions will be taken due to the proximity of Thomas Canyon and the water resources that are present along the drainage.

## ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: This location is in a secondary drainage to Thomas Canyon and Crane Creek, there is a stock watering pond developed in the mouth of the drainage, and an active spring within  $\frac{3}{4}$  of a mile of this location. All precautions will be taken to insure the integrity of these resources.

FLORA/FAUNA: Open sagebrush, and grass meadows, cactus, birds, lizards, coyotes, rodents, raptors, occasional elk, deer pronghorn and sage grouse.

SOIL TYPE AND CHARACTERISTICS: Mostly clay with very little sand, lots of small rocks to larger pit run type gravel and head sized rocks.

SURFACE FORMATION & CHARACTERISTICS: Wasatch Formation Clay with numerous rocks light gray to medium brown in color. Minor sand, and topsoil. Moderate to Poor Permeability.

EROSION/SEDIMENTATION/STABILITY: Stable. Wasatch type soils are generally susceptible to slumping when slopes are wet and become saturated. The slope of the ground in this location will not be sufficient for the unstable conditions to occur. Erosion and sedimentation at this location will not be an issue.

PALEONTOLOGICAL POTENTIAL: None observed.

## RESERVE PIT

CHARACTERISTICS: Dugout, earthen pit, as above.

LINER REQUIREMENTS (Site Ranking Form attached): Synthetic liner is required.

## SURFACE RESTORATION/RECLAMATION PLAN

A surface use agreement is in place, and restoration will be managed by the surface owner.

SURFACE AGREEMENT: There is a surface use agreement.

CULTURAL RESOURCES/ARCHAEOLOGY: Archaeological survey not required.

## OTHER OBSERVATIONS/COMMENTS:

This area was burned and revegetated by the surface owner two years ago. Discussion was had concerning the establishment of new grass for the livestock using this area during the year, as this is the pasture used by the ranch to wean their animals in the fall.

## ATTACHMENTS:

Photographs of the new location were taken.

K. Michael Hebertson  
DOGM REPRESENTATIVE

25-May-2001 11:00 AM  
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score  
For Reserve and Onsite Pit Liner Requirements**

<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>10</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	<u>15</u>
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	20	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>0</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>10</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	10	
TDS >10000 or Oil Based Mud	15	
Fluid containing significant levels of hazardous constituents	20	<u>10</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>0</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>10</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>0</u>
Presence of Nearby Utility Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>0</u>

**Final Score**    60    (Level I Sensitivity)

Sensitivity Level I = 20 or more; total containment is required.

Sensitivity Level II = 15-19; lining is discretionary.

Sensitivity Level III = below 15; no specific lining is required.





**Fat Chance Oil & Gas, Crane #6-7, Sec. 6, T6N, R8E, Rich County, API 43-033-30053**

Well name:

**06-01 Fat Chance Crane 6-7**Operator: **Fat Chance Oil**String type: **Production**

Project ID:

43-033-30053

Location: **Rich Co.****Design parameters:****Collapse**Mud weight: 9.500 ppg  
Design is based on evacuated pipe.**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 135 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 368 ft

Cement top: 3,258 ft

**Burst**Max anticipated surface  
pressure: 0 psi  
Internal gradient: 0.494 psi/ft  
Calculated BHP 2,467 psi

No backup mud specified.

**Tension:**8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Non-directional string.

Tension is based on air weight.

Neutral point: 4,286 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	5000	7	<u>23.00</u>	J-55	ST&C	5000	5000	6.25	231.1
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	2467	3270	<u>1.33</u>	2467	4360	<u>1.77</u>	115	284	<u>2.47 J</u>

Prepared R.A.McKee  
by: Utah Dept. of Natural ResourcesDate: June 4,2001  
Salt Lake City, Utah**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop &amp; Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 5000 ft, a mud weight of 9.5 ppg The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*



Well name:

**06-01 Fat Chance Crane 6-7**Operator: **Fat Chance Oil**String type: **Surface**

Project ID:

43-033-30053

Location: **Rich Co.****Design parameters:****Collapse**

Mud weight: 9.000 ppg

Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No

Surface temperature: 65 °F

Bottom hole temperature: 72 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 200 ft

Cement top: Surface

**Burst**

Max anticipated surface pressure: 0 psi

Internal gradient: 0.494 psi/ft

Calculated BHP 247 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

Tension is based on air weight.

Neutral point: 434 ft

Non-directional string.

**Re subsequent strings:**

Next setting depth: 5,000 ft

Next mud weight: 9.500 ppg

Next setting BHP: 2,468 psi

Fracture mud wt: 19.250 ppg

Fracture depth: 500 ft

Injection pressure 500 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	500	9.625	32.30	H-40	ST&C	500	500	8.876	31.7
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	234	1370	<u>5.86</u>	247	2270	<u>9.20</u>	16	254	<u>15.73 J</u>

Prepared R.A.McKee  
by: Utah Dept. of Natural Resources

Date: June 4, 2001  
Salt Lake City, Utah

**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop &amp; Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 500 ft, a mud weight of 9 ppg. The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

# 06-01 Fat Chance Crane 6

## Casing Schematic

Surface

TOC @  
0.

~ w/ 25% Wash-Out

Surface  
500. MD

9-5/8"  
MW 9.  
Frac 19.3

BOP

$$.052 (9.5) 5000 = 2470$$

$$.12 (5000) = \langle 600 \rangle$$

1870psi

∴ 3M-SRRA BOP

ADEQUATE R<sub>tm</sub>

6/4/01

TOC @  
3258.

~ w/ 10% Wash-Out

Production  
5000. MD

7"  
MW 9.5

# QUANECO, LLC

June 5, 2001

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

## RE: Crane 6-7 – Exception Location

Attention:

The Crane 6-7 was originally staked and surveyed in a location that required excessive cut and surface disturbance as well as road relocation. Therefore, an alternate location was selected. The alternate site was surveyed and the center stake was moved approximately 238' south and 34' west. The alternate location remains within the SE  $\frac{1}{4}$  NW  $\frac{1}{4}$  of Section 7, but is within 460' of the south boundary of the SE  $\frac{1}{4}$  NW  $\frac{1}{4}$ . Therefore, the alternate location is now an exception location.

Fat Chance Oil and Gas, LLC is the lessee of the minerals surrounding this 40-acre  $\frac{1}{4}$   $\frac{1}{4}$  section (SE  $\frac{1}{4}$  NW  $\frac{1}{4}$  Section 7, T6N, R8E) including the 40-acre  $\frac{1}{4}$   $\frac{1}{4}$  section directly to the south (NE SW Section 7, T6N, R8E). An amended APD and survey were submitted to your office May 24, 2001 reflecting the changes. Fat Chance Oil and Gas, LLC requests that the aforementioned amended APD be approved based upon the submitted alternate survey.

Thank you for your prompt attention and cooperation.

Sincerely,

*Casey Osborn*  
Casey Osborn  
Operations Manager

*by Rona James*  
*Admin. Asst.*

**RECEIVED**

JUN 11 2001

DIVISION OF  
OIL, GAS AND MINING



# State of Utah

DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt  
Governor

Kathleen Clarke  
Executive Director

Lowell P. Braxton  
Division Director

1594 West North Temple, Suite 1210

PO Box 145801

Salt Lake City, Utah 84114-5801

801-538-5340

801-359-3940 (Fax)

801-538-7223 (TDD)

June 13, 2001

Fat Chance Oil & Gas, LLC  
PO Box 7370  
Sheridan WY 82801

Re: Crane 6-7 Well, 2363' FNL, 1970' FWL, SE NW, Sec. 7, T. 6 North, R. 8 East,  
Rich County, Utah


Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-033-30053.

Sincerely,

  
John R. Baza  
Associate Director

er

Enclosures

cc: Rich County Assessor

**Operator:** Fat Chance Oil & Gas, LLC  
**Well Name & Number** Crane 6-7  
**API Number:** 43-033-30053  
**Lease:** Fee  
**Location:** SE NW **Sec.** 7 **T.** 6 North **R.** 8 East

### Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

5. Operator shall comply with applicable recommendations resulting from Resource Development Coordinating Committee review. Statements attached.

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL  
FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
2. NAME OF OPERATOR: Fat Chance Oil & Gas, LLC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: PO Box 7370 CITY Sheridan STATE WY ZIP 82801		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (307) 673-1500		8. WELL NAME and NUMBER: Crane 6-7
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2363' FNL 1970' FWL		9. API NUMBER: 4303330053
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 7 6N 8E S		10. FIELD AND POOL, OR WILDCAT: Wildcat
COUNTY: Rich		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Extension of Permit
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Operator requests a one year extension of approval for permit to drill to allow further evaluation of offset wells.

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 05-20-02

By: [Signature]

COPY SENT TO OPERATOR

Date: 5-20-02  
Initials: CHD

NAME (PLEASE PRINT) Lorna James TITLE Administrative Assistant  
SIGNATURE [Signature] DATE 5/13/2002

(This space for State use only)

RECEIVED

MAY 16 2002

DIVISION OF  
OIL, GAS AND MINING

RECEIVED

MAY 16 2002

DIVISION OF  
OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
2. NAME OF OPERATOR: Fat Chance Oil & Gas, LLC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: PO Box 7370 CITY Sheridan STATE WY ZIP 82801		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2363' FNL 1970' FWL COUNTY: Rich		8. WELL NAME and NUMBER: Crane 6-7
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 7 T6N R8E S STATE: UTAH		9. API NUMBER: 4303330053
PHONE NUMBER: (307) 673-1500		10. FIELD AND POOL, OR WILDCAT: Wildcat

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: APD Extension
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Operator requests a one year extension of APD.

Approved by the  
Utah Division of  
Oil, Gas and Mining  
Date: 07-03-03  
By: *[Signature]*

COPY SENT TO OPERATOR  
Date: 7-8-03  
Initials: LAD

NAME (PLEASE PRINT) Lorna James	TITLE Administrative Assistant
SIGNATURE <i>Lorna James</i>	DATE 6/25/2003

(This space for State use only)

RECEIVED  
JUL 02 2003  
DIV. OF OIL, GAS & MINING



**Application for Permit to Drill  
Request for Permit Extension  
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

**API:** 4303330053  
**Well Name:** Crane 6-7  
**Location:** SENW, Section 7, T6N, R8E, SLM, Rich County  
**Company Permit Issued to:** Fat Chance Oil & Gas, LLC  
**Date Original Permit Issued:** 6/13/2001

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒


Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐

  
Signature

6/25/2003

Date

Title: Administrative Assistant

Representing: Fat Chance Oil & Gas, LLC

**RECEIVED**  
**JUL 02 2003**  
DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
2. NAME OF OPERATOR: Fat Chance Oil & Gas, LLC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: PO Box 7370 CITY Sheridan STATE WY ZIP 82801		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (307) 673-1500		8. WELL NAME and NUMBER: Crane 6-7
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2363' FNL 1970' FWL		9. API NUMBER: 4303330053
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 7 T6N R8E S		10. FIELD AND POOL, OR WILDCAT: Wildcat
COUNTY: Rich		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


Please change the Operator to:

Quaneco, LLC  
PO Box 7370  
Sheridan WY 82801

Effective: July 19, 2003  
Bond# 885588C

  
Fat Chance Oil & Gas, LLC  
Casey Osborn

  
Quaneco, LLC  
Casey Osborn

NAME (PLEASE PRINT) Lorna James	TITLE Administrative Assistant
SIGNATURE 	DATE 8/13/2003

(This space for State use only)

RECEIVED  
AUG 25 2003  
DIV. OF OIL, GAS & MINING

## OPERATOR CHANGE WORKSHEET

## ROUTING

1. GLH

2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

**X Operator Name Change**

Merger

The operator of the well(s) listed below has changed, effective:

**7/19/2003**

FROM: (Old Operator):	TO: ( New Operator):
N1395 - Fat Chance Oil & Gas, LLC PO Box 7370 Sheridan, WY 82801 Phone: 1-(307) 673-1500	N2495 - Quaneco, LLC PO Box 7370 Sheridan, WY 82801 Phone: 1-(307) 673-1500

CA No.

Unit:

## WELL(S)

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS	
COALVILLE 9-3	03	020N	050E	4304330322		Fee	GW	APD	C
COALVILLE 12-3	03	020N	050E	4304330323		Fee	GW	APD	C
SUTTONS 4-12	12	060N	070E	4303330058	13286	Fee	GW	S	C
CRANE 4-4	04	060N	080E	4303330049	13056	Fee	GW	S	C
CRANE 12-4	04	060N	080E	4303330050	13057	Fee	GW	S	C
CRANE 13-6	06	060N	080E	4303330054		Fee	GW	APD	C
CRANE 6-7	07	060N	080E	4303330053		Fee	GW	APD	C
CRANE 13-8	08	060N	080E	4303330052	13093	Fee	GW	S	C
CRANE 13-18	18	060N	080E	4303330055		Fee	GW	APD	C
STACEY HOLLOW 14-35	35	070N	070E	4303330056	13104	Fee	GW	S	C
SIMS 13-33	33	070N	080E	4303330051		Fee	GW	APD	C
NEPONSET 4-35	35	080N	070E	4303330048		Fee	GW	APD	C
MURPHY RIDGE 1-32	32	080N	080E	4303330045	12970	State	GW	S	C
MURPHY RIDGE 7-32	32	080N	080E	4303330046		State	GW	APD	C
CRAWFORD 4-25	25	090N	070E	4303330065		Fee	GW	APD	C

## OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 8/25/2003
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 8/25/2003
3. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 8/25/2003
4. Is the new operator registered in the State of Utah: YES Business Number: 4743368-0161
5. If **NO**, the operator was contacted on: \_\_\_\_\_

6. (R649-9-2)Waste Management Plan has been received on: \_\_\_\_\_

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases or N/A

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: N/A

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: N/A

10. **Underground Injection Control ("UIC"** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

**DATA ENTRY:**

1. Changes entered in the **Oil and Gas Database** on: 10/31/2003
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 10/31/2003
3. Bond information entered in RBDMS on: 10/31/2003
4. Fee wells attached to bond in RBDMS on: 10/31/2003

**STATE WELL(S) BOND VERIFICATION:**

1. State well(s) covered by Bond Number: 885708C

**FEDERAL WELL(S) BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number: N/A

**INDIAN WELL(S) BOND VERIFICATION:**

1. Indian well(s) covered by Bond Number: N/A

**FEE WELL(S) BOND VERIFICATION:**

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 885588C
2. The **FORMER** operator has requested a release of liability from their bond on: N/A  
The Division sent response by letter on: N/A

**LEASE INTEREST OWNER NOTIFICATION:**

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 10/30/2003

**COMMENTS:**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_



# State of Utah

DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

1594 West North Temple, Suite 1210  
PO Box 145801  
Salt Lake City, Utah 84114-5801  
(801) 538-5340 telephone  
(801) 359-3940 fax  
(801) 538-7223 TTY  
www.nr.utah.gov

Michael O. Leavitt  
Governor

Robert L. Morgan  
Executive Director

Lowell P. Braxton  
Division Director

November 25, 2004 <sup>3</sup>

Lorna James  
Fat Chance Oil & Gas, LLC  
PO Box 7370  
Sheridan, WY 82801

Re: Notification of Sale or Transfer of Fee Lease Interest

Dear Ms. James:

The Division has received notification of a operator change from Fat Chance Oil & Gas, LLC to Quaneco, LLC for the attached list of wells which are located on fee leases.

Utah Administrative Rule R649-2-10 states; the owner of a lease shall provide notification to any person with an interest in such lease, when all or part of that interest in the lease is sold or transferred.

This letter is written to advise Fat Chance Oil & Gas, LLC of its responsibility to notify all individuals with an interest in this lease (royalty interest and working interest) of the change of operator. Please provide written documentation of this notification to:

Utah Royalty Owners Association  
Box 1292  
Roosevelt, Utah 84066

Your assistance in this matter is appreciated.

Sincerely,

Earlene Russell  
Engineering Technician

cc: Utah Royalty Owners Association, Lamar Wilson  
John R. Baza, Associate Director

Fat Chance Oil & Gas, LLC  
November 25, 2004

ATTACHMENT "A"

<u>Well Name</u>	<u>Sec.-Twsp -Rng.</u>	<u>API Number</u>
NEPONSET 4-35	35 080N 070E	4303330048
CRANE 4-4	04 060N 080E	4303330049
CRANE 12-4	04 060N 080E	4303330050
SIMS 13-33	33 070N 080E	4303330051
CRANE 13-8	08 060N 080E	4303330052
CRANE 6-7	07 060N 080E	4303330053
CRANE 13-6	06 060N 080E	4303330054
CRANE 13-18	18 060N 080E	4303330055
STACEY HOLLOW 14-35	35 070N 070E	4303330056
SUTTONS 4-12	12 060N 070E	4303330058
CRAWFORD 4-25	25 090N 070E	4303330065
COALVILLE 9-3	03 020N 050E	4304330322
COALVILLE 12-3	03 020N 050E	4304330323

**OIL & GAS INFORMATION SYSTEM**

FILE EDIT OIL GAS GAS PLANT REPORTS DB MAINTENANCE OPTIONS HELP DATA CONVERSION LOGS DATABASE QUERY

**Well Data**

**WELL SEARCH**

**WELL DATA**

**WELL HISTORY**

**WELL ACTIVITY**

WELL NAME **CRANE 6-7** API NUMBER **4303330053** WELL TYPE **GW** WELL STATUS **DRL**  
 OPERATOR **FELLOWS ENERGY LTD** ACCOUNT **N2560** # OPERATOR APPROVED BY BLM / BIA ☐  
 DESIGNATED OPERATOR \_\_\_\_\_ ACCOUNT \_\_\_\_\_  
 FIELD NAME **WILDCAT** FIELD NUMBER **1** FIRST PRODUCTION \_\_\_\_\_ LA / PA DATE \_\_\_\_\_

**WELL LOCATION:**

SURF LOCATION \_\_\_\_\_  
 Q. S. T. R. M. **SEMW** **07** **06.0 N** **08.0 E** **S**  
 COUNTY **RICH**

**UTM Coordinates:**

SURFACE - N **4568437.00** BHL - N \_\_\_\_\_  
 SURFACE - E **492921.00** BHL - E \_\_\_\_\_  
 LATITUDE **41.26924**  
 LONGITUDE **-111.08450**

CONFIDENTIAL FLAG ☒

CONFIDENTIAL DATE \_\_\_\_\_

DIRECTIONAL | HORIZONTAL ☐

HORIZONTAL LATERALS ☐

ORIGINAL FIELD TYPE **W**

WILDCAT TAX FLAG ☐

CB-METHANE FLAG ☐

ELEVATION **6802 GR**

BOND NUMBER / TYPE **353103303510** **4**

**SHOW WELL IMAGES**

LEASE NUMBER **FEE**

MINERAL LEASE TYPE **4**

SURFACE OWNER TYPE **4**

INDIAN TRIBE \_\_\_\_\_

C.A. NUMBER \_\_\_\_\_

UNIT NAME \_\_\_\_\_

**CUMULATIVE PRODUCTION:**

OIL \_\_\_\_\_

GAS \_\_\_\_\_

WATER \_\_\_\_\_

**COMMENTS** 020520 1YR APD EXT:030703 1YR APD EXT:031031 FR N1395:040324 DESIG AGENT/FELLOWS:040330 BOND FR 885588C:040331 OP FR N2495:040331 ENTITY ADDED:

Create New Rec

Save

Cancel Change

To History

To Activity

Print Recd

Export Recd





# **FELLOWS ENERGY**

**CRANE**

**6-7**

**API Well No.:**

**31-Mar-04  
RICH CO., UTAH**

**8 5/8 SURFACE CASING**

**Customer Representative:**

**CLIFF MURRAY**

**Halliburton Operator:**

**WAYNE MOUNT**

**Ticket No.:**

**3008090**



		JOB SUMMARY		SAP #/TICKET #		TICKET DATE	
				3008090		03/31/04	
REGION		NORTH AMERICA LAND		SAP #/STATE		DENVER CO	
WELL ID / EMP #		247118		H.S. EMPLOYEE NAME		WAYNE MOUNT	
LOCATION		10142 ROCK SPRINGS, WY		FSL DEPARTMENT		10003 CEMENTING SERVICES	
TICKET AMOUNT		\$17,891.62		CUSTOMER REP / PHONE		CLIFF MURRAY	
WELL LOCATION		WEST OF EVANSTON, WY		SAP BOMB NUMBER		7521	
LEASE NAME		CRANE		DESCRIPTION		8 5/8 SURFACE CASING	
WELL NO.		6-7		DEPARTMENT		CEMENTING SERVICES 10003	
SEC / TWP / RNG		S7 - T6N - R8E		APLUMI #			

H.S. EMP NAME / EMP # / (EXPOSURE HOURS)		HRS		HRS		HRS		HRS	
W. MOUNT 247118		6.0		D. LISH 295022		6.0		C. WARNE S.O.S.	

H.S. UNIT #S / (R / T MILES)		R / T MILES		R / T MILES		R / T MILES		R / T MILES	
10286388 (WBM)		240		10240238		10025185 RCM		240	

Form. Name		Type: GAS		Date		Called Out		On Location		Job Started		Job Completed	
Form. Thickness		From		Set At		3/31/04		3/31/04		3/31/04		3/31/04	
Packer Type		Pressure		Time		0830		1200		1606		1710	
Bottom Hole Temp.		Total Depth											
Retainer Depth													

Tools and Accessories				Well Data								
Type and Size		Qty	Make	New/Used		Weight	Size	Grade	From	To	Max. Allow	
Float Collar		1	SSII	Conductor Casing								
Float Shoe				Surface Casing		NEW	24.0	8 5/8	J-55	0	513	
Guide Shoe		1		Intermediate Casing								
Centralizers		4		Production Casing								
Bottom Plug				Liner								
Top Plug		1	5W	Tubing								
PDF Collar				Tubing								
PDF Shoe				Drill Pipe								
L Clamp		1		Drill Pipe								
DV Tool				Open Hole							Shots/Ft.	
Guide Shoe				Perforations								
Plug Set				Perforations								
Weld-a		1		Perforations								

Materials And Tank Strap				Hours On Location		Operating Hours (Pumping)		OPERATING TIME ( RIG UP/ RIG DOWN )		
Mud Type	WBM	Density	10.5	Lb/Gal	Date	Hours	Date	Hours	DATE	HRS. / MIN.
Disp. Fluid	H2O	Density	8.33	Lb/Gal	3/31	6.00	3/31	1.00	3/31	2
Plug #1 Set at _____ to _____ Ft _____ Sks										
Plug #2 Set at _____ to _____ Ft _____ Sks										
Plug #3 Set at _____ to _____ Ft _____ Sks										
Plug #4 Set at _____ to _____ Ft _____ Sks										
Plug #5 Set at _____ to _____ Ft _____ Sks										
Plug #6 Set at _____ to _____ Ft _____ Sks										
Plug #7 Set at _____ to _____ Ft _____ Sks										
Plug #8 Set at _____ to _____ Ft _____ Sks										
Total				6.0		1.0		TOTAL		2

Beging Strap				End Strap				Lead Cmt			
Beging Strap				End Strap				Lead Cmt			
Beging Strap				End Strap				Lead Cmt			
Beging Strap				End Strap				Lead Cmt			
Beging Strap				End Strap				Tail Cmt			
Beging Strap				End Strap				Tail Cmt			

Cement Data				Hydraulic Horsepower				Average Rates in BPM				Cement Left in Pipe			
Ordered				Avail.				Used							
Treating				Disp.				Overall							
Feet				43.0				Reason				SHOE JOINT			

Stage		Sacks	Cement	Bulk/Sks	Additives	W/Rq.	Yield	Lbs/Gal	BBLs
1	350	AG-300	BULK	2% CC, 1/4#/SK FLOCELE, 1/4 #/SK KWIKSEAL		5.00	1.15	15.8	71.7
2									0.0
3									0.0
4									0.0
5									0.0
6									0.0

Circulating		Displacement		Preflush:		Gal - BBI		Type:	
Breakdown		Maximum		Circulate Hole		Gal - BBI		Pad: Bbl - Gal	
Lost Returns-YES		Lost Returns-NO		Excess /Return Gal BBI				Calc. Disp Bbl	
Cmt Rtn#Bbl		29		SURFACE				Actual Disp.	
Average		Frac. Gradient		Treatment:		Gal - BBI		Disp: Bbl-Gal	
Shut In: Instant		15 Min.		30 Min.		Cement Slurry:		72	
						Total Volume		Gal - BBI	
								101	

THE INFORMATION STATED HEREIN IS CORRECT

CUSTOMER REPRESENTATIVE CLIFF MURRAY

SIGNATURE \_\_\_\_\_

## Job Log

**TICKET #**

3008090



03/31/04

REGION

## NORTH AMERICA LAND

[illegible]

# WESTERN

BDA / STATE

DENVER, CO

COUNTY

RICH CO., UTAH

MBU ID / EMPL #

247118

[illegible]

WAYNE MOUNT

PSL DEPARTMENT

10003 CEMENTING SERVICES

**LOCATION**

10142 ROCK SPRINGS, WY

COMPANY	
---------	--

**FELLOWS ENERGY**

CUSTOMER REP / PHONE

**CLIFF MURRAY**

TICKET AMOUNT
100
200
300
400
500
600
700
800
900
1000
1100
1200
1300
1400
1500
1600
1700
1800
1900
2000
2100
2200
2300
2400
2500
2600
2700
2800
2900
3000
3100
3200
3300
3400
3500
3600
3700
3800
3900
4000
4100
4200
4300
4400
4500
4600
4700
4800
4900
5000
5100
5200
5300
5400
5500
5600
5700
5800
5900
6000
6100
6200
6300
6400
6500
6600
6700
6800
6900
7000
7100
7200
7300
7400
7500
7600
7700
7800
7900
8000
8100
8200
8300
8400
8500
8600
8700
8800
8900
9000
9100
9200
9300
9400
9500
9600
9700
9800
9900
10000

**\$17,891.62**

WELL TYPE

## 02 GAS

API/UNI #	
-----------	--

WELL LOCATION

WEST OF EVANSTON, WY

DEPARTMENT

**CEMENTING SERVICES 10003**

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00
JOB PURPOSE CODE																																																																																																			

7521

LEASE / WELL #

**CRANE**

Well No.

6-7


SEC / TWP / RNG

**S7 - T6N - R8E**

[illegible]



# ROCK SPRINGS CEMENT



## Event Log

1 Start Job	16:06:36	2 Test Lines	16:08:30	3 Pump Spacer 1	16:09:39
4 Pump Cement	16:16:55	5 Shut Down / Drop Top Plug	16:48:08	6 Pump Displacement	16:48:38
7 Bump Plug	16:58:47	8 Check Floats	17:03:20		

Customer: FELLOWS ENERGY  
Well Description: CRANE 6-7


Job Date: 3/31/04  
Operator: WAYNE MOUNT

Ticket #: 3008090  
Job Type: 8 5/8 SURFACE CASING



CemWin v1.5.0  
31-Mar-04 17:25

Fax Transmittal Form



P.O. Box 7370  
850 Val Vista  
Sheridan WY 82801-7370

To  
Name: Vickie  
Organization Name/Dept: \_\_\_\_\_  
Phone number: \_\_\_\_\_  
Fax number: \_\_\_\_\_

From  
Quaneco, LLC  
Phone: 307-673-1500  
Fax: 307-673-1400  
Name: Lorna James

Date sent: 3-17-04  
Time Sent: \_\_\_\_\_  
Number of pages including cover page: 2

Message:

RECEIVED

MAR 17 2004

DIV. OF OIL, GAS & MINING

# QUANECO, LLC


850 Val Vista-Box 7370-Sheridan, WY 82801-Office 307-673-1500-Fax 307-673-1400 [quaneco@fiberpipe.net](mailto:quaneco@fiberpipe.net)

3/17/2004

To Whom It May Concern:

Quaneco, LLC does here by authorize Steven Prince and Cliff Murray to have full access to all well files permitted by Quaneco, LLC or Fat Chance Oil and Gas, LLC. This authorization is not limited to permit information. The above individuals have full access to all records we have submitted including logs.

Sincerely,



Lorna James

Administrative Assistant

RECEIVED

MAR 17 2004

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 5

DESIGNATION OF AGENT OR OPERATOR

The undersigned is, on record, the holder of oil and gas lease

LEASE NAME: Deseret

LEASE NUMBER: Fee

and hereby designates

NAME: Fellows Energy, Ltd.

ADDRESS: 807 N. Pinewood Circle

city Price state UT zip 84051

as his (check one) agent ☒ / operator ☐, with full authority to act in his behalf in complying with the terms of the lease and regulations applicable thereto and on whom the Division Director or Authorized Agent may serve written or oral instructions in securing compliance with the Oil and Gas Conservation General Rules and Procedural Rules of the Board of Oil, Gas and Mining of the State of Utah with respect to:

(Describe acreage to which this designation is applicable. Identify each oil and gas well by API number and name. Attach additional pages as needed.)

Crane 6-7 well location specified as API# 4303330053

RECEIVED  
MAR 24 2004

DIV. OF OIL, GAS & MINING

It is understood that this designation of agent/operator does not relieve the lessee of responsibility for compliance with the terms of the lease and the Oil and Gas Conservation General Rules and Procedural Rules of the Board of Oil, Gas and Mining of the State of Utah. It is also understood that this designation of agent or operator does not constitute an assignment of any interest in the lease.

In case of default on the part of the designated agent/operator, the lessee will make full and prompt compliance with all rules, lease terms or orders of the Board of Oil, Gas and Mining of the State of Utah or its authorized representative.

The lessee agrees to promptly notify the Division Director or Authorized Agent of any change in this designation.

Effective Date of Designation: 03/16/2004

BY: (Name) Casey Osborn  
(Signature) *Casey Osborn*  
(Title) Operations Manager  
(Phone) (307) 673-1500

OF: (Company) Quaneco, LLC  
(Address) PO Box 7370  
city Sheridan  
state WY zip 82801

*W*



CONFIDENTIAL

**DIVISION OF OIL, GAS AND MINING**

**SPUDDING INFORMATION**

Name of Company: QUANECO LLC

Well Name: CRANE 6-7

Api No: 43-033-30053 Lease Type: FEE

Section 07 Township 06N Range 08E County RICH

Drilling Contractor MIDWAY DRILLING RIG # 1

**SPUDDED:**

Date 03/25/04

Time 3:00 PM

How ROTARY

**Drilling will commence:** \_\_\_\_\_

Reported by CLIFF MURRAY

Telephone # 1-435-650-5387

Date 03/26/2004 Signed CHD

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		6. LEASE DESIGNATION AND SERIAL NUMBER: Fee
2. NAME OF OPERATOR: Quaneco, LLC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: PO Box 7370 CITY Sheridan STATE WY ZIP 82801		7. UNIT OF CO-AGREEMENT NAME:
PHONE NUMBER: (307) 673-1500		8. WELL NAME AND NUMBER: Crane 6-7
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2363 FNE 1970 FWL		9. API NUMBER: 4303330053
QTR/OTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 7 T6N R8E S		10. FIELD AND POOL, OR WILDCAT: Wildcat
		COUNTY: Rich
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: transfer of permit
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Please transfer the APD for this well to:

Fellows Energy Ltd  
807 N. Pinewood Circle  
Price UT 84051

NAME (PLEASE PRINT) <u>Lorna James</u>	TITLE <u>Administrative Assistant</u>
SIGNATURE <u>Lorna James</u>	DATE <u>3/29/2004</u>

(This space for State use only)

**RECEIVED**  
**MAR 29 2004**  
DIV. OF OIL, GAS & MINING

## Request to Transfer Application or Permit to Drill

(This form should accompany a Sundry Notice, Form 9, requesting APD transfer)

<b>Well name:</b>	Crane 6-7
<b>API number:</b>	4303330053
<b>Location:</b>	Qtr-Qtr: <u>SE</u> NW Section: <u>7</u> Township: <u>6N</u> Range: <u>R8E</u>
<b>Company that filed original application:</b>	Fat Chance OIL & GAS
<b>Date original permit was issued:</b>	6-13-2001
<b>Company that permit was issued to:</b>	FAT CHANCE OIL & GAS

Check one	Desired Action:
	<b>Transfer pending (unapproved) Application for Permit to Drill to new operator</b>
	The undersigned as owner with legal rights to drill on the property, hereby verifies that the information as submitted in the pending Application for Permit to Drill, remains valid and does not require revision. The new owner of the application accepts and agrees to the information and procedures as stated in the application.
<input checked="" type="checkbox"/>	<b>Transfer approved Application for Permit to Drill to new operator</b>
	The undersigned as owner with legal rights to drill on the property as permitted, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.	Yes	No
If located on private land, has the ownership changed?		<input checked="" type="checkbox"/>
If so, has the surface agreement been updated?		<input checked="" type="checkbox"/>
Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location?		<input checked="" type="checkbox"/>
Have there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well?		<input checked="" type="checkbox"/>
Have there been any changes to the access route including ownership or right-of-way, which could affect the proposed location?		<input checked="" type="checkbox"/>
Has the approved source of water for drilling changed?		<input checked="" type="checkbox"/>
Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation?		<input checked="" type="checkbox"/>
Is bonding still in place, which covers this proposed well? Bond No. <u>blanket statewide 353103303510</u>	<input checked="" type="checkbox"/>	

Any desired or necessary changes to either a pending or approved Application for Permit to Drill that is being transferred, should be filed on a Sundry Notice, Form 9, or amended Application for Permit to Drill, Form 3, as appropriate, with necessary supporting information as required.

Name (please print) Steven L. Prince Title Vice President, Operations  
 Signature *Steven L. Prince* Date 03/24/2004  
 Representing (company name) Fellows Energy Ltd.

The person signing this form must have legal authority to represent the company or individual(s) to be listed as the new operator on the Application for Permit to Drill.

**RECEIVED**

**MAR 29 2004**

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 5

## DESIGNATION OF AGENT OR OPERATOR

The undersigned is, on record, the holder of oil and gas lease

LEASE NAME: DeseretLEASE NUMBER: Fee

and hereby designates

NAME: Fellows Energy Ltd.ADDRESS: 807 N. Pinewood Circlecity Price state UT zip 84051

as his (check one) agent ☐ / operator ☒, with full authority to act in his behalf in complying with the terms of the lease and regulations applicable thereto and on whom the Division Director or Authorized Agent may serve written or oral instructions in securing compliance with the Oil and Gas Conservation General Rules and Procedural Rules of the Board of Oil, Gas and Mining of the State of Utah with respect to:

(Describe acreage to which this designation is applicable. Identify each oil and gas well by API number and name. Attach additional pages as needed.)

Crane 6-7 API# 4303330053 located in Township 6 North, Range 8 East, Section 7: SENW

It is understood that this designation of agent/operator does not relieve the lessee of responsibility for compliance with the terms of the lease and the Oil and Gas Conservation General Rules and Procedural Rules of the Board of Oil, Gas and Mining of the State of Utah. It is also understood that this designation of agent or operator does not constitute an assignment of any interest in the lease.

In case of default on the part of the designated agent/operator, the lessee will make full and prompt compliance with all rules, lease terms or orders of the Board of Oil, Gas and Mining of the State of Utah or its authorized representative.

The lessee agrees to promptly notify the Division Director or Authorized Agent of any change in this designation.

Effective Date of Designation: 03/29/2004

BY: (Name) Lorna James  
(Signature) *Lorna James*  
(Title) Administrative Assistant  
(Phone) (307) 673-1500

OF: (Company) Quaneco, LLC  
(Address) PO Box 7370  
city Sheridan  
state WY zip 82801

(5/2000)

RECEIVED

MAR 29 2004

DIV. OF OIL, GAS &amp; MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:

Fellows Energy Ltd.

3. ADDRESS OF OPERATOR:

807 N. Pinewood Circle CITY Price STATE UT ZIP 84501

PHONE NUMBER:

(435) 650-4492

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 2363' FNL 1970' FWL

COUNTY: Rich

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 7 T6N R8E S

STATE:

UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:

Fee

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

NA

7. UNIT or CA AGREEMENT NAME:

NA

8. WELL NAME and NUMBER:

Crane 6-7

9. API NUMBER:

4303330053

10. FIELD and POOL, OR WILDCAT:

Wildcat

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>3/25/2004</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Change operator for this well from Quaneco, LLC and/or Fat Chance Oil & Gas, LLC to Fellows Energy Ltd.

NAME (PLEASE PRINT) Steven L. Prince

TITLE Vice President, Operations

SIGNATURE

DATE 3/24/2004

(This space for State use only)

RECEIVED

MAR 29 2004

DIV. OF OIL, GAS & MINING

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, rewire plugged wells, or to drill horizontal intervals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

Fee

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

Crane 6-7

9. API NUMBER:

4303330053

10. FIELD AND POOL, OR WILDCAT:

Wildcat

1. TYPE OF WELL

OIL WELL ☐GAS WELL ☒

OTHER

2. NAME OF OPERATOR:

Fellows Energy Ltd.

3. ADDRESS OF OPERATOR:

807 N. Pinewood Circle, Price

STATE UT ZIP 84501

PHONE NUMBER:

(435) 650-4492

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 2353' FNL 1970' FWL

COUNTY: Rich

QUARTER, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 7 T6N R8E S

STATE:

UTAH

## 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 3/25/2004	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input checked="" type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMENCE PRODUCE FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER:
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPILE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Change Surface Casing: FROM 9-5/8" H-40 32.3 #/ft TO 8-5/8" H-40 28#/ft

Change Surface Cement: 350 sacks of "G" (1.18 c/sack, 15.6 #/gal)

Change Production Casing: FROM 7" K-55 23#/ft TO 5-1/2" K-55 17#/ft (or N-80 17#/ft)

Change Production Cement: Lead: 542 sacks of "G" 35/65 POZ (1.89 c/sack, 12.4 #/gal); Tail: 70 sacks of "G" Thix (1.6 c/sack, 14.2 #/gal)

We also plan to dig and line a small (10'X24') pit for surface drilling and cementing. The pit shall be reclaimed as soon after setting surface casing as practical.

**APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING**

DATE: 3/30/2004

BY: *[Signature]*

RECEIVED

MAR 26 2004

DIV. OF OIL, GAS &amp; MINING

NAME (PLEASE PRINT) Steven L. Prince

TITLE Vice President, Operations

SIGNATURE *Steven L. Prince*

DATE 3/25/2004

(This space for State use only)

*Lorna James for Quaneco LLC*  
3-25-04

COPY SENT TO OPERATOR

Date: 3-30-2004

Initials: *[Signature]*

## Northeastern Utah core hole targeting Cretaceous coals under way

**B**ROOMFIELD, COLORADO-BASED Fellows Energy Ltd said it has spudded a core hole on the northeastern Utah salient of the Overthrust Belt approximately six miles west of Evanston, Wyoming.


The 6-7 Crane, se nw 7-6n-8e, southeastern Rich County, is designed as a core test of the Spring Valley (Frontier) and Bear River coals. A continuous coring, wireline retrievable, system will be used to recover the coal and carbonaceous shale core samples for gas content analysis, according to Fellows. The company said the core analysis, combined with information from three wells previously drilled in the vicinity by Quaneco LLC, will help it formulate total gas-in-place estimates.

Drilling of the 6-7 Crane is expected to take 3-4 weeks to reach its projected depth of 5000 ft.

The 6-7 Crane originally was permitted by Far Chance Oil & Gas LLC (subsequently Quaneco) in 2001. Fellows recently entered into a purchase and option agreement with Quaneco to acquire a 65 percent working interest in the "Overthrust Project," which comprises over 183,000 acres of leases in northeastern Utah and southwestern Wyo-

ming. Quaneco previously drilled seven exploratory wells that identified multiple coal seams of Tertiary and Cretaceous age that appear to be prospective for coalbed methane, according to Fellows.

The 6-7 Crane is nearly two miles west of the Wyoming border and about five miles southwest of the Thomas Canyon field discovery, a Bear River oil producer completed in 1987 in Uinta County, Wyoming.





## Fax Transmittal Form



P.O. Box 7370  
850 Val Vista  
Sheridan WY 82801-7370

To

Name:

Dustin Doucet

Organization Name/Dept: \_\_\_\_\_

Phone number: \_\_\_\_\_

Fax number: \_\_\_\_\_

From

Quanco, LLC

Phone: 307-673-1500

Fax: 307-673-1400

Name:

Lorna

Date sent: \_\_\_\_\_

Time Sent: \_\_\_\_\_

Number of pages including cover page: 2

Message:

RECEIVED

MAR 26 2004

DIV. OF OIL, GAS &amp; MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER ☐

2. NAME OF OPERATOR:

Fellows Energy Ltd.

3. ADDRESS OF OPERATOR:

807 N. Pinewood Circle CITY Price STATE UT ZIP 84501

PHONE NUMBER:

(435) 650-4492

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 2363' FNL 1970' FWL

COUNTY: Rich

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 7 T6N R8E S

STATE:

UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:  
Fee

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

Crane 6-7

9. API NUMBER:

4303330053

10. FIELD and POOL, OR WILDCAT:

Wildcat

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit In Duplicate) Approximate date work will start: <u>3/25/2004</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

We plan to core the coals in the Frontier and Kelvin Formations.

COPY SENT TO OPERATOR

Date: 3-31-04  
Initials: CHD

NAME (PLEASE PRINT) Steven L. Prince

TITLE Vice President, Operations

SIGNATURE

DATE 3/29/2004

(This space for State use only)

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING

DATE: 3/30/2004

BY: [Signature]

RECEIVED

MAR 29 2004

DIV. OF OIL, GAS & MINING

Well name:	<b>3-04 Fellows Crane 6-7rev.</b>	
Operator:	<b>Quanneco/Fellows</b>	Project ID:
String type:	<b>Production</b>	<b>43-033-30053</b>
Location:	<b>Rich Co.</b>	

**Design parameters:****Collapse**

Mud weight: 9.500 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 135 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 368 ft

Cement top: 1,660 ft

**Burst**

Max anticipated surface pressure: 0 psi  
Internal gradient: 0.494 psi/ft  
Calculated BHP 2,467 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Non-directional string.

Tension is based on air weight.  
Neutral point: 4,280 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	5000	5.5	17.00	K-55	ST&C	5000	5000	4.767	172.3

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	2467	4910	1.99	2467	5320	2.16	85	252	2.96 J

Prepared Dustin K. Doucet  
by: Utah Dept. of Natural Resources

Date: March 29, 2004  
Salt Lake City, Utah

**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 5000 ft, a mud weight of 9.5 ppg. The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>3-04 Fellows Crane 6-7rev.</b>	
Operator:	<b>Quanneco/Fellows</b>	Project ID:
String type:	Surface	43-033-30053
Location:	Rich Co.	

**Design parameters:****Collapse**

Mud weight: 9.000 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 72 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 200 ft

Cement top: Surface

**Burst**

Max anticipated surface pressure: 0 psi  
Internal gradient: 0.494 psi/ft  
Calculated BHP 247 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on air weight.  
Neutral point: 434 ft

Non-directional string.

**Re subsequent strings:**

Next setting depth: 5,000 ft  
Next mud weight: 9.500 ppg  
Next setting BHP: 2,468 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 500 ft  
Injection pressure 500 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	500	8.625	28.00	H-40	ST&C	500	500	7.892	27.6

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	234	1610	6.89	247	2470	10.01	14	233	16.64 J

Prepared Dustin K. Doucet  
by: Utah Dept. of Natural Resources

Date: March 29, 2004  
Salt Lake City, Utah

**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 500 ft, a mud weight of 9 ppg. The casing is considered to be evacuated for collapse purposes.


Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

# 3-04 Fellows Crane 6-7re

## Casing Schematic

CONFIDENTIAL



**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: <b>Fee</b>
2. NAME OF OPERATOR: <b>Fellows Energy Ltd.</b>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: <b>807 N. Pinewood Circle</b> CITY <b>Price</b> STATE <b>UT</b> ZIP <b>84501</b>		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: <b>2363' FNL 1970' FWL</b>		8. WELL NAME and NUMBER: <b>Crane 6-7</b>
PHONE NUMBER: <b>(435) 650-4492</b>		9. API NUMBER: <b>4303330053</b>
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>SE NW 7 T6N R8E S</b>		10. FIELD AND POOL, OR WILDCAT: <b>Wildcat</b>
COUNTY: <b>Rich</b>		STATE: <b>UTAH</b>

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> (Submit in Duplicate)  Approximate date work will start: <b>3/25/2004</b>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input checked="" type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> (Submit Original Form Only)  Date of work completion: _____	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Change Surface Casing: FROM 9-5/8" H-40 32.3 #/ft TO 8-5/8" H-40 28#/ft  
 Change Surface Cement: 350 sacks of "G" (1.18 cf/sack, 15.6 #/gal)  
 Change Production Casing: FROM 7" K-55 23#/ft TO 5-1/2" K-55 17#/ft (or N-80 17#/ft)  
 Change Production Cement: Lead: 542 sacks of "G" 35/65 POZ (1.89 cf/sack, 12.4 #/gal); Tail: 70 sacks of "G" Thix (1.6 cf/sack, 14.2 #/gal)

We also plan to dig and line a small (10'X24') pit for surface drilling and cementing. The pit shall be reclaimed as soon after setting surface casing as practical.

**COPY SENT TO OPERATOR**  
Date: 3-30-04  
Initials: CHD

NAME (PLEASE PRINT) <u>Steven L. Prince</u>	TITLE <u>Vice President, Operations</u>
SIGNATURE <u><i>Steven L. Prince</i></u>	DATE <u>3/25/2004</u>

(This space for State use only)

*Fax Copy Approved with conditions 3/30/04 DKD*

**RECEIVED**  
**MAR 29 2004**

DIV. OF OIL, GAS & MINING

### 3. FILE

## Merger

**3/25/2004**

**Phone: 1-(435) 650-4492**

Unit:

[illegible]

3/29/2004

3/29/2004

3/30/2004

**YES Business Number: 5589189-0143**

Fellows Energy 0304 FORM 4A.xls 3/30/2004



6. (R649-9-2)Waste Management Plan has been received on:

IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM n/a BIA n/a

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: n/a

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

**DATA ENTRY:**

1. Changes entered in the **Oil and Gas Database** on: 3/30/2004
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 3/30/2004
3. Bond information entered in RBDMS on: 3/30/2004
4. Fee wells attached to bond in RBDMS on: 3/30/2004
5. Injection Projects to new operator in RBDMS on: n/a
6. Receipt of Acceptance of Drilling Procedures for APD/New on: 3/29/2004

**STATE WELL(S) BOND VERIFICATION:**

1. State well(s) covered by Bond Number: 353103303510

**FEDERAL WELL(S) BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number: n/a

**INDIAN WELL(S) BOND VERIFICATION:**

1. Indian well(s) covered by Bond Number: n/a

**FEE WELL(S) BOND VERIFICATION:**

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 353103303510  
#####
2. The **FORMER** operator has requested a release of liability from their bond on: N/A  
The Division sent response by letter on: N/A

**LEASE INTEREST OWNER NOTIFICATION:**

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 3/30/2004

**COMMENTS:**

# ENTITY ACTION FORM

Operator: Fellows Energy Ltd.  
Address: 807 N. Pinewood Circle  
city Price  
state UT zip 84501

Operator Account Number: N 2560

Phone Number: (435) 650-4492

## Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4303330053	Crane 6-7		SEnw	7	6N	8E	Rich
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	99999	14100	3/25/2004			3/31/04	
Comments: <u>Kelvin</u>							

## Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

## Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

## ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

RECEIVED

MAR 3 1 2004

Steven L. Prince

Name (Please Print)

Signature

VP Operations

Title

3/30/2004

Date

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>	5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
2. NAME OF OPERATOR: Fellows Energy Ltd.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 807 N. Pinewood Circle, Price, UT 84501	7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2363' FNL 1970' FWL	8. WELL NAME and NUMBER: Crane 6-7
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 7 T6N R8E S	9. API NUMBER: 4303330053
PHONE NUMBER: (435) 650-4492	10. FIELD AND POOL, OR WILDCAT: Wildcat

CONFIDENTIAL

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

We plan to use potassium chloride in our drilling mud to prevent sloughing of shales.

The BOP equipment we plan to use while drilling will be as illustrated in the attached Exhibit "E".

Surface casing head will be by a 2000 psi unit.

COPY SENT TO OPERATOR  
Date: 4-1-04  
Initials: C/L

NAME (PLEASE PRINT) Steven L. Prince TITLE Vice President, Operations  
SIGNATURE Steven L. Prince DATE 3/30/2004


(This space for State use only)

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING  
DATE: 4/1/2004  
BY: [Signature]

RECEIVED  
APR 01 2004  
DIV. OF OIL, GAS & MINING

**Exhibit "E"**

CONFIDENTIAL



**3000 psi BOP Equipment**  
Fellows Energy Ltd.

2/23/04



State of Utah

Department of  
Natural Resources

Division of  
Oil, Gas & Mining

ROBERT L. MORGAN  
*Executive Director*

LOWELL P. BRAXTON  
*Division Director*

April 12, 2004

Lorna James  
Quaneco, LLC.  
PO Box 7370  
Sheridan, WY 82801

Re: Notification of Sale or Transfer of Fee Lease Interest

Dear Lorna:

The Division has received notification of an operator change from Quaneco, LLC. to Fellows Energy LTD for the attached list of wells, which are located on fee leases.

Utah Administrative Rule R649-2-10 states; the owner of a lease shall provide notification to any person with an interest in such lease, when all or part of that interest in the lease is sold or transferred.

This letter is written to advise Quaneco, LLC. of its responsibility to notify all individuals with an interest in this lease (royalty interest and working interest) of the change of operator. Please provide written documentation of this notification to:

Utah Royalty Owners Association  
Box 1292  
Roosevelt, Utah 84066

Your assistance in this matter is appreciated.

Sincerely,

*Earlene Russell*  
Earlene Russell  
Engineering Technician

cc: Utah Royalty Owners Association  
John R. Baza, Associate Director

Quaneco, LLC.  
April 12, 2004

ATTACHMENT "A"

<u>Well Name</u>	<u>Sec.-Twp -Rng.</u>			<u>API Number</u>
CRANE 6-7	07	060N	080E	4303330053

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
2. NAME OF OPERATOR: Fellows Energy Ltd.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 807 N. Pinewood Circle, Price, UT 84501		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2363' FNL 1970' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 7 T6N R8E S		8. WELL NAME and NUMBER: Crane 6-7
PHONE NUMBER: (435) 650-4492		9. API NUMBER: 4303330053
COUNTY: Rich		10. FIELD AND POOL, OR WILDCAT: Wildcat
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 5/3/2004	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input checked="" type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER:
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

2.2. The status of the well, whether drilling, producing, injecting or inactive.

Drilling of the Crane 6-7 was completed on 5/1/04.

2.3. A description of the well bore configuration indicating depth, casing strings, cement tops if known, and hole size.

Wellbore Diameter: 7-7/8" drilled to a total depth of 4280'.

Surface Casing: 8-5/8" J-55 24#/ft set at 528' with cement to surface.

2.4. The tops of known geologic markers or formations.

Wasatch	Surface
Unconformity	1516'
Frontier	1516'
Aspen Shale	2234'
Bear River	2614'

The plugging program:

We will leave the drilling mud (description attached) in the well bore and place a 100' cement plug centered at the top of each of the following formations: the Bear River (2614'), the Aspen Shale (2234'), and the Frontier (1516'). We will also center a 100' cement plug at the surface casing shoe (528') and place a ten sack plug at surface.

Cement: Class "G" 28 cc/lb 1.15 yield Cliff Murray 5/3/04

COPY SENT TO OPERATOR

Date: 5-3-04

Initials: CHD


NAME (PLEASE PRINT) Steven L. Prince	TITLE Vice President, Operations
SIGNATURE <i>Steven L. Prince</i>	DATE 5/2/2004


(This space for State use only)

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING

DATE: 5/03/2004 (See Instructions on Reverse Side)

BY: *[Signature]*  
\* See Conditions of Approval Attached





# KEMTEC

P.O. Drawer 160  
Roosevelt, Utah 84066



## CONFIDENTIAL

WATER MUD REPORT NO. 24

API Well No.	State	County	Well	S/T

Date <u>02 May 04</u>	Depth <u>4280 TD</u>
Spud Date <u>09 April 04</u>	Present Activity <u>Circ 4-5 LBS</u>

OPERATOR:  
FELIOWS ENERGY, LTD.

CONTRACTOR:  
Union Drilling, Inc.

RIG NO: 14

Report for  
Mr. Cliff Murray

Report for  
Mr. Rex Harris Sr.

Section, Township, Range  
7-6N-8E

Well Name and No.  
CRANE 6-7

Field or Block No.  
WILDCAT

County, Parish, Offshore Area  
RICH

State  
UTAH

DRILLING ASSEMBLY			CASING:		MUD VOLUME: (bbl)		CIRCULATION DATA:			
Bit Size <u>7 1/8</u>	Type <u>HHT-447</u>	Jet Size <u>3/16</u>	Surface <u>8 5/8</u>	513"	Hole <u>270</u>	Pits <u>450</u>	Pump Size <u>16 x 8</u>	x	in.	Annular Vel (ft/min)
Drill Pipe Size <u>5</u>	Type	Length	Intermediate		Total Circulating Volume <u>720</u>		Pump Make, Model <u>ED PZ-8</u>	Assumed Eff. <u>85</u>		Circulation Pressure (psi) <u>640</u>
Drill Pipe Size <u>5</u>	Type	Length	Liner		In Storage	Weight		stk/min		Bottoms Up
Drill Collar Size <u>6 3/8 x 2 1/4</u>	Length		Production or Liner		Mud Type <u>SEMI-DISP</u>		bbl/min <u>8.0494</u>	gal/min <u>338</u>	(min) <u>34</u>	(stks) <u>117</u>

MUD PROPERTIES:				MUD PROPERTY SPECIFICATIONS:			
Sample From	<input type="checkbox"/> F.L. Pit	<input checked="" type="checkbox"/> F.L. Pit	<input type="checkbox"/> F.L. Pit	Weight	Viscosity	Filtrate	
Time Sample Taken		<u>6:00 AM</u>		<u>9.3 to 9.5</u>	<u>45 to 48</u>	<u>3 to 5 cc</u>	
Flowline Temperature (°F)				SOLIDS EQUIPMENT:			
Depth (ft)	<input type="checkbox"/> TVD	<input type="checkbox"/> MD	<u>4280</u>	Processing Equipment	Screen Size	Screen Size	Shaker 3
Weight <input type="checkbox"/> (ppg) <input type="checkbox"/> (lb/cu ft) <input type="checkbox"/> (sp gr) °F			<u>9.8</u>	Shaker 1			Cleaner
Funnel Viscosity (sec/qt) API @ °F			<u>45</u>	Shaker 2			Degasser
Plastic Viscosity cp @ °F			<u>17</u>				Centrifuge
Yield Point (lb/100 ft²)			<u>12</u>	REMARKS:			
Gel Strength (lb/100 ft²) 10 sec/10 min			<u>6.11</u>	<u>NO FURTHER CHEMICAL TREATMENT SHOULD BE NEEDED.</u>  <u>SUGGEST SAVING 400-750 LBS OF MUD FOR HOLE UPGRADING WORK IN JORDAN'S VALLEY.</u>			
Filtrate API (cm³/30 min)			<u>8.0</u>				
API HTHP Filtrate (cm³/30 min.) @ °F			<u>—</u>				
Cake Thickness (32nd in API/HTHP)			<u>1 2/32</u>				
Retort Solids (% Vol.)			<u>5</u>				
Retort Liquid (% Vol.) Oil/Water			<u>1 1/2</u>				
Sand Content (% Vol.)			<u>72</u>				
Methylene Blue Capacity <input type="checkbox"/> (bbl/sq ft) <input type="checkbox"/> (cm³/cm² mud)			<u>—</u>				
pH <input type="checkbox"/> Strip <input type="checkbox"/> Meter @ °F			<u>11.0</u>				
Alkalinity Mud (P <sub>H</sub> ), cm³ N/50 Acid			<u>—</u>				
Alkalinity Filtrate (P <sub>H</sub> /M), cm³ N/50 Acid			<u>1 6.1/4</u>				
Chloride (mg/L)			<u>3200</u>				
<input type="checkbox"/> Total Hardness <input type="checkbox"/> Calcium, (mg/L)			<u>60</u>				
ECQ Bit (#/CAL)			<u>9.6</u>				
% KCL			<u>4 1/2</u>				

PRODUCTS:

	BARGE	KCL	MAW-SEA	DURAN	MARCO	SUNDRAL	DISCO	PAC-B	MICA	SUNDRAL	PAINTS	CRANE	C-320	SAPP	ALUM	SEPARATE	K-560
Starting Inventory	-	-	92	250	80	24	12	40	160	55	29	30	-	2	2	-	
Received																	
Used Last 24 hr.																	
Closing Inventory	-	-	92	250	80	14	6	34	160	55	29	21	-	2	2	-	
Cost Last 24 hr.																	

Representative <u>Law Arrows (435)</u>	Phone <u>823-5160</u>	Warehouse Phone	Daily Cost <u>ESTIMATED \$ 1715 +/-</u>	Cumulative Cost <u>ESTIMATED \$ 62,333 +/-</u>
---	--------------------------	-----------------	--	---

In consideration of the furnishing of this report and oral suggestions, it is agreed that no recommendations made hereon shall be construed as authorizing the infringement of any valid patent, and it is agreed that Kemtec shall not be liable for any damages resulting from the furnishing of this and oral suggestions and it is to be held harmless.

BIT DATA:	MUD VOLUME ACCOUNTING:	SOLIDS ANALYSIS:	MUD RHEOLOGY AND HYDRAULICS:
Current Bit No. <u>RR# 14</u>	Water Added (bbl)	Low Gravity, (% Vol.)	600 RPM   Annular Section   1   2   3



**From:** "Steven L. Prince" <cvGPC@emerytelcom.net>  
**To:** "Dustin Doucet" <dustindoucet@utah.gov>  
**Date:** 5/2/04 11:02PM  
**Subject:** Crane 6-7 Plugging Notice

Dustin:

Please let me know ASAP regarding approval of the attached plugging notice and procedure. If you have any questions or concerns, please call me at 435-650-4492 prior to 9 am on 5/3/04. Thanks for your help.  
Steven Prince

**CC:** "Dan Jarvis" <danjarvis@utah.gov>, "Lisha Cordova" <lcordova@state.ut.us>, "Clifford Murray" <nonapi@iwworks.com>



State of Utah

Department of  
Natural Resources

Division of  
Oil, Gas & Mining

ROBERT L. MORGAN  
*Executive Director*

LOWELL P. BRAXTON  
*Division Director*

MICHAEL O. LEAVITT  
*Governor*

OLENE S. WALKER  
*Lieutenant Governor*

CONFIDENTIAL

## ***CONDITIONS OF APPROVAL TO PLUG AND ABANDON WELL***

Well Name and Number: Crane 6-7  
API Number: 43-033-30053  
Operator: Fellows Energy Ltd.  
Reference Document: Original Sundry Notice dated May 2, 2004,  
received by DOGM on May 3, 2004

### Approval Conditions:

1. Notify the Division at least 24 hours prior to conducting abandonment operations. Please call Dan Jarvis at 801-538-5338.
2. ADD: A minimum of 20 sx shall be placed at surface to ensure an adequate length plug for proper sealing ---  $\pm 50'$ . (Procedure calls for 10 sx)
3. All balanced plugs shall be tagged to ensure that they are at the depths specified in the intent.
4. A dry hole marker shall be erected in accordance with R649-3-24-7 unless a variance for a subsurface marker is requested by the operator and approved by the Division.
5. Surface reclamation shall be done in accordance with R649-3-34 – Well Site Restoration. Evidence of compliance with this rule should be supplied to the Division upon completion of reclamation.
6. Form 8 – Well Completion or Recompletion Report and Log shall be submitted to the Division upon completion of work.
7. All requirements in the Oil and Gas Conservation General Rule R649-3-24 shall apply.
8. If there are any changes to the plugging procedure or the wellbore configuration, notify Dustin Doucet at 801-538-5281 prior to continuing with the procedure.
9. All other requirements for notice and reporting in the Oil and Gas Conservation General Rules shall apply.

Dustin K. Doucet  
Petroleum Engineer

May 3, 2004

Date

5/3/2004

## Wellbore Diagram

CONFIDENTIAL

r263

API Well No: 43-033-30053-00-00

Permit No:

Well Name/No: CRANE 6-

Company Name: FELLOWS ENERGY LTD

Location: Sec: 7 T: 6N R: 8E Spot: SENW

Coordinates: X: 492921 Y: 4568437

Field Name: WILDCAT

County Name: RICH

## String Information

String	Bottom (ft sub)	Diameter (inches)	Weight (lb/ft)	Length (ft)
HOL1	528	12.25		
SURF	528	8.625	24	528
HOL2	4280	7.875		

Well

2797

Surface Plug

$$(bxc)(1.15)(2797) = 82'$$

minimum of 20 SK required (±50')

$$\frac{(1.2)(2875)^2}{183.35} = 0.4871$$

2.053

50' Cement from 528 ft. to surface

Hole: 12.25 in. @ 528 ft.

Surface: 8.625 in. @ 528 ft.

500' Plug 4

$$600' \frac{50'}{(1.15)(2.053)} = 21 SK$$

$$50' / (1.15)(2.797) = 16 SK$$

37 SK

## Cement Information

String	BOC (ft sub)	TOC (ft sub)	Class	Sacks
SURF	528	0	G	

1516' Plug 3

$$1600' \frac{100'}{100'} = 42 SK$$

2234' Plug 2

$$2300' \frac{100'}{100'} = 42 SK$$

## Perforation Information

2614' Plug 1

$$2700' \frac{100'}{(1.15)(2.053)} = 42 SK$$

## Formation Information

Formation	Depth	Formation	Depth
WSTC	0		
FRTR	1516		
ASPEN	2234		
BRRVR	2614		

Hole: 7.875 in. @ 4280 ft.

TD:

TVD:

PBTD:

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee	
		6. INDIAN, ALLOTTEE OR TRIBE NAME:	
		7. UNIT OR CO AGREEMENT NAME:	
1. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>		8. WELL NAME AND NUMBER: Crane 6-7	
2. NAME OF OPERATOR: Fellows Energy Ltd.		9. API NUMBER: 4303330053	
3. ADDRESS OF OPERATOR: 807 N. Pinewood Circle Price		10. FIELD AND POOL, OR WILDCAT: Wildcat	PHONE NUMBER: (435) 650-4492
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 2363' FNL 1970' FWL		COUNTRY: Rich	
OILQTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 7 T6N R8E S		STATE: UTAH	

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 5/3/2004	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input checked="" type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMBING PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER:
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

2.2. The status of the well, whether drilling, producing, injecting or inactive.

Drilling of the Crane 6-7 was completed on 5/1/04.

2.3. A description of the well bore configuration indicating depth, casing strings, cement tops if known, and hole size.

Wellbore Diameter: 7-7/8" drilled to a total depth of 4280'.

Surface Casing: 8-5/8" J-55 24#/ft set at 528' with cement to surface.

2.4. The tops of known geologic markers or formations.

Wasatch	Surface
Unconformity	1516'
Frontier	1516'
Aspen Shale	2234'
Bear River	2614'

2.5. The plugging program approved by the appropriate federal agency if the well is located on federal or Indian land.

We will leave the drilling mud (description attached) in the well bore and place a 100' class G cement balance plug from 2,700' to 2,200' and from 2,100' to 1,600' and from 1,500' to 1,000' and from 900' to 300' and from 300' to surface, pull remaining drill pipe and 1" 30' cement to surface.

NAME (PLEASE PRINT) <u>Clifford Murray</u>	TITLE <u>Exploitationist, Project Manager</u>
SIGNATURE <u>Clifford Murray</u>	DATE <u>5/3/2004</u>

(This space for State use only)

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING

DATE: 5/3/2004  
BY: D. K. Dent

\* See Conditions of Approval (Attachment 1)

COPY SENT TO OPERATOR

Date: 5-4-04  
Initials: CHD



State of Utah

Department of  
Natural Resources

Division of  
Oil, Gas & Mining

ROBERT L. MORGAN  
*Executive Director*

LOWELL P. BRAXTON  
*Division Director*

MICHAEL O. LEAVITT  
*Governor*

OLENE S. WALKER  
*Lieutenant Governor*

## ***CONDITIONS OF APPROVAL TO PLUG AND ABANDON WELL***

Well Name and Number: Crane 6-7  
API Number: 43-033-30053  
Operator: Fellows Energy Ltd.  
Reference Document: Original Sundry Notice dated May 3, 2004,  
received by DOGM on May 3, 2004

### Approval Conditions:

1. Notify the Division at least 24 hours prior to conducting abandonment operations. Please call Dan Jarvis at 801-538-5338.
2. Operator shall ensure that cement remains at surface and shall RIH and top off as needed.
3. A dry hole marker shall be erected in accordance with R649-3-24-7 unless a variance for a subsurface marker is requested by the operator and approved by the Division.
4. Surface reclamation shall be done in accordance with R649-3-34 – Well Site Restoration. Evidence of compliance with this rule should be supplied to the Division upon completion of reclamation.
5. Form 8 – Well Completion or Recompletion Report and Log shall be submitted to the Division upon completion of work.
6. All requirements in the Oil and Gas Conservation General Rule R649-3-24 shall apply.
7. If there are any changes to the plugging procedure or the wellbore configuration, notify Dustin Doucet at 801-538-5281 prior to continuing with the procedure.
8. All other requirements for notice and reporting in the Oil and Gas Conservation General Rules shall apply.

Dustin K. Doucet  
Petroleum Engineer

May 3, 2004  
Date

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

## SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
2. NAME OF OPERATOR: Fellows Energy Ltd.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 807 N. Pinewood Circle CITY Price STATE UT ZIP 84501		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2363' FNL 1970' FWL		8. WELL NAME and NUMBER: Crane 6-7
PHONE NUMBER: (435) 650-4492		9. API NUMBER: 4303330053
		10. FIELD AND POOL, OR WILDCAT: Wildcat

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 7 T6N R8E S

COUNTY: Rich

STATE: UTAH

### 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Weekly Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

### 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

4/9/04—MIRT. Rig up. Slip drilling line. Test BOP and well control equip. PU BHA. RIH and tag up @ 417' KB. Commence drilling cement out of casing

4/10/04—Drilled to 580'. Survey @ 510' = 5°. Drill ahead to 643'. Survey @ 570' = 5.5°. TOOH and lay down top stabilizer. RIH w/Corion Express BHA with stabilizers @ 1' and 29'. Drill ahead to 731' with 8 to 10,000# on bit. Survey @ 650 = 6.5°. TOOH and lay down core barrel. Wait 1.5 hrs on tools. P.U 7 7/8" HTC MX-18 re-run bit, bit sub, 2-6 7/8" spiral collars, stabilizer and RIH with Corion collars and pipe. Drill ahead to 825' with 10-12,000# on bit.

4/11/04—Drill from 825' to 1,280'. Survey @ 828' = 5°. Survey @ 911' = 4 3/4°. Survey @ 973' = 3 3/4°. Survey @ 1,063' = 3 1/4°. Survey @ 1,150' = 2 3/4°.

4/12/04—Drill ahead to 1,384'. Survey @ 1,242' = 2 1/4°. Survey @ 1,329' = 2 1/2°. Survey @ 1,430' = 2 1/2° TOOH and LD 6 7/8" drill collars and bit. TIH with PDC coring bit with plug bit and core barrel. Drill ahead from 1,384' to 1,510'. ROP dropped @ 1,506' to <2'/hr. Prep to TOOH.

4/13/04—Drill to 1,510. TOOH and LD coring bit and core barrel. PDC core bit wiped out. Plug bit OK. P.U. tricone bit and BHA and TIH. 10' fill. Drill ahead from 1,510' to 1,623' w/15,000-20,000# on bit. Survey @ 1,543' = 2 3/4°.

4/14/04—Drill from 1,623' to 1,946' w/12,000-28,000# on bit.

4/15/04—Drill from 1946' to 2113'. TOOH. Pick up coring tools. TIH. Begin coring.

416/04—Core from 2, 113' to 2,137'. Wireline retrieve core. No coal. Core from 2,137' to 2,158'. Wireline retrieve core. Core from 2,158' to 2,166'. Coring rate as low as 1 1/2 hrs/ft. Wireline retrieve core. Core from 2,166' to 2,167'.

NAME (PLEASE PRINT) Steven L. Prince

TITLE Vice President, Operations

SIGNATURE

DATE 4/17/2004

CONFIDENTIAL

(This space for State use only)

RECEIVED

APR 19 2004

DIV. OF OIL, GAS & MINING

DOUBLE JACK TESTING & SERVICES, INC.  
Phone (307) 789-9213

B.O.P TEST REPORT

RECEIVED

APR 14 2004

DIV. OF OIL, GAS & MINING

B.O.P. TEST PERFORMED ON (DATE) 4/8/04

OIL COMPANY Fellows Energy

WELL NAME & NUMBER Crane 6-7 43-033-30053

SECTION 6N

TOWNSHIP 8E

RANGE 7S

COUNTY & STATE Rich, Utah

DRILLING CONTRACTOR Union Drilling #14

OIL COMPANY SITE REPRESENTATIVE \* Cliff Murray

RIG TOOL PUSHER \* Rex

TESTED OUT OF Evanston, Wyoming

NOTIFIED PRIOR TO TEST \_\_\_\_\_

COPIES OF THIS TEST REPORT SENT TO: Utah Oil & Gas Division

BLM- Salt Lake City, Utah

ORIGINAL CHART & TEST REPORT ON FILE AT:

DOUBLE JACK TESTING & SERVICES, INC.  
PO BOX 2097  
EVANSTON, WY 82930

TESTED BY: J. Bruce

# Double Jack Testing & Services Inc.

FIELD TICKET

No 20488

Accounting Office: P.O. Box 516 Shoshoni, WY 82649 • (307) 876-9390  
Field Operations: Shoshoni, WY (307) 876-9390  
Evanston, WY (307) 789-9213  
Rock Springs, WY (307) 382-4020  
Big Piney, WY (307) 276-5265  
Vernal, UT (435) 781-0448

DATE 4-8-04  
☒ OPERATOR Fellows Energy  
☐ CONTRACTOR Union Drlg. Rig #14  
WELL NAME Crane 6-7 6N8E S.7

COUNTY Rich STATE Utah SECTION 807 N. Pinewood Circle Price, Utah TOWNSHIP 84501 RANGE 84501

Items Tested:	LOW TEST PSI	TIME HELD MINUTES	HIGHEST PSI	TIME HELD MINUTES	
Top Pipe Rams	<u>250</u>	<u>5</u>	<u>2,000</u>	<u>15</u>	Closing Unit PSI <u>1,300</u>
Bottom Pipe Rams	<u>N/A</u>				Closing Time of Rams <u>6 secs.</u>
Blind Rams	<u>250</u>	<u>5</u>	<u>2,000</u>	<u>15</u>	Closing Time of Annular <u>N/A</u>
Annular B.O.P.	<u>N/A</u>				Closed Casing Head Valve <u>yes</u>
Choke Manifold	<u>250</u>	<u>5</u>	<u>2,000</u>	<u>15</u>	Set Wear Sleeve _____
Choke Line	<u>250</u>	<u>5</u>	<u>2,000</u>	<u>15</u>	COMMENTS _____
Kill Line Valve	<u>250</u>	<u>5</u>	<u>2,000</u>	<u>15</u>	_____
Super Choke	<u>N/A</u>				_____
Upper Kelly	<u>250</u>	<u>5</u>	<u>2,000</u>	<u>15</u>	_____
Lower Kelly	<u>N/A</u>				_____
Floor Valve	<u>250</u>	<u>5</u>	<u>2,000</u>	<u>15</u>	_____
Dart Valve	<u>250</u>	<u>5</u>	<u>2,000</u>	<u>15</u>	_____
Casing	<u>N/A</u>				_____

## ADDITIONAL TESTS & COMMENTS

DRILLING ☒ COMPLETION ☐

QUANTITY	RATES	CHARGES
UNIT	UNIT RATES	
	ADDITIONAL	
20 miles	MILEAGE	
45 gals.	ANTIFREEZE	
	OTHER	

TEST PLUG 8 5/8" Larkin  
TOP SUB. 4 1/2 IF  
KELLY SUB. 4 1/2 IF N/C  
X-OVER SUB. 4 1/2 IF x 3 1/2 IF  
OTHER \_\_\_\_\_

\$50.00  
\$50.00  
\$50.00

\$1,000.00

\$40.00  
\$67.50

Joe Bruce  
TESTED BY  
174  
DOUBLE JACK TESTING UNIT NUMBER

SUBTOTAL \$1,257.50  
TAX \_\_\_\_\_  
TOTAL \_\_\_\_\_

PURCHASE ORDER #

COMPANY REPRESENTATIVE

## NOTICE TO ALL CUSTOMERS

If this account shall not be paid when due and it is placed with an attorney for collection, or if suit be instituted for collection, the undersigned agree(s) to pay in either case, reasonable expense of collection including attorney's fees and court cost in compliance with TRUTH IN LENDING AND THE UNIFORM CONSUMER CREDIT CODE, the following information disclosure, under the terms of our regular accounts, all amounts for service due and payable within THIRTY (30) DAYS from the receipt of an invoice for such services. A LATE CHARGE will be assessed when accounts are not paid when due. THE LATE CHARGE is computed by a "periodic rate" 1-3/4% PER MONTH which is an ANNUAL PERCENTAGE RATE OF 21% to the previous balance in the account on the billing date. No further credit can be extended on unpaid delinquent accounts until the delinquent account is paid in full. The contractor will not be held liable for damages caused by acts or omissions in circumstances that could not be reasonably anticipated in performing the work done as set forth above.



# SERVICES

[illegible]

COMPANY: Fellows Energy  
CONTRACTOR: Union Drilling Rig #14  
WELL NAME: Crane 6-7  
DATE: 4/8/04  
TEST UNIT: 174  
TESTER(S): J. Bruce

## Accumulator Function Test

TO CHECK THE USABLE FLUID STORED IN THE NITROGEN BOTTLES ON THE ACCUMULATOR ( O.S.O. #2 section III.A.2.c.i. or ii or iii)

1. Make sure all rams and annular are open and if applicable HCR is closed.
2. Ensure accumulator is pumped up to working pressure! (Shut off all pumps)
3. Open HCR Valve. (If applicable)
4. Close annular.
5. Close **all** pipe rams.
6. Open one set of the pipe rams to simulate closing the blind ram.
7. If you have a 3 ram stack open the annular to achieve the 50±% safety factor for 5M and greater systems).
8. Accumulator pressure should be 200 psi over **desired** precharge pressure, ( Accumulator working pressure { 1500 psi = 750 **desired** psi } { 2000 and 3000 psi = 1000 **desired** psi } ).

9. Record the remaining pressure 1,300 psi.  
If annular is closed, open it at this time and close HCR.

TO CHECK THE CAPACITY OF THE ACCUMULATOR PUMPS ( O.S.O. #2 section III.A.2.f.)

Shut the accumulator bottles or spherical, ( isolate them from the pumps & manifold) open the bleed off valve to the tank,( manifold psi should go to 0 psi) close bleed valve.

1. Open the HCR valve, ( if applicable).
2. Close annular.
3. With **pumps** only, time how long it takes to regain manifold pressure to 200 psi over **desired** precharge pressure! ( Accumulator working pressure { 1500 psi = 750 **desired** psi } { 2000 and 3000 psi = 1000 **desired** psi } ).

4. Record elapsed time 15 seconds. ( 2 minutes or less)

TO CHECK THE PRECHARGE ON BOTTLES OR SPHERICAL ( O.S.O. #2 section III.A.2.d.)

1. Open bottles back up to the manifold ( pressure should be above the **desired** precharge pressure, { 1500 psi = 750 **desired** psi } { 2000 and 3000 psi = 1000 **desired** psi } ) may need to use pumps to pressure back up.
2. With power to pumps shut off open bleed line to the tank.
3. Watch and record where the pressure drops, ( **accumulator** psi ).

Record the pressure drop 775 psi.

If pressure drops below MINIMUM precharge, (Accumulator working pressure { 1500 psi = 700 min. } { 2000 and 3000psi = 900 psi min. } ) each bottle shall be independently checked with a gauge.




AM TYPE DOP


Fellows Energy

odel  
ID. CHIOKE VALVE


odel

Crane  
Union Rig #14





TESTED BY:  
DOUBLE JACK TESTING  
& SERVICES, INC.  
EVANSTON  
(307) 789-9213  
CASPER  
(307) 265-3678  
SHOSHONI  
(307) 876-2308  
VERNAL  
(801) 781-0448  
MICHIGAN  
(517) 773-4800  
*Fellows Energy Crane*  
*Union #14 4-8-04*  
GC GC-15430



TESTED BY:  
DOUBLE JACK TESTING  
& SERVICES, INC.

SHOSHONI  
(307) 876-2308

EVANSTON  
(307) 789-9213

VERNAL  
(801) 781-0448

CASPER  
(307) 265-3678


MICHIGAN  
(517) 773-4800

*Fellows Energy Crane*  
*Union Rig 14 7-8-04*  
GC GC-15430

## Accumulator Function Test

TO CHECK THE USABLE FLUID STORED IN THE NITROGEN BOTTLES ON THE ACCUMULATOR ( O.S.O. #2 section III.A.2.c.i. or ii or iii)

1. Make sure all rams and annular are open and if applicable HCR is closed.
2. Ensure accumulator is pumped up to working pressure! (Shut off all pumps)
3. Open HCR Valve. (If applicable)
4. Close annular.
5. Close **all** pipe rams.
6. Open one set of the pipe rams to simulate closing the blind ram.
7. If you have a 3 ram stack open the annular to achieve the 50±% safety factor for 5M and greater systems).
8. Accumulator pressure should be 200 psi over **desired** precharge pressure, ( Accumulator working pressure { 1500 psi = 750 **desired** psi } { 2000 and 3000 psi = 1000 **desired** psi } ).
9. Record the remaining pressure 1,300 psi.  
If annular is closed, open it at this time and close HCR.



TO CHECK THE CAPACITY OF THE ACCUMULATOR PUMPS ( O.S.O. #2 section III.A.2.f.)

Shut the accumulator bottles or spherical, ( isolate them from the pumps & manifold) open the bleed off valve to the tank,( manifold psi should go to 0 psi) close bleed valve.



1. Open the HCR valve, ( if applicable).
2. Close annular.
3. With **pumps** only, time how long it takes to regain manifold pressure to 200 psi over **desired** precharge pressure! ( Accumulator working pressure { 1500 psi = 750 **desired** psi } { 2000 and 3000 psi = 1000 **desired** psi } ).
4. Record elapsed time 15 seconds. ( 2 minutes or less)



TO CHECK THE PRECHARGE ON BOTTLES OR SPHERICAL ( O.S.O. #2 section III.A.2.d.)

1. Open bottles back up to the manifold ( pressure should be above the **desired** precharge pressure, { 1500 psi = 750 **desired** psi } { 2000 and 3000 psi = 1000 **desired** psi } ) may need to use pumps to pressure back up.
2. With power to pumps shut off open bleed line to the tank.
3. Watch and record where the pressure drops, ( **accumulator** psi ).

Record the pressure drop 775 psi.

If pressure drops below MINIMUM precharge, (Accumulator working pressure { 1500 psi = 700 min. } { 2000 and 3000psi = 900 psi min. }) each bottle shall be independently checked with a gauge.







AM TYPE DOP






Fellows Energy

Crane

Union Rig #14

odel  
D. CHOK VALVE

odel





STATE OF UTAH  
DIVISION OF OIL GAS AND MINING  
PLUGGING OPERATIONS

Well Name: Crane 6-7 API Number: 43-033-30053  
 Qtr/Qtr: SEnw Section: 7 Township: 6N Range: 8E County: Rich  
 Company Name: Fellows Energy Ltd (N2560) / Cliff Murray 435-650-4492  
 Lease: State \_\_\_\_\_ Fee X Federal \_\_\_\_\_ Indian \_\_\_\_\_  
 Surface Owner: Desert Land & Livestock/James Sewell Area Foreman 435-793-4288  
 Inspector: Lisha Cordova Date: May 3, 2004

Casing Tested: YES\_\_\_ NO\_\_\_ Results:

Cementing Company: Halliburton/Lennie Cook

Rig: Union Rig #14

Draw a wellbore diagram as plugged:

COMMENTS:

Plugs 1-4 (balanced plugs):

500' each of Class G cement (175 sxs/35.8 bbls, 15.8 wgt/1.15 yld w/ 2% Calcium Chloride) were set @ 2700-2200', 2100-1600', 1500-1000', & 900-400', pumped cmt @ 5 bpm/145 psi.

Plug 5 (surface plug):


300' of Class G cement (125 sxs/25.6 bbls, 15.8 wgt/1.15 yld w/2% Calcium Chloride) was set @ 300-surface, pumped cmt @ 5 bpm/85 psi.

Plug 6 (surface plug/part 2):

Used 1" pipe to set a 50' plug (32 sxs/6.6 bbls, 15.8 wgt/1.15 yld w/2% Calcium Chloride) between annulus, pumped cmt @ 1 bpm/22 psi. Fresh water between all plugs.

5/4/04 Op planning to weld metal plate (w/well name & location) to casing in the AM for below grade burial per L/O request.

(Copy of cement ticket to file)



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☒  
(highlight changes)

<b>APPLICATION FOR PERMIT TO DRILL</b>		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee	
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		7. UNIT or CO-AGREEMENT NAME:	
2. NAME OF OPERATOR: Fat Chance Oil & Gas, LLC		8. WELL NAME and NUMBER: Crane 6-7	
3. ADDRESS OF OPERATOR: PO Box 7370 CITY Sheridan STATE WY ZIP 82801		9. FIELD AND POOL, OR WILDCAT: Wildcat	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 2363' FNL 1970' FWL AT PROPOSED PRODUCING ZONE: Same		10. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW Sec. 7 T6N R8E	
13. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 5 miles west of Evanston, Wyoming		11. COUNTY: Rich	12. STATE: UTAH
14. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 3077'	15. NUMBER OF ACRES IN LEASE: 52,395	16. NUMBER OF ACRES ASSIGNED TO THIS WELL: 160	
17. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 3279'	18. PROPOSED DEPTH: 5,000	19. BOND DESCRIPTION: Utah DOGM Surety# 885588C	
20. ELEVATIONS (SHOW WHETHER OF, RT, GR, ETC.): 6802' GR	21. APPROXIMATE DATE WORK WILL START: 6/15/2001	22. ESTIMATED DURATION: 10 days	

**CONFIDENTIAL**

23. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
12 1/4"	9 5/8"	H-40	32.3#	500	G-Poz	250 sx	1.77 12.5# lead
						50 sx	1.17 15.8" tail
8 3/4"	7"	K-55	20#	5,000	G-35/65 Poz	150 sx	2.34 11# lead
						50 sx	1.27 14.2# tail

24. ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

**RECEIVED**  
JUN 28 2004  
DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Lorna James TITLE Administrative Assistant

SIGNATURE Lorna James DATE 5-24-01

(This space for State use only)

API NUMBER ASSIGNED: 43-033-30053

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 06-13-01  
(See Instructions on Reverse Side)  
By: [Signature]

**RECEIVED**  
MAY 25 2001  
DIVISION OF  
OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☒  
(highlight changes)

APPLICATION FOR PERMIT TO DRILL		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
8. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		7. UNIT or CA AGREEMENT NAME:
2. NAME OF OPERATOR: Fat Chance Oil & Gas, LLC <i>Fellows Energy LTD</i>		8. WELL NAME and NUMBER: Crane 6-7
3. ADDRESS OF OPERATOR: PO Box 7370 CITY Sheridan STATE WY ZIP 82801 PHONE NUMBER: (307) 673-1500		9. FIELD AND POOL, OR WILDCAT: Wildcat
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 2363' FNL 1970' FWL <i>Bth hole</i> AT PROPOSED PRODUCING ZONE: same <i>162'S 220'E</i>		10. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW <i>Sec. 7</i> T6N R8E
13. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 5 miles west of Evanston, Wyoming <i>45/8437N 492921E</i>		11. COUNTY: Rich
14. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET): 3077'		12. STATE: UTAH
15. NUMBER OF ACRES IN LEASE: 52,395		16. NUMBER OF ACRES ASSIGNED TO THIS WELL: 160
17. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET): 3279'		19. BOND DESCRIPTION: Utah DOGM Surety# 885588C
20. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 6802' GR		22. ESTIMATED DURATION: 10 days

23. PROPOSED CASING AND CEMENTING PROGRAM						
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT			
12 1/4"	<del>9 5/8"</del> H-40 32.3#	500	G-Poz	250 sx	1.77	12.5# lead
	<del>8 5/8"</del> J-55 24#			50 sx	1.17	15.8" tail
<del>8 3/4"</del>	7" K-55 20#	5,000	G-35/65 Poz	150 sx	2.34	11# lead
7 7/8"	5 1/2 N-80 17#			50 sx	1.27	14.2# tail

24. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR CORPORATION OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) Lorna James TITLE Administrative Assistant

SIGNATURE *Lorna James* DATE 5-24-01

(This space for State use only)

API NUMBER ASSIGNED: 43-033-30053

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 06-13-01  
(See Instructions on Reverse Side)  
By: *[Signature]*

RECEIVED  
JUN 28 2004  
DIV. OF OIL, GAS & MINING

RECEIVED  
MAY 25 2001  
DIVISION OF  
OIL, GAS AND MINING

REPORT OF WATER ENCOUNTERED DURING DRILLING

Well name and number: Crane 6-7

API number: 4300330053

Well Location: QQ SENW Section 7 Township 6N Range 8E County Rich

Well operator: Fellows Energy Ltd

Address: 807 N. Pinewood Circle

city Price state Ut zip 84501

Phone: (435) 650-4492

Drilling contractor: Midway Drilling

Address: 1430 N. 500 W.

city Nephi state Ut zip 84648

Phone: (435) 623-8000

Water encountered (attach additional pages as needed):

DEPTH		VOLUME (FLOW RATE OR HEAD)	QUALITY (FRESH OR SALTY)
FROM	TO		
			Well drilled with mud from
			surface. No water shows.

Formation tops:  
(Top to Bottom)

1	<u>Wasatch</u>	2	<u>Frontier</u>	3	<u>Aspen</u>
4	<u>Bear river</u>	5		6	
7		8		9	
10		11		12	

RECEIVED

JUN 28 2004

If an analysis has been made of the water encountered, please attach a copy of the report to this form.

DIV. OF OIL, GAS & MINING

I hereby certify that this report is true and complete to the best of my knowledge.

NAME (PLEASE PRINT) Clifford Murray

TITLE Exploitationist

SIGNATURE

*Clifford Murray*

DATE

5/25/2004

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: NA
2. NAME OF OPERATOR: Fellows Energy Ltd		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NA
3. ADDRESS OF OPERATOR: 807 N Pinewood Circle CITY Price STATE Ut ZIP 84501		7. UNIT or CA AGREEMENT NAME: NA
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2,363' FNL 1,970' FWL		8. WELL NAME and NUMBER: Crane 6-7
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 7 6N 8E		9. API NUMBER: 4303330053
COUNTY: Rich		10. FIELD AND POOL, OR WILDCAT: Wildcat
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will start: _____  <input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only)  Date of work completion: 5/3/2004	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Plugged well using G cement @ 15.8ppg. 175 sack (35.8 bbls) balance plugs set @ 2,700'-2,200', 2,100'-1,600', 1,500'-1,000', 900'-400' and 125 sack (25.6 bbls) 300'-surface. Drilling mud used to drill well between balance plugs. Pulled last of drill pipe. Used 1" pipe to set 32 sack balance plug at surface. Welded on cap with well name, number and location for below grade burial.

**RECEIVED**  
**JUN 28 2004**  
DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) <u>Clifford Murray</u>	TITLE <u>Exploitationist</u>
SIGNATURE <u><i>Clifford Murray</i></u>	DATE <u>5/25/2004</u>

(This space for State use only)

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8  
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> OTHER <input type="checkbox"/>		<b>CONFIDENTIAL</b>  PERIOD EXPIRED ON 6-3-05	5. LEASE DESIGNATION AND SERIAL NUMBER: NA																																																																							
b. TYPE OF WORK: NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER <input type="checkbox"/>			6. IF INDIAN, ALLOTTEE OR TRIBE NAME NA																																																																							
2. NAME OF OPERATOR: Fellows Energy Ltd			7. UNIT or CA AGREEMENT NAME NA																																																																							
3. ADDRESS OF OPERATOR: 807 N Pinewood Circle CITY Price STATE Ut ZIP 84501			8. WELL NAME and NUMBER: Crane 6-7																																																																							
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 2,363' FNL 1,970' FWL AT TOP PRODUCING INTERVAL REPORTED BELOW: NA AT TOTAL DEPTH: 2,525' FNL 2,190' FWL		9. API NUMBER: 4303330053	10. FIELD AND POOL, OR WILDCAT Wildcat																																																																							
14. DATE SPUDDED: 3/25/2004		15. DATE T.D. REACHED: 5/2/2004	16. DATE COMPLETED: 5/3/2004	17. ELEVATIONS (DF, RKB, RT, GL): 6.802' GR																																																																						
18. TOTAL DEPTH: MD 4,280 TVD 4,276		19. PLUG BACK T.D.: MD TVD		20. IF MULTIPLE COMPLETIONS, HOW MANY? *																																																																						
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) <input checked="" type="checkbox"/> Inclineretry, <input checked="" type="checkbox"/> Induction, <input checked="" type="checkbox"/> Microlog, <input checked="" type="checkbox"/> Density Compensated Neutron, <input checked="" type="checkbox"/> Mud		23. WAS WELL CORED? NO <input type="checkbox"/> YES <input checked="" type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input type="checkbox"/> YES <input checked="" type="checkbox"/> (Submit copy)																																																																								
24. CASING AND LINER RECORD (Report all strings set in well)																																																																										
<table border="1"><thead><tr><th>HOLE SIZE</th><th>SIZE/GRADE</th><th>WEIGHT (#/ft.)</th><th>TOP (MD)</th><th>BOTTOM (MD)</th><th>STAGE CEMENTER DEPTH</th><th>CEMENT TYPE &amp; NO. OF SACKS</th><th>SLURRY VOLUME (BBL)</th><th>CEMENT TOP **</th><th>AMOUNT PULLED</th></tr></thead><tbody><tr><td>12 1/4</td><td>8.62" J55</td><td>24</td><td>0</td><td>525</td><td></td><td>G 350</td><td>0</td><td>Surface</td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr></tbody></table>					HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED	12 1/4	8.62" J55	24	0	525		G 350	0	Surface																																																			
HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED																																																																	
12 1/4	8.62" J55	24	0	525		G 350	0	Surface																																																																		
25. TUBING RECORD																																																																										
<table border="1"><thead><tr><th>SIZE</th><th>DEPTH SET (MD)</th><th>PACKER SET (MD)</th><th>SIZE</th><th>DEPTH SET (MD)</th><th>PACKER SET (MD)</th><th>SIZE</th><th>DEPTH SET (MD)</th><th>PACKER SET (MD)</th></tr></thead><tbody><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr></tbody></table>					SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)																																																													
SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)																																																																		
26. PRODUCING INTERVALS																																																																										
<table border="1"><thead><tr><th>FORMATION NAME</th><th>TOP (MD)</th><th>BOTTOM (MD)</th><th>TOP (TVD)</th><th>BOTTOM (TVD)</th></tr></thead><tbody><tr><td>(A)</td><td></td><td></td><td></td><td></td></tr><tr><td>(B)</td><td></td><td></td><td></td><td></td></tr><tr><td>(C)</td><td></td><td></td><td></td><td></td></tr><tr><td>(D)</td><td></td><td></td><td></td><td></td></tr></tbody></table>					FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	(A)					(B)					(C)					(D)																																																	
FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)																																																																						
(A)																																																																										
(B)																																																																										
(C)																																																																										
(D)																																																																										
27. PERFORATION RECORD																																																																										
<table border="1"><thead><tr><th>INTERVAL (Top/Bot - MD)</th><th>SIZE</th><th>NO. HOLES</th><th>PERFORATION STATUS</th></tr></thead><tbody><tr><td></td><td></td><td></td><td>Open <input type="checkbox"/> Squeezed <input type="checkbox"/></td></tr><tr><td></td><td></td><td></td><td>Open <input type="checkbox"/> Squeezed <input type="checkbox"/></td></tr><tr><td></td><td></td><td></td><td>Open <input type="checkbox"/> Squeezed <input type="checkbox"/></td></tr><tr><td></td><td></td><td></td><td>Open <input type="checkbox"/> Squeezed <input type="checkbox"/></td></tr></tbody></table>					INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS				Open <input type="checkbox"/> Squeezed <input type="checkbox"/>				Open <input type="checkbox"/> Squeezed <input type="checkbox"/>				Open <input type="checkbox"/> Squeezed <input type="checkbox"/>				Open <input type="checkbox"/> Squeezed <input type="checkbox"/>																																																		
INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS																																																																							
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>																																																																							
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>																																																																							
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>																																																																							
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>																																																																							
28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.																																																																										
<table border="1"><thead><tr><th>DEPTH INTERVAL</th><th>AMOUNT AND TYPE OF MATERIAL</th></tr></thead><tbody><tr><td></td><td></td></tr><tr><td></td><td></td></tr><tr><td></td><td></td></tr></tbody></table>					DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL																																																																				
DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL																																																																									
29. ENCLOSED ATTACHMENTS:																																																																										

☒ ELECTRICAL/MECHANICAL LOGS ☒ GEOLOGIC REPORT ☐ DST REPORT ☒ DIRECTIONAL SURVEY  
☒ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER: \_\_\_\_\_

DIVISION OF OIL, GAS & MINING

P&A



**31. INITIAL PRODUCTION**
**INTERVAL A (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL B (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL C (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL D (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)**
**33. SUMMARY OF POROUS ZONES (Include Aquifers):**

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

**34. FORMATION (Log) MARKERS:**

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				Wasatch	0
				Unconformity	1.452
				Frontier	1.452
				Aspen	2.234
				Bear River	2.614

**35. ADDITIONAL REMARKS (Include plugging procedure)**

G Cement-15.8ppg, 175 sack balance plugs @ 2,700'-2,200', 2,100'-1,600', 1,500'-1,000', 900'-400' and 125 sack 300' to surface

**36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.**

NAME (PLEASE PRINT) Clifford Murray

TITLE Exploitationist

SIGNATURE Clifford Murray

DATE 6/25/2004

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

CONFIDENTIAL

H Halliburton				<b>JOB SUMMARY</b>				SAP #/TICKET #		TICKET DATE																																																																
REGION NORTH AMERICA LAND				COUNTRY WESTERN				SAP #/TICKET # 3057115		TICKET DATE 05/03/04																																																																
MEMO ID / EMPL # G2487 / 122022				H.E.S. EMPLOYEE NAME LENNIE N. COOK				SAP #/TICKET # 3057115		TICKET DATE 05/03/04																																																																
LOCATION 10142 ROCK SPRINGS, WY				COMPANY Fellow Energy				SAP #/TICKET # 3057115		TICKET DATE 05/03/04																																																																
TICKET AMOUNT				WELL TYPE 02 GAS				SAP #/TICKET # 3057115		TICKET DATE 05/03/04																																																																
WELL LOCATION Evanston, WY				DEPARTMENT CEMENTING SERVICES 10003				SAP #/TICKET # 3057115		TICKET DATE 05/03/04																																																																
LEASE NAME Crane				SEC / TWP / R / NG SEC 7 TWP 6N RNG 8E				SAP #/TICKET # 3057115		TICKET DATE 05/03/04																																																																
H.E.S. EMP NAME / EMP # / (EXPOSURE HOURS)				HRS				HRS																																																																		
L. COOK 122022				15.0				15.0																																																																		
B. Lessman				15.0				15.0																																																																		
M. Olsen				15.0				15.0																																																																		
S. Burnham				15.0				15.0																																																																		
H.E.S. UNIT #S (R / T MILES)				R / T MILES				R / T MILES																																																																		
10547387 PICKUP 240				10243540 10025176 RCM 240				10026528*TK 10025027*660 240																																																																		
10026535*TK 10322492*660 240																																																																										
<div style="display: flex; justify-content: space-between;"> <div style="width: 30%;"> <p>Form Name: _____ Type: GAS</p> <p>Form Thickness: _____ From: _____ To: _____</p> <p>Packer Type: _____ Set At: _____</p> <p>Bottom Hole Temp: _____ Pressure: _____</p> <p>Retainer Depth: _____ Total Depth: _____</p> <p><b>Tools and Accessories</b></p> <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Type and Size</th> <th>Qty</th> <th>Make</th> </tr> </thead> <tbody> <tr><td>Float Collar</td><td></td><td></td></tr> <tr><td>Float Shoe</td><td></td><td></td></tr> <tr><td>Guide Shoe</td><td></td><td></td></tr> <tr><td>Centralizers</td><td></td><td></td></tr> <tr><td>Bottom Plug</td><td></td><td></td></tr> <tr><td>Top Plug</td><td></td><td></td></tr> <tr><td>PDF Collar</td><td></td><td></td></tr> <tr><td>PDF Shoe</td><td></td><td></td></tr> <tr><td>L Clamp</td><td></td><td></td></tr> <tr><td>DV Tool</td><td></td><td></td></tr> <tr><td>Plug Set</td><td></td><td></td></tr> <tr><td>Weld-a</td><td></td><td></td></tr> </tbody> </table> </div> <div style="width: 30%;"> <p><b>Materials And Tank Strap</b></p> <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Mud Type</th> <th>Density</th> <th>Lb/Gal</th> </tr> </thead> <tbody> <tr> <td>Disp. Fluid</td> <td></td> <td></td> </tr> </tbody> </table> </div> <div style="width: 30%;"> <p><b>Hours On Location</b></p> <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Date</th> <th>Hours</th> </tr> </thead> <tbody> <tr> <td>5/3</td> <td>15.00</td> </tr> <tr> <td>Total</td> <td>15.0</td> </tr> </tbody> </table> </div> <div style="width: 30%;"> <p><b>Operating Hours (Pumping)</b></p> <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Date</th> <th>Hours</th> </tr> </thead> <tbody> <tr> <td>5/3</td> <td>5.00</td> </tr> <tr> <td>Total</td> <td>5.0</td> </tr> </tbody> </table> </div> <div style="width: 30%;"> <p><b>OPERATING TIME (RIG UP/RIG DOWN)</b></p> <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>DATE</th> <th>HRS. / MIN.</th> </tr> </thead> <tbody> <tr> <td>5/3</td> <td>2</td> </tr> <tr> <td>TOTAL</td> <td>2</td> </tr> </tbody> </table> </div> </div>												Type and Size	Qty	Make	Float Collar			Float Shoe			Guide Shoe			Centralizers			Bottom Plug			Top Plug			PDF Collar			PDF Shoe			L Clamp			DV Tool			Plug Set			Weld-a			Mud Type	Density	Lb/Gal	Disp. Fluid			Date	Hours	5/3	15.00	Total	15.0	Date	Hours	5/3	5.00	Total	5.0	DATE	HRS. / MIN.	5/3	2	TOTAL	2
Type and Size	Qty	Make																																																																								
Float Collar																																																																										
Float Shoe																																																																										
Guide Shoe																																																																										
Centralizers																																																																										
Bottom Plug																																																																										
Top Plug																																																																										
PDF Collar																																																																										
PDF Shoe																																																																										
L Clamp																																																																										
DV Tool																																																																										
Plug Set																																																																										
Weld-a																																																																										
Mud Type	Density	Lb/Gal																																																																								
Disp. Fluid																																																																										
Date	Hours																																																																									
5/3	15.00																																																																									
Total	15.0																																																																									
Date	Hours																																																																									
5/3	5.00																																																																									
Total	5.0																																																																									
DATE	HRS. / MIN.																																																																									
5/3	2																																																																									
TOTAL	2																																																																									
<p><b>Hydraulic Horsepower</b></p> <p>Ordered: _____ Avail: _____ Used: _____</p> <p><b>Average Rates in BPM</b></p> <p>Treating: _____ Disp: _____ Overall: _____</p> <p><b>Cement Left in Pipe</b></p> <p>Feet: _____ Reason: _____</p>																																																																										
<b>Cement Data</b>																																																																										
Stage	Sacks	Cement	Bulk/Sks	Additives	W/Rq.	Yield	Lbs/Gal	BBLs																																																																		
1	175	AG-300	Bulk/Sks	2% C.C	5.00	1.15	15.80	35.8																																																																		
2	175	AG-300	Bulk/Sks	2% C.C	5.00	1.15	15.8	35.8																																																																		
3	175	AG-300	Bulk/Sks	2% C.C	5.00	1.15	15.8	35.8																																																																		
4	175	AG-300	Bulk/Sks	2% C.C	5.00	1.15	15.8	35.8																																																																		
5	125	AG-300	Bulk/Sks	2% C.C	5.00	1.15	15.8	25.6																																																																		
6	32	AG-300	Bulk/Sks	2% C.C	5	1.15	15.8	6.6																																																																		
<p><b>Circulating Breakdown</b></p> <p>Displacement: _____ Preflush: Gal - BBI _____ Type: _____</p> <p>Maximum: _____ Circulate Hole: Gal - BBI _____ Pad: Bbl - Gal _____</p> <p>Lost Returns-YES: _____ Excess / Return Gal BBI _____ Calc. Disp Bbl _____</p> <p>Cmt Rtn#Bbl: _____ Actual TOC: _____ Actual Disp. _____</p> <p>Average: _____ Frac. Gradient: _____ Treatment: Gal - BBI _____ Disp: Bbl-Gal _____</p> <p>Shut In: Instant _____ 15 Min. _____ 30 Min. _____ Cement Slurry: Gal - BBI _____ 176 _____</p> <p>Total Volume: Gal - BBI _____ 176 _____</p>																																																																										
<p><b>THE INFORMATION STATED HEREIN IS CORRECT</b></p> <p>CUSTOMER REPRESENTATIVE: _____ SIGNATURE: _____</p>																																																																										

Halliburton		Job Log		TICKET # 3057115		TICKET DATE 03/04	
REGION NORTH AMERICA LAND		NWA / COUNTRY WESTERN		BDA / STATE DENVER, CO		COUNTY Rich, Ut	
MRU ID / EMPL # G2487 / 122022		H.E.S. EMPLOYEE NAME LENNIE N. COOK		PSL DEPARTMENT 10003 CEMENTING SERVICES			
LOCATION 10142 ROCK SPRINGS, WY		COMPANY Fellow Energy		CUSTOMER REP / PHONE Cliff Murray			
TICKET AMOUNT		WELL TYPE 02 GAS		APIAUM # 43-033-30053			
WELL LOCATION Evanston, wy		DEPARTMENT CEMENTING SERVICES 10003		JOB PURPOSE CODE 7521			
LEASE / WELL # Crane		Well No. 6-7		SEC / TWP / RNG SEC 7 TWP 6N RNG 8E			
DATE	Time	Rate (BPM)	Volume (GAL)	Perps T C	Press. (PSI) Tbg Csg	Job Description / Remarks	
5/3/04	0500						Call Out
	0600						Safety meeting, Leave Yard
5/3/04	0900						On location
	915						Pre-job safety meeting
	0930						Rig Up
	1345						Safety meeting,
	1402						Start 1st Plug
	1403	5.0	10.0		65		Pump H2O Spacer
	1406				5000		Test Lines
	1415	5.0	35.8		145		Pump Cement, 175 sks Of AG-300 With 2% C.C. @ 15.8 PPG
	1424	2.0	3.8		65		Pump H2O Displacement
	1427	2.0	36.5		65		Pump Mud Displacement
	1437						Shut Down
	1439						End 1st Plug
	1519						Start 2nd plug
	1520	5.0	10.0		65		Pump H2O Spacer
	1525				5000		Test Lines
	1535	5.0	35.8		145		Pump Cement, 175 sks Of AG-300 With 2% C.C. @ 15.8 PPG
	1548	2.0	3.8		65		Pump H2O Displacement
	1550	2.0	25.5		65		Pump Mud Displacement
	1557						Shut Down
	1558						End 2nd Plug
	1837						Start 3rd Plug
	1838				65		Pump H2O Spacer
	1840				5000		Test Lines
	1846				145		Pump Cement, 175 sks Of AG-300 With 2% C.C. @ 15.8 PPG
	1856				65		Pump H2O Displacement
	1858				65		Pump Mud Displacement
	1900						Shut Down
	1901						End 3rd Plug
	1905						Wash up Truck to Pit
	1912						Shut Down
	1947						Start 4th plug
	1948	5.0	10.0		65		Pump H2O Spacer
	1955	5.0	35.8		145		Pump Cement, 175 sks Of AG-300 With 2% C.C. @ 15.8 PPG
	2002	2.0	3.8		65		Pump H2O Displacement
	2003	2.0	15.5		65		Pump Mud Displacement
	2007						Shut Down
	2008						End 4th Plug
	2049						Start 5th Plug
	2050	5.0	10.0		65		Pump H2O Spacer
	2055	5.0	25.6		85		Pump Cement, 125 sks Of AG-300 With 2% C.C. @ 15.8 PPG
	2059						Shut Down
	2100						End 5th Pug
	2200						Start 1" top Out
	2201	1.0	6.6		22		Pump Cement, 32 sks Of AG-300 With 2% C.C. @ 15.8 PPG
	2205						Shut Down
	2206						End Job
	2215						Post-job Safety Meeting
	2230						Rig Down
	0000						Leave Location

THANK YOU L ENNIE COOK AND CREW

# FELLOWS ENERGY

**CRANE**

**6-7**

**API Well No.:**

**31-Mar-04  
RICH CO., UTAH**

**8 5/8 SURFACE CASING**

**Customer Representative:  
CLIFF MURRAY  
Halliburton Operator:  
WAYNE MOUNT  
Ticket No.:  
3008090**


**RECEIVED  
JUN 28 2004  
DIV. OF OIL, GAS & MINING**



THANK YOU. WAYNE MOUNT AND CREW!!



# ROCK SPRINGS CEMENT



## Event Log

1 Start Job	16:06:36	2 Test Lines	16:08:30	3 Pump Spacer 1	16:09:39
4 Pump Cement	16:16:55	5 Shut Down / Drop Top Plug	16:48:08	6 Pump Displacement	16:48:38
7 Bump Plug	16:58:47	8 Check Floats	17:03:20		

Customer: **FELLOWS ENERGY**  
 Well Description: **CRANE 6-7**

Job Date: **3/31/04**  
 Operator: **WAYNE MOUNT**

Ticket #: **3008090**  
 Job Type: **8 5/8 SURFACE CASING**



CemWin v1.5.0  
 31-Mar-04 17:25

State  
Copy

# Fellow Energy

## Crane

### 6-7

API Well No.:  
43-033-30053

3-May-04  
Rich, Ut

## PTA


Customer Representative:  
Cliff Murray  
Halliburton Operator:  
LENNIE N. COOK  
Ticket No.:  
3057115

RECEIVED  
JUN 28 2004  
DIV. OF OIL, GAS & MINING








		<h1>Job Log</h1>		TICKET # 3057115		DATE 5/3/04	
REGION NORTH AMERICA LAND		NWA / COUNTRY WESTERN		BDA / STATE DENVER, CO		COUNTY Rich, Ut	
MSU ID / EMPL # G2487 / 122022		H.E.S. EMPLOYEE NAME LENNIE N. COOK		PSL DEPARTMENT 10003 CEMENTING SERVICES			
LOCATION 10142 ROCK SPRINGS, WY		COMPANY Fellow Energy		CUSTOMER REP / PHONE Cliff Murray			
TICKET AMOUNT		WELL TYPE 02 GAS		APIUM # 43-033-30053			
WELL LOCATION Evanston, wy		DEPARTMENT CEMENTING SERVICES 10003		JOB PURPOSE CODE 7521			
LEASE / WELL # Crane		Well No. 6-7		SEC / TWP / RNG SEC 7 TWP 6N RNG 8E			

DATE	Time	Rate (BPM)	Volume (GAL)	Pumps T C	Press. (PSI) Reg Csg	Job Description / Remarks
5/3/04	0500					Call Out
	0600					Safety meeting, Leave Yard
5/3/04	0900					On location
	915					Pre-job safety meeting
	0930					Rig Up
	1345					Safety meeting,
	1402					Start 1st Plug
	1403	5.0	10.0		65	Pump H2O Spacer
	1406				5000	Test Lines
	1415	5.0	35.8		145	Pump Cement, 175 sks Of AG-300 With 2% C.C. @ 15.8 PPG
	1424	2.0	3.8		65	Pump H2O Displacement
	1427	2.0	36.5		65	Pump Mud Displacement
	1437					Shut Down
	1439					End 1st Plug
	1519					Start 2nd plug
	1520	5.0	10.0		65	Pump H2O Spacer
	1525				5000	Test Lines
	1535	5.0	35.8		145	Pump Cement, 175 sks Of AG-300 With 2% C.C. @ 15.8 PPG
	1548	2.0	3.8		65	Pump H2O Displacement
	1550	2.0	25.5		65	Pump Mud Displacement
	1557					Shut Down
	1558					End 2nd Plug
	1837					Start 3rd Plug
	1838				65	Pump H2O Spacer
	1840				5000	Test Lines
	1846				145	Pump Cement, 175 sks Of AG-300 With 2% C.C. @ 15.8 PPG
	1856				65	Pump H2O Displacement
	1858				65	Pump Mud Displacement
	1900					Shut Down
	1901					End 3rd Plug
	1905					Wash up Truck to Pit
	1912					Shut Down
	1947					Start 4th plug
	1948	5.0	10.0		65	Pump H2O Spacer
	1955	5.0	35.8		145	Pump Cement, 175 sks Of AG-300 With 2% C.C. @ 15.8 PPG
	2002	2.0	3.8		65	Pump H2O Displacement
	2003	2.0	15.5		65	Pump Mud Displacement
	2007					Shut Down
	2008					End 4th Plug
	2049					Start 5th Plug
	2050	5.0	10.0		65	Pump H2O Spacer
	2055	5.0	25.6		85	Pump Cement, 125 sks Of AG-300 With 2% C.C. @ 15.8 PPG
	2059					Shut Down
	2100					End 5th Pug
	2200					Start 1" top Out
	2201	1.0	6.6		22	Pump Cement, 32 sks Of AG-300 With 2% C.C. @ 15.8 PPG
	2205					Shut Down
	2206					End Job
	2215					Post-job Safety Meeting
	2230					Rig Down
	0000					Leave Location
						THANK YOU LENNIE COOK AND CREW

# Halliburton Energy Services



## Event Log

Start 1ST Plug	14:02:19	Pump H2O Spacer	14:03:28	Test Lines	14:06:33
Pump Cement	14:15:36	Pump H2O Displacement	14:24:03	Pump Mud Displacement	14:27:27
Shut Down	14:37:51	End 1ST Plug	14:39:23	Start 2ND Plug	15:19:49
Pump H2O Spacer	15:20:38	Test lines	15:25:17	Pump Cement	15:35:59
Pump H2O Displacement	15:48:26	Pump Mud Displacement	15:50:42	Shut Down	15:57:54
End 2ND Stage	15:58:31				


Customer: Fellow Energy  
Well Description: Crane #6-7  
PTA

Job Date: 5/3/04  
Cliff Murray

Ticket #: 3057115  
Lennie N. Cook

**HALLIBURTON**  
CemWin v1.5.0  
03-May-04 18:08

# Halliburton Energy Services



## Event Log

Start 3RD Plug	18:37:35	Pump H2O Spacer	18:38:03	Test Lines	18:40:22
Pump Cement	18:46:10	Pump H2O Displacement	18:56:45	Pump Mud Displacement	18:58:38
Shut Down	19:00:50	End 3RD Plug	19:01:54	Wash Truck Up To Pit	19:05:14
Shut Down	19:12:57	Start 4th Plug	19:47:43	Pump H2O Spacer	19:48:08
Pump Cement	19:55:56	Pump H2O Displacement	20:02:56	Pump Mud Displacement	20:03:47
Shut Down	20:07:16	End 4th Plug	20:07:26		


Customer: Fellow Energy  
Well Description: Crane #6-7  
PTA

Job Date: 5/3/04

Ticket #: 3057115  
Lennie N. Cook

**HALLIBURTON**  
CemWin v1.5.0  
03-May-04 22:21

# Halliburton Energy Services



Customer: Fellow Energy  
 Well Description: Crane 6-7  
 PTA

Job Date: 5/3/04

Ticket #: 3057115  
 Lennie N. Cook

**HALLIBURTON**  
 CemWin v1.5.0  
 03-May-04 22:18

**FELLOWS ENERGY, LLC**

**CRANE #6-7**

**2363' FNL & 1970' FWL**

**SECTION 7, T6N, R8E**

**RICH COUNTY, UTAH**

**GEOLOGY REPORT**  
by  
**JASON G. BLAKE, CPG, RPG**  
**411 TAMARISK DRIVE**  
**SUNBURST CONSULTING**  
**BILLINGS, MONTANA**  
**(406) 259-4124**  
***sunburstconsulting@compuserve.com***

**RECEIVED**  
**JUN 28 2004**  
**DIV. OF OIL, GAS & MINING**

## **WELL SUMMARY**

<b>OPERATOR:</b>	FELLOWS ENERGY, LLC
<b>NAME:</b>	CRANE #6-7
<b>LOCATION:</b>	2363' FNL & 1970' FWL, SEC 7-T6N-R8E AT TOTAL DEPTH-2525' FNL & 2193' FWL
<b>COUNTY/STATE:</b>	RICH COUNTY, UTAH
<b>ELEVATION:</b>	GR 6802', KB 6812'
<b>SPUD DATE:</b>	4/8/04
<b>COMPLETION DATE:</b>	TOTAL DEPTH 4280' @ 0600 HOURS 5/2/04; TVD 4276'
<b>DRILLING ENGINEERS:</b>	CLIFF MURRAY, STEVE PRINCE
<b>WELLSITE GEOLOGY:</b>	JASON BLAKE-TITAN ENERGY RESOURCES
<b>GAS DETECTION EQUIP:</b>	SUNBURST DIGITAL GEOLOGY SYSTEM
<b>LOGGERS:</b>	JASON BLAKE, TOM GRIGGS, ROGER HAAG
<b>CONTRACTOR:</b>	UNION DRILLING, RIG 14
<b>TOOL PUSHER:</b>	REX HARRIS
<b>HOLE SIZE:</b>	12 1/4", SURF-525'; 7 7/8" 525' TO 4280' TD
<b>CASING RECORD:</b>	8 5/8" TO 525' KB (PRE-SET), CEM TO SURF
<b>DRILLING MUD:</b>	KEMTEC, ROOSEVELT, UTAH
<b>ENGINEERS:</b>	LEN ARNOLD
<b>MUD TYPE:</b>	KCL SEMI-DISPERSED
<b>ELECTRIC LOGS:</b>	SCHLUMBERGER PLATFORM EXPRESS ARRAY IND, DENS/NEUT, MICROLOG, INCLIN, 4270'-528'
<b>SAMPLES:</b>	30' SAMP: 1300-1600'; 10' SAMPLES 1600'-2113'; CORE 2113'-2255'; 10' SAMP: 2555'-3510'; CORE 3510'-3746', 10' SAMP: 3746'-4006'; CORE 4006'-4185'; 10' SAMP. 4185'-4280'
<b>DRILL STEM TESTS:</b>	NONE
<b>CORES:</b>	WIRELINE RETREIVABLE CORING SYSTEM
<b>CORING COMPANY:</b>	CORION CORING SYSTEMS, CALGARY, ALBERTA, CANADA
<b>CORE ANALYSIS:</b>	TICORA GEOSCIENCES, ARVADA, COLORADO



# **DRILLING CHRONOLOGY**

## **FELLOWS ENERGY, LLC**

### **CRANE #6-7**

DATE	DEPTH	DAILY	ACTIVITY
4/10/04	--	--	Rig up Sunburst Consulting 1-man geological consulting with gas detection.
4/11/04	1106'	358'	Drill 1106' to 1384'. Circ out and TOH. LD drill collars. PU coring system BHA and TIH. Drill 1384'-1464'.
4/12/04	1464'	115'	Drill 1464' to 1515'. Circ out & TOH to inspect BHA. LD coring system and PU NB #4 and conventional BHA. TIH and resume drilling at 1930 hours. Drill 1515' to 1579'.
4/13/04	1579'	304'	Drill 1579'-1883'.
4/14/04	1883'	230'	Drill 1883'-2113'. Circ out, run survey and TOH to PU coring assembly.
4/15/04	2113'	52'	TIH with coring assembly. Core Spring Valley coal section 2113'-2165'.
4/16/04	2165'	66'	Core 2165'-2231'.
4/17/04	2231'	99'	Core 2231'-2255', TOH and LD core assembly. PU new BHA and NB #7 and TIH. Drill 2255'-2330'.
4/18/04	2330'	187'	Drill 2330'-2517'. TOH for NB #8.
4/19/04	2517'	397'	PU NB #8 & TIH. Drill 2517'-2914'.
4/20/04	2914'	244'	Drill 2914'-3158'.
4/21/04	3158'	268'	Drill 3158' to 3424'.
4/22/04	3424'	109'	Drill 3424' to 3510'. TOH to PU coring assembly. TIH and core 3510'-3533'.
4/23/04	3533'	76'	Core 3533'-3609'.
4/24/04	3609'	73'	Core 3609'-3682'. Swivel locked up when attempting to resume drilling. Wait on new swivel.
4/25/04	3682'	64'	Swap out new swivel. Resume coring, core 3682'-3745'. Run bit insert in core barrel and drill 3745'-3746'. TOH to PU conventional BHA.
4/26/04	3746'	124'	PU Bit #10, extra collars and TIH. Ream 250 feet to bottom. Resume drilling at 1330 hours. Drill 3746'-3870'.
4/27/04	3870'	136'	Drill 3870'-4006'. Circ out and TOH for coring BHA. Stand back collars and TIH with core barrel.



## **DRILLING CHRONOLOGY CONT.**

**FELLOWS ENERGY, LLC**

**CRANE #6-7**

DATE	DEPTH	DAILY	ACTIVITY
4/28/04	4006'	77'	TIH with core barrel. Cut core #20 from 4006'-4019', rec 12.5' of 13' (core jammed). Cut core #21 from 4019-4042', rec 24.3'. Cut core #22 from 4042-4062', rec 19.8'. Cut core #23 from 4062-4083', rec 21'.
4/29/04	4083'	59'	Cut core #24 from 4083-4103', rec 19.9'. Cut core #25 from 4103-4122', rec 19.3'. Cut core #26 from 4122-4134', rec 12'. Cut core #27 from 4134-4134.2', rec 0.2'.
4/30/04	4144'	19'	Cut core #28 from 4134.2'-4144.4, rec 9.9'. Cut core #29 from 4144.4'-4144.9, rec 0.7'. TOH to PU conventional BHA. PU Bit #12 and extra collars, TIH. Drill 4145'-4163'. TOH for core barrel & Bit # 13.
5/1/04	4163'	89'	TIH w/ Bit #13 & core barrel and cut core #30 from 4163'-4185, rec 23'. TOH for Bit #14 and conventional BHA. Drill 4185'-4252'.
5/2/04	4252'	28'	Drill 4252'-4280'. Circulate 1 ½ hours and TOH for logs. Rig up Schlumberger and run Platform Express log suite. Sunburst Consulting released at 1800 hours 5/2/04.

## **BIT RECORD**

OPERATOR: FELLOWS ENERGY, LLC  
WELL NAME: CRANE #6-7

BIT #	SIZE	MAKE	TYPE	SERIAL #	IN	OUT	FTG	HRS	FT/HR
1	7 7/8"	PDC	CSS513	4DP021	470'	731'	261'	3.5	74.57
2	7 7/8"	HTC	MX-18	396JD	731'	1384'	653'	29.0	22.52
3	7 7/8"	PDC	CSS513	HDP02	1384'	1515'	131'	10.75	12.19
4	7 7/8"	HTC	HAT447	08306	1515'	2113'	598'	40.5	14.76
5	7 7/8"	PDC	CSS513	020	2113'	2183'	70'	24	2.92
6	7 7/8"	DPI	CMR34	2016055	2183'	2255'	72'	11	6.54
7	7 7/8"	HTC	HAT447	08306	2255'	2517'	262'	20.5	12.78
8	7 7/8"	Varel	CH29HS	198121	2517'	3510'	993'	62.5	15.89
9	7 7/8"	DPI	CMR34	2016055	3510'	3746'	236'	47.5	4.97
10 (rr8)	7 7/8"	Varel	CH29HS	198121	3746'	4006'	260'	24.0	10.83
11	7 7/8"	DPI	CMR36	2015682	4006'	4144'	139'	40.0	3.48
12(rr7)	7 7/8"	HTC	HHT447	08306	4144'	4163'	19'	1.0	19
13	7 7/8"	DPI	CMR46	2015959	4163'	4185'	22'	1.5	14.67
14 (rr 7)	7 7/8"	HTC	HHT447	08306	4185'	4280'	95	11.5	8.26

## **DEVIATION RECORD**

OPERATOR: FELLOWS ENERGY, LLC  
WELL NAME: CRANE #6-7

DEPTH	ANGLE	AZIM	DEPTH	ANGLE	AZIM	DEPTH	ANGLE	AZIM	DEPTH	ANGLE	AZIM
493'	4°		1150'	2 3/4°		2010'	2 3/4°		2880'	6 1/4°	
523'	3 3/4°		1242'	2 1/4°		2063'	2°		2908'	7°	
650'	6 1/2°		1430'	2 1/2°		2315'	3°		3033'	4 1/2°	
775'	6°		1543'	2 3/4°		2457'	4 1/2°		3130'	7 1/2°	
828'	5°		1639'	1 1/2°		2472'	4 1/2°		3259'	7 3/4°	
911'	4 3/4°		1732'	2°		2565'	5 1/2°		3437'	7 3/4°	
973'	3 3/4°		1815'	2 1/2°		2660'	5 1/4°		3908'	4°	
1063'	3 1/4°		1900'	2°		2782'	6 3/4°				

# **MUD REPORT**

**OPERATOR: FELLOWS ENERGY, LLC**

**WELL NAME: CRANE #6-7**

DATE	DEPTH	WT	VIS	PV	YLD	GEL	pH	WL	CK	CL	Ca	SD	SOL	WTR
4/10/04	902'	8.8	35	6	3	½	11.5	8.4	2/32	18000	420	Tr	2.0%	98.0%
4/11/04	1262'	8.9	38	9	4	2/5	11.0	7.6	2/32	29000	240	1%	3.0%	97.0%
4/12/04	1515'	9.4	39	10	5	2/4	11.0	8.8	2/32	23000	160	Tr	6.0%	94.0%
4/13/04	1703'	9.5	40	11	5	2/4	11.0	7.6	2/32	25000	80	Tr	7.0%	93.0%
4/14/04	2105'	9.3	40	14	6	2/5	11.0	6.4	2/32	28000	120	Tr	6.0%	94.0%
4/15/04	2119'	9.5	42	16	9	3/7	11.0	6.0	2/32	34000	80	Tr	7.0%	93.0%
4/16/04	2183'	9.7	42	18	10	4/8	10.5	6.4	2/32	26000	100	Tr	7.0%	93.0%
4/17/04	2255'	9.7	42	20	11	5/10	10.0	6.8	2/32	30000	60	Tr	8.0%	92.0%
4/18/04	2548'	9.7	42	16	8	3/7	11.0	9.6	2/32	34000	20	Tr	7.0%	93.0%
4/19/04	2686'	9.7	42	16	9	4/7	11.0	8.4	2/32	35000	60	Tr	8.0%	92.0%
4/20/04	2997'	9.7	42	17	10	4/8	10.5	7.4	2/32	39000	80	Tr	7.0%	93.0%
4/21/04	3397'	9.7	42	15	8	4/6	10.0	5.8	2/32	27000	60	Tr	6.0%	94.0%
4/22/04	3510'	9.6	42	16	10	5/7	11.0	9.8	2/32	33000	80	Tr	7.0%	93.0%
4/23/04	3561'	9.7	43	18	12	6/9	10.5	8.9	2/32	29000	80	Tr	9.0%	91.0%
4/24/04	3646'	9.5	43	16	10	5/8	11.5	9.4	2/32	33000	60	Tr	6.0%	94.0%
4/25/04	3683'	9.5	43	16	11	5/9	11.0	10.2	2/32	30000	80	Tr	6.0%	94.0%
4/26/04	3853'	9.5	42	15	12	5/10	10.5	9.8	2/32	24000	120	Tr	7.0%	93.0%
4/27/04	3996'	9.4	41	13	10	4/8	11.0	9.4	2/32	36000	100	Tr	5.0%	95.0%
4/28/04	4061'	9.5	44	16	11	6/9	10.5	8.8	2/32	32000	80	Tr	6.0%	94.0%
4/29/04	4133'	9.4	43	17	12	6/10	11.0	8.4	2/32	25000	60	Tr	5.0%	95.0%
4/30/04	4144'	9.4	42	15	10	5/8	10.5	8.2	2/32	29000	80	Tr	5.0%	95.0%
5/1/04	4185'	9.3	41	15	9	4/9	10.5	8.8	2/32	35000	120	Tr	NA	NA
5/2/04	4280'	9.4	45	17	12	6/11	11.0	8.0	2/32	32000	60	Tr	5.0%	95.0%

## **SAMPLE DESCRIPTIONS**

**OPERATOR: FELLOWS ENERGY, LLC**  
**WELL NAME: CRANE #6-7**

1300-30 SLTSTN, varicol, lr rd- lt gr, spt blk ip, sft frm, sl pyr ip, calc, SS strng, chlor, hd, wl cem, scat LS, lt gr-gr, argil, hd, scat CHT, brn-wht-gr-blk, NFSOC

1330-60 SLTSTN aa, bcm vlt gr-lt gr, sft-gummy grd to CLYSTN ip, rr sndy ip, com rnd congl pebs, calc, NFSOC

1360-90 SLTSTN grd to SHL, lt-md gr-brn-yel, blk, md frm ip, scat-com clr-yel CHT, com SS, wht-gr mott, fn-md grn, pr srt, argil, cly fill, NFSOC

1390-1420 pred SHL, lt gr-gr grn to occ gr brnr, blk, sl frm-sft, sl wxy tex ip, bent, calc, NFSOC

1420-50 SHL, lt gr-gr grn to occ gr brn-dk gr, blk, sl frm, silty to sl wxy tex ip, sl sndy ip, calc, scat lt gr-clr CHT, NFSOC

1450-80 SHL, gr grn-lt gr, blk, sl sft-md frm, bent, sl mic ip, scat SS, clr-lt gr, v fn-md grn, sb rnd, pr srt, cly fill, scat lt gr transl CHT, NFSOC

1480-1510 pred bent SHL, lt gr-pl gr grn, blk, md frm, wxy, sl mic ip, scat dk gr SHL, scat dk gr CHT, NFSOC

### FRONTIER FORMATION 1516' (5296)

1510-40 SHL, md gr brn, blk, sl-md frm, com carb inclus, scat coal string-pyr ip, scat-com BENT, lt gr-crm, frm, NFSOC

1540-70 SHL, tn-crm, blk, frm, bent to slty ip, calc

1570-1600 SS, lt gr, sl S&P, vfn-fn grn, sb rnd, md srt, md frm, mic, calc & SHL, tn-crm, blk, frm, bent to slty ip, NFSOC

1600-20 SS, crm-lt gr, S&P, vfn-fn grn, sb rnd, md srt, com dk lithic frags, md frm, calc cem, scat wht transl CHT, scat crm BENT, scat SHL, lt gr-gr grn-brn, blk, md frm, sl calc, NFSOC

1620-40 SHL, md gr, blk-sb plty, sl frm, slty ip grd to SLTSTN ip, calc, NFSOC

1640-60 NO SAMPLES SAVED

1660-80 SHL, lt-md-occ dk gr, blk-sb plty, sl frm-md sft, gummy ip, slty tex ip, sl pyr ip, calc

1680-1700 SS, lt gr, sl S&P, vfn grn grd to SLTSTN ip, sb rnd, md wl srt, md frm-fri ip, calc, NFSOC, SHL, dk gr-dk brn, striat, blk, md sft, carb w blk carb inclus, rr vit coal inclus, NFSOC

1700-20 LS, lt brn, md hd, mic xln, dens, argil + SHL, brn-dk gr, stiat blk ip, blk-sb plty, sl frm-md sft, carb ip, blk shl ptgs, sl pyr ip, scat COAL, blk, vit, britt, NFSOC

1720-40 SHL, lt-md gr, blk, md frm, slty ip to sl carb ip, calc + SS, lt gr-mott dk gr ip, sl S&P, fn grn, sb ang, md sft, argil, calc, NFSOC

1740-60 SHL, dk gr-blk ip, striat, md sft, carb w blk carb inclus, sl-non calc, scat COAL strng, blk, vit w conc frac + SLTSTN, lt-md gr, blk, sl frm, calc, NFSOC

1760-80 SS grd to SLTSTN ip, lt-occ md gr, vfn grn, sb rnd, md wl srt, cly fill, argil w blk carb ptgs, scat blk vit COAL + SHL, md gr- gr grn ip, blk, sl pyr ip, bent ip, scat calc fill frac, NFSOC

1780-1800 SHL, lt gr-tn, grd to md-dk gr, blk, md-sl frm, v calc ip grd to LS, tn, mic-crypto xln, dens, hd, sl pyr ip, scat wht calc fill frac, scat dull yel min FLUOR (calc), no shows

1800-20 SHL, pred md gr, blk, sl frm, sl slty/grny tex ip, calc-v calc ip grd to v argil LS, tn, micxln, dens, NFSOC

1820-40 SHL, lt-md gr, blk, sl-md frm, sl slty/grny tex ip, sl calc-calc, sl argil ip grd to SLTSTN ip, minor dk gr carb ptgs, NFSOC

1840-60 SHL aa, lt-md gr, blk, sl-md frm, sl slty/grny tex ip grd to SLTSTN ip, sl calc-calc, minor dk gr carb ptgs aa, NFSOC

1860-80 SS, lt gr-mott brn-dk gr, fn-vfn to occ md grn, sb ang, pr-md srt, com-abund lith frags, sl

pyr ip, abund cly fill, calc cem + SHL, lt gr, blk, md frm, calc, slty ip to sl wxy tex ip, NFSOC  
 1880-1900 SHL, lt-md gr, blk, md-sl frm, sl wxy tex ip to slty tex ip, calc, NFSOC  
 1900-20 SHL, lt gr-pl blu gr, blk-plty, frm, bent, sl mic, sl calc & SHL, lt brn, plty-blk, md frm, sl calc, NFSOC  
 1920-40 SHL, lt gr brn, blk, md frm, sl calc + SS, lt gr-md brn, mott dk gr ip, fn-occ md grn, sb rnd, md srt, abund lith frags, wl cem w calc cem, NFSOC  
 1940-60 SHL, dk brn-blk, sb plty-blk, sl plastic to brittle, lt brn grsy strk, v carb grd to low grd COAL ip, blk vit COAL strngs, sl sheen on smp wtr, no FLUOR  
 1960-80 SHL, md blu-gr, blk, md frm, calc, slty ip to sl bent-wxy ip, scat SS, lt gr-mott brn-dk gr, fn grn, sb rnd, md srt, lithic frags, calc cem, NFSOC  
 1980-2000 SS, crm-brn-lt gr, fn-md grn, sb rn-sb ang, pr srt, cly fill, scat glauc, NFSOC + SHL, md gr-dk brn, blk, md-sl frm, carb ip w COAL strngs, NFSOC  
 2000-20 SHL, md blu-gr, blk, md frm, calc, sl wxy tex ip, silty/sndy in grd to SS strngs, lt gr-mott brn-dk gr, fn-md grn, sb ang, md srt, wl cem w calc cem, NFSOC  
 2020-40 SHL, lt-md gr, blk, md-sl frm, slty ip grd to SLTSTN ip, sl-mod calc, NFSOC, loc COAL strgs, loc SLTST strgr  
 2040-2060 SHL aa, lt-md gr, blk, md-sl frm, slty ip gcm pl bly gr, wxy, bent ip, blk, md frm, sl calc, sl mic, NFSOC  
 2060-80 SHL, md gr, blk, md frm-frm, gny/slty tex, calc, scat-com blk carb inclus, scat blk vit COAL, NFSOC  
 2080-2113 SHL, dk gr-dk gr brn, blk-sp plty, sl-md frm, carb, calc, scat-com blk vit COAL ptgs, NFSOC  
 CORE #1 2113-37', rec 23', pred SHL, md-dk gr, sl slty ip, masv-thn lam ip, intrbd zones of bioturb/foss hash (brach), scat blk vit carb/coat inclus, 6" bent SHL at 2130'  
 CORE #2 2137-58', rec 20', interbd SHL, md-dk gr, slty/sndy ip, CARB SHL, blk, coaly, sl frm-md sft & COAL, blk, sft, fri, fract, 3/8-1/2" cleats in lowermost coal interval  
 CORE #3 2158-66', rec 8', SHL, md gr, md frm, sl calc, slty ip, rr carb inclus  
 CORE #4 2166-83', rec 17', SHL, md-dk gr, sl calc, slty/sndy ip, CARB SHL, dk gr-blk, md frm, sl calc, intbd COAL, blk, vit, frac, shly ip  
 CORE #5 2183-2207', rec 24', SHL, md gr, sl calc, slty/sndy ip, CARB SHL, dk gr-blk, md hd, sl-md calc, shly intbds, loc COAL strgs, blk, loc vit, SNDST, med-lt gr, v fn grn, sl calc, detrital/slty, fos frags, mnr carb, rr pyr  
 CORE #6 2207-31', rec 24.8', SNDST, med-lt gy, fn-v fn grn, md-sl calc, detrital/slty, fos frags, mnr carb, rr v fn grn pyr, SHL, md gr, sl calc, slty intbd w/ CARB SHL, dk gr-blk, md frm, sl slty, sl calc

#### ASPEN SHALE 2234' (4578)

CORE #7 2231-55', rec 24', CARB SHL, dk gr-blk, md hd, sl slty, sl calc, carb alng fracs  
 2255-80 SHL, md-lt gry, md frm, slty, md calc, loc grdg to mnr CARB SHL, dk gr-blk, md hd-frm, sl slty, sl calc, wk fluo, no cut, w/ loc SS ib, md gry, fn gr, slty, md calc  
 2280-2300 SHL, md gry, sub plty, md hd-frm, slty, md calc, rr fn gn pyr, NFSOC  
 2300-20 SHL, md gry, sub plty, md frm, slty, md calc, loc grdg to mnr CARB SHL, dk gr-blk, md frm, sl slty, md calc, NFSOC, w/ loc strgs SLTST-SS, md-lt gry, v fn gr-slty, md calc  
 2320-40 SHL, md gry, sub plty, md frm, slty, md calc, NFSOC, w/ loc strgs SLTST, md-lt gry, md calc  
 2340-60 SHL, md gry, sb plty-plty, md hd-frm, slty, md calc, loc rr v fn grn pyr, NFSOC  
 2360-80 SHL, md-lt gry, sub plty-plty, md hd-frm, slty, md calc, NFSOC  
 2380-2400 SHL, md-lt gr, sub plty, sft, pr consol, slty, loc wxy, md calc, grdg to NFSOC  
 2400-20 SHL, md-lt gr, sub plty, sft, pr consol, slty, loc wxy, md calc, grdg to NFSOC, SLTSTN, md gry, sb plty-mssv, sft, sndy, md calc, mnr BENT lt gry-gry gn, wxy  
 2420-40 SHL, dk gry brn, plty-sub plty, md hd, sl slty, com v fn grn dissem pyr, NFSOC

2440-60 SHL, dk gry brn, dk gry, plty-sub plty, md hd, sl slty, v fn grn dissem pyr, NFSOC  
 2460-80 SHL, dk gry brn, dk gry, plty-sub plty, md hd, sl slty, com v fn grn dissem pyr, NFSOC, loc BENT wht-ltgry, blu grn, shly-loc mssv, wxy, wk calc  
 2480-2500 SHL, dk gry brn, dk gry, plty-sub plty, md hd, sl slty, sl calc, NFSOC, SNDST ib, lt-md gry, fn-v fn grn, detrital/slty, fos frags, mnr carb, loc BENT wht-ltgry, blu grn, shly-loc mssv, wxy, wk calc  
 2500-20 SHL, dk gry brn, dk gry, plty-sub plty, md hd, sl slty, wk calc, NFSOC  
 2520-40 SHL, dk gry- dk gry brn, plty-sub plty, md hd, loc foss hash, sl slty, v sl calc, NFSOC  
 2540-60 SHL, dk gry brn, dk gry, plty-sub plty, md hd, sl slty, v sl calc, NFSOC, loc BENT, lt gry, frm, wk min flu  
 2560-80 SHL, dk gry brn, plty-sub plty, md hd, loc mnr lt brn foss hash, sl slty, v sl calc, NFSOC, loc mnr BENT, lt gry, frm, wk min flu  
 2580-2600 SHL, dk gry brn, dk gry, plty-sub plty, md hd, loc mnr foss hash, sl slty, v sl calc, NFSOC, loc mnr BENT, lt gry, blu gry, frm, wk min flu

#### BEAR RIVER FORMATION 2614' (4198)

2600-20 SHL, dk gry, dk gry brn, sub plty-plty, md hd, sl slty, v sl calc, v fn gr, dissem pyr, NFSOC, loc BENT strgrs, lt gry, lt blu gry, frm, wk min flu, loc v sl calc  
 2620-40 SHL, dk gry-dk gry brn, sub plty-plty, md hd, sl slty, v sl calc, v fn gr, dissem pyr, NFSOC, loc BENT strgrs, lt gry- wht, sft- frm, v wk-no min flu  
 2640-60 SHL, dk gry, dk gry brn, plty-sub plty, md hd, sl slty, v sl calc, NFSOC, loc BENT, lt gry- wht, lt blu gry, frm-sft, v wk min flu, loc v sl calc  
 2660-80 SHL, dk gry, dk gry brn, plty-sub plty, md hd, sl slty, v sl calc, NFSOC, loc BENT, lt gry- wht, lt blu gry, frm-sft, v wk min flu, v sl calc, loc SNDY SLTST, lt gry-wht, md hd-frm, mnr pyr  
 2680-2700 SNDSTN lt gry, lt brn, S&P, mssv, md hd-frm, loc mnr mic, rr pyr, v sl-no calc, SHL, dk gry, dk gry brn, plty-sub plty, md hd, sl slty, v sl calc  
 2700-20 SHL, dk gry, dk gry brn, plty- sub plty, md hd, sl slty, v sl calc, NFSOC, loc SLTSTN, lt gry, frm, sndy, v sl calc, mnr BENT, lt gry-wht, frm-sft, v sl calc  
 2720-40 SHL, dk gry brn, dk gry, plty- sub plty, md hd, loc mnr foss, sl slty, loc v fn gr pyr, v sl calc, NFSO  
 2740-60 SHL, dk gry brn, dk gry, plty- sub plty, md hd, loc mnr foss, sl slty, loc v fn gr pyr, v sl calc, NFSOC  
 2760-80 SHL, md-dk gry, loc brn gry, sub plty, md hd, str slty, loc v fn gr pyr, sl-md calc, NFSOC, loc SNDST, lt gry, S&P, v fn grn, frm-md hd, slty, SLTST, lt-md gry, frm-md hd, md calc  
 2780-2800 SLTST, md-lt gry, frm-md hd, md calc, mnr dissem pyr, SNDST, lt gry-wht, S&P, v fn grn, md hd-frm, slty, md calc, SHL, md-dk gry, plty, md hd, str slty, sl-md calc, NFSOC  
 2800-20 SNDST, trnslc, lt gry-wht, S&P, fn grn, md hd-loc frm, sbang-sbrnd, no flu  
 2820-40 SS, trnslc, lt gry-wht, S&P, fn grn, md hd-loc frm, sbrnd-sbang, no flu, SLTST, gry brn, frm-md hd, com sndy, sl calc, mnr BENT, blu grn, wxy, mnr SH, blk, plty, md hd  
 2840-60 SNDST, trnslc, lt gry-wht, S&P, fn grn, md hd-loc frm, sbrnd- sbang, no flu, loc slty, SLTST, dk brn, md hd, com sndy  
 2860-80 SLTST, gry brn, dk gry, md hd-v sft, com sndy, str cly, sl calc, rr pyr, SS, lt gry-wht, S&P, trnslc, v fn grn, md hd, sbrnd- rnd, com slty, SH, dk gry, md hd, sbplty-plty, mnr BENT, md gry-blu grn, wxy  
 2880-2900 SLTST, lt-md gry, md hd-frm, com sndy, loc str cly, sil cmt, md intxln calc, rr pyr, SS, lt gry-wht, S&P, trnslc, v fn grn, md hd, sbrnd-sbang, com slt-cly, sil cmt, md calc  
 2900-20 SS, lt gry, loc brn gry, v fn grn, md hd, sbrnd-sbang, com slty-cly, rr v fn grn pyr, sil cmt, md intxln calc, SLTST, lt-md gry, com snd, str cly, sil cmt, md calc, rr pyr  
 2920-40 SS, lt gry, v fn grn, md hd, sbrnd-sbang, com slt-cly, rr v fn grn pyr, sil cmt, md-str intxln calc, SLTST, lt-md gry, md hd-frm, loc sndy, str cly, sil cmt, md intxln calc

2940-60 SLTST, lt-md gry, frm-sft, loc sndy, str cly, sil cmt, md intxln calc, SS, lt gry, v fn-fn grn, md hd, sbrnd-sbang, com slt-cly, sil cmt, md-str intxln calc  
 2960-80 SS, lt gry, S&P, trnslc ip, v fn grn, md hd, sbrnd-sbang, mntr slt, sil cmt, str intxln calc, SLTST ib, lt-md gry, sft-frm, str cly, mntr SH dk gry, plty, md hd  
 2980-3000 SLTST, lt brn, lt gry, sft, str cly, md-str calc, loc mntr carb SHL, SS, md brn, v fn grn, md hd, com slt, sil cmt, md-str intxln calc  
 3000-20 SS, lt gry, S&P, trnslc ip, fn-v fn grn, md hd, sbrnd-sbang, mntr slt, sil cmt, str intxln calc, rr pyr, SLTST ib, lt-md gry, plty, md hd, md calc, rr fn grn pyr  
 3020-40 SH, dk gry-blk, plty-sub plty, frm-md hd, com carb, loc pyr, md calc, loc md brn & foss, loc grdg to COAL, blk, plty, vit, SLTST, grn gry, frm, sl calc  
 3040-60 SH, md-dk gry, sub plty, md hd, com carb, rr loc pyr, sl-md calc, loc md brn & foss, SS lt gry, S&P, trnsluc, fn grn, md hd, sl intxln calc, SLTSTN grn gry, frm, sl calc  
 3060-80 SH, md-dk gry, plty, md hd, com carb, md calc, loc md brn & foss, SS lt gry, S&P, mntr COAL strgr, blk, vit, md pyr, v fn grn, md hd, md intxln calc  
 3080-3100 SH, md-dk gry, plty, md frm-hd, md calc, loc md brn & foss, SS lt gry, loc trnsluc, md hd, v fn grn, SLTSTN, md gry, frm, md calc  
 3100-20 SLTST, lt-md gry, frm-md hd, loc sndy, str cly, sl-md calc, loc mssv calc alng fracs, SS, lt gry, v fn-fn grn, md hd, sbrnd- sbang, com slt-cly, sil cmt, md-str calc, SH, dk gry, md hd, sl calc  
 3120-40 SS, lt gry, loc S&P, v fn-fn grn, md hd, sbrnd-sbang, loc slt, str sil cmt, md-sl calc  
 3140-60 SLTST, md gry-gry grn, frm, loc sndy, str cly, sl calc, loc rr dissem pyr, grdg to SS, lt gry, v fn-fn grn, md hd, sbrnd- sbang, com slt-cly, sil cmt, md calc, SH, dk gry, md hd, sl calc  
 3160-80 SS, lt-md brn, gry grn-lt gry, v fn grn, sbang-sbrnd, md hd, loc sndy, str slt-cly, sil cmt, md calc, loc SLTSTN strgrs, gry brn, frm, com cly, sl calc, SH, dk gry, md hd, sl calc  
 3180-3200 SLTST, lt-md gry-gry grn, sft-frm, loc sndy, str cly, sl-md calc, grdg to SS, lt gry, v fn grn, md hd, sbang-sbrnd, com slt-cly, sil cmt, sl-md calc  
 3200-20 SS, ltgry-lt brn, wk S&P, v fn grn, sbrnd-sbang, md hd, str com slt-cly, wk sil cmt, md calc, loc SLTSTN strgrs, md gry-grn gry, frm, cly, sl calc, rr pyr, SH, dk gry, md hd, loc carb grdg to COAL  
 3220-40 SLTST, lt-md gry, md hd-frm, loc sndy, com cly, sl calc, grdg to SS, lt gry, v fn grn, md hd, com slt-cly, sil cmt, md calc, SH md-dk gry, md hd, loc carb, mntr BENT, lt grn, wxy  
 3240-60 SLTST, lt-md gry, lt brn, mssv-sbplty, md hd-frm, loc sndy, com cly, sl-md calc  
 3260-80 SS, lt-md gry, v fn grn, md hd, str com slt-cly, sil cmt, md calc, loc SLTSTN strgrs, lt gry, lt brn, md hd, cly, sl calc SH, dk gry, md hd, sl calc grdg to mntr COAL  
 3280-3300 SH, md-dk gry, lt-md brn, md hd, loc arg, loc foss, md-sl calc, SLTSTN, md gry, md hd-sft, com slt-cly, md calc, mntr BENT lt grn, wxy  
 3300-20 SLTST, lt gry-lt gry grn, mssv, frm-sft, loc sndy, com cly, sl calc, sil cmt, SS, lt gry, S&P, fn-v fn grn, md hd, sbrnd- sbang, loc slty, md calc, rr pyr  
 3320-40 SS, lt gry, S&P, v fn grn, sbang- sbrnd, md hd, com slt-cly, sil cmt, md calc, loc SLTSTN strgrs, lt gry-gry grn, frm-sft, com cly, sl calc  
 3340-60 SLTST, lt gry-lt gry grn, mssv, md hd-frm, loc sndy, com cly, md-sl calc, SS, lt gry, lt brn, v fn grn, md hd, slty, md calc, SH, dk gry, md hd, sl calc, mntr BENT, lt grn, wxy, frm  
 3360-80 SLTST, md gry, lt brn, frm, com cly, md-sl calc, SS, lt gry, v fn grn, md hd, slty, md calc, SH, md gry, md hd, sl calc, mntr BENTaa  
 3380-3400 SS, lt-md gry, gry brn, v fn grn, sbang- sbrnd, md hd, com slt-cly, sil cmt, md calc, SLTSTN strgrs, lt-md gry, md hd-sft, com cly, sl-md calc, SH aa  
 3400-20 SLTST, md-lt gry, frm-sft, com cly, md calc, SH md-dk gry, md hd, sl-no calc, SS, lt gry, lt brn, v fn grn, md hd, slty, md calc  
 3420-40 SS, lt gry, lt gry brn, loc S&P, fn-v fn grn, sbang-sbrnd, md hd, incr slt-cly w/ depth, sil cmt, v sl calc, loc SLTST, aa  
 3440-60 SS, lt gry, lt gry brn, v fn grn, sbang- sbrnd, md hd, com slt-cly, sil cmt, sl-md calc, loc SLTST, lt-md gry, sft, com cly, md calc, SH dk gry, md hd, sl- md calc

3460-80 SLTST, md brn gry-lt gry, md hd-sft, v sndy, com cly, md calc, grdg to SS ib, md gry brn, v fn grn, md hd, slty, md calc, SH md-dk gry, md hd, plty, sl-no calc

3480-3500 SLTST, gry brn-lt gry, sft, com cly, md-sl calc, grdg to SS, lt gry grn, v fn grn, md frm, md-sl calc, SH md gry, md gry brn, md hd, sl calc

3500-10 SS, lt gry, lt brn, v fn grn, sbrnd, md hd, com slt-cly, sil cmt, md calc, loc SLTST, lt-md gry, gry grn, md hd-frm, com cly, sl calc

CORE #8, 3510'-3533', rec 23', SHL, md-dk gr, frm, sl calc, rip-up clasts ip & intrbd SS, lt gr, sl S&P, fn grn, sb rnd, md srt, fn lam to sl x-bd, sl mic, calc cem, NFOSC

CORE #9, 3533'-3557', rec 22.5', SHL, md-dk gr, blk, frm, sndy ip, calc & SS, lt-md gr brn, mott dk gr, fn grn, sb rnd, md wl srt, md wl cem w calc, cly fill, scat calc lined frac, NFSOC

CORE #10, 3557'-3561', rec 4', SLTY SHL, md gr, frm, sl calc ip, scat calc fill frac, NFSOC

CORE #11, 3561'-3585', rec 24', SS, lt gr, vfn grn grd to SLTSTN ip, sb ang, wl srt, wl cem w calc cem, SHL, md gr, frm, dens, sl calc w rr blk carb flks, scat calc fill frac, NFSOC

CORE #12, 3585'-3609', rec 24', SS, lt gr, fn grn, sb ang, wl srt, x bed, wl cem w calc, intrbd SHL, md gr-dk gr ip, frm, sl calc to calc, sndy ip w SS strngs, thin carb shl int near base, NFSOC

CORE #13, 3609'-20.5', rec 11.5', SHL, md-dk gr-occ blk, frm to sft, carb ip, sl-md calc, bioturb ip w oyst shells @ 3616', coal strngs in carb shl section

CORE #14, 3620.5'-3644', rec 23.5', SHL & SNDY SHL, md-sl gr, md frm, sl bent ip, com calc fill frac + SS, lt-md gr, vfn-fn grn, sb ang, md wl srt, x bed ip, calc cem, intrbd sndy shl, NFSOC

CORE #15, 3644'-3662', rec 14.5', SS, lt-md gr, vfn grn grd to SLTSTN ip, sb ang, wl srt, calc cem, low energy envi w abund intrbd dk gr SHL + SHL, md-dk gr, frm, calc, sl carb-lost 2' at base-prob carb SHL

CORE #16, 3662-3682', rec 22.5', (rec base of core #15), pred SHL, dk gr-blk, carb ip, sl-non calc, com foss intrbds (oysters), scat blk vit coal prtgs in carb shl, rr thin bent strngs, lt brn, sft

CORE #17, 3582'-3707', rec 22.5', (lost coal at base) pred SHL, dk gr-blk, sl frm-sft, carb ip, calc, com foss intrbds, thin intrbd COAL, NFSOC

CORE #18, 3707'-3729', rec 22' pred carb SHL, dk gr-blk, sl frm-sft, sl calc, foss ip, scat thin intrbd COAL, intrbd SHL, md-dk gr, frm, calc, foss, NFSOC

CORE #19, 3429'-3745', rec 18'?, upper 11'-SHL grd to carb SHL, md-dk gr-blk, md frm-md sft, sl calc ip, v foss beds & COAL strngs; lower 6'-SLTSTN grd to SS, lt-md gr, vfn grn, wl srt, hd, wl cem w calc, NFSOC

3745-60 SHL, md-dk gr-lt gr grn, blk-sb plty, md frm-md sft, carb ip to bentic ip, sl-non calc

3760-80 SS, tn-lt brn, vfn grn-occ fn grn, sb rnd, md wl srt, pred qtz w scat dk gr lith grns, md hd-hd, wl cem, calc cem, NFSOC

3780-3800 SHL, md-dk gr-occ dk gr brn, blk-sl plty, md frm-sft ip, slty/rthy tex ip, carb ip, brn grsy strk, sl-md calc, scat COAL, blk, vit + LS, md brn-dk gr brn, mic xln, dens, hd, argil, sl foss ip, NFOSC

3800-20 pred LS, md-dk brn, fn-mic xln, den-sl rthy tex ip, argil, sl foss, poss scat blk STN in frac, rr calc frac fill, scat COAL, blk, vit, concoid frac, no FLUOR, sl resid rnd CUT

3820-40 SHL, md-dk gr, sb blk, sl frm-md sft, carb, sl calc, sl pyr ip, scat-com blk vit COAL ptgs, scat tn calc frac fill; shl bcm sft, rthy, slty, sl foss, NFOSC

3840-60 LS, tn-md br-dk gr ip, mic xln, dens-sl rthy tex, v foss/ coquin ip, argil, abund shl ptgs + SHL, md-dk gr, sb blk, sl frm-md sft, rthy tex ip, carb, SS at base, lt gr-brn, v fn grn, md wl srt, hd-wl cem w calc, sl pyr ip, NFSOC

3860-80 SHL, md-dk gr-occ blk, sb blk, sl frm-md sft, rthy/slty tex ip, sl calc, foss ip, carb grd to shly COAL ip, blk, sft, brittle, NFOSC

3880-3900 LS, md-dk brn, sl hd, mic xln, foss, argil to v argil grd to v calc SHL ip + abund COAL grd to coaly SHL, blk, blk, brittle, cleated, NFOSC

3900-20 LS, brn-occ tn, mic xln, dens-sl rthy tex ip, foss, argil grd to v calc SHL ip, scat SHL, dk gr, blk, carb, scat COAL, blk, vit, concoid frac, NFOSC

3920-40 LS aa, brn-occ tn, mic xln, dens-sl rthy tex ip, foss, argil grd to v calc SHL & scat COAL,



blk, vit aa, NFOSC

3940-60 SS, crm-lt gr, vfn grn, sb rnd, md wl srt, hd, pred qtz w scat dk gr lith grns, calc & poss qtz ovrgth cem + SHL, md-dk gr, sb blk, sl frm-md sft, calc, NFSOC

3960-80 SHL, md-dk gr-occ blk, sb blk, frm, rthy, v carb ip, coaly lams, foss, v calc grade to foss Marlstn w/ LS, brn-occ tn, dns-rthy, arg, foss, grade to foss Marlstn

3980-4006 SS, crm-lt gr, vfn grn, sb rnd, md wl srt, hd, pred qtz w scat dk gr lith grns, v calc, grade to sndy LS w/ LS, brn-occ tn, dns-rthy, arg, v sndy + SHL, aa NFSOC

CORE #20 4006'-4019', rec 12.5',

5.5'-SHL, md-dk gr-blk, hrd- frm, calc, v slty, carb ip, occ foss; 2'- Coal & sm carb SHL; 5'- SHL, tn-brn gr-blk, hrd- frm, carb ip, abnd foss, v calc, grd to Mrlstn, NFSOC

CORE #21 4019-4042', rec 24.3', Thin intrbdng of SHL, tn-brn gr-blk, hrd- frm, v slty, carb ip, v foss, v calc, grd to Mrlstn; Coal / carb SHL; LS, brn-occ tn, dns-rthy, arg, foss, grd to foss Mrlstn. Calc frac fill thru out

CORE #22 4042-4062', rec 19.8', Thin intrbdng of SHL, tn-brn gr-blk, hrd- frm, v slty, carb ip, v foss, v calc, grd to Mrlstn; Coal / carb SH and occ brn-occ tn, dns, foss, LS. Calc frac fill thru out

CORE #23 4062-4083', rec 21', SS, crm-lt grn, vfn grn, sb rnd, fr srt, hd, Qtz occ hvy min, abnd calc cmt / mtrx. SHL, tn-brn gr-blk, hrd- frm, v slty, v carb, coaly lams, foss, v calc. LS, brn-tn, dns, foss, shly.

CORE #24 4083-4103', rec 19.9', SHL, tn-brn gr-blk, hrd- frm, v slty, v carb, coaly lams, foss, v calc. w/ strngs LS, brn-tn, dns, foss, shly.

CORE #25 4103-4122', rec 19.3', SHL, tn-brn gr-blk, hrd- frm, v slty, v carb, coaly lams, foss, v calc, Bent w/ strngs LS, brn-tn, dns, shly, sndy, v foss and shly Coal.

CORE #26 4122-4134', rec 12', SHL, tn-brn gr-blk, hrd- frm, v slty, v carb, coaly lams, foss, v calc. LS, brn-tn, v dns, foss, shly & vf gr, calc, SS

CORE #27 4134-4134.2', rec 0.2'.

CORE #28 4134.2'-4144.4, rec 9.9', SHL, brn-blk, hd-frm, v slty, v carb, coal lam, foss, calc. Coal. & vf gr, calc, SS

CORE #29 4144.4'-4144.9, rec 0.7'.

4145-63 SS, lt crm-lt gy, md occ f grn, ang-sbrnd, wl srt, fri, Qtz occ hvy min, sli calc, cln, fr-gd occ v gd por, NSOCF. SH, gy-blk, blk, v carb, coal lams. Coal, blk, vit, blk.

CORE #30 4163'-4185, rec 23'. SHL, brn-blk, hd-frm, v slty ip, v carb, coal lam, calc occ ls lam intrbd w/COAL, blk, vit, blk, pyr

4185-4200 SS, lt-md gr-gr brn, vfn-fn grn, sb rnd, md wl srt, hd, wl cem, calc cem + SHL, dk gr-blk, blk, sl frm-md sft, non calc, v carb grd to shly COAL ip, blk, sft, concoid frac, pyr ip, NFSOC

4200-20 pred SHL, md gr, blk-sb plty, sl frm-sl sft, sl pyr ip, calc, scat SS, tn-vfn grn, sb rnd, wl srt, calc cem, scat LS, tn-lt brn-dk gr, mic-fn xln, v foss, scat wht BENT, dull min FLUOR, no shows

4220-40 SLTSTN, tn-lt brn, blk, hd ip to sft/rthy ip, calc grd to v argil slty LS ip, scat SHL, md gr, sb plty, sl frm, sl calc, NFSOC

4240-60 SHL, lt-md gr, blk, sl frm, non calc, slty ip grd to SLTSTN, tn-lt gr, sl frm-sft, rthy ip, calc + SS, crm-tn, vfn-occ fn grn, sb rnd, wl srt, md hd-hd, scat dk gr lith frags, cly fill ip, wl cem w calc, NFSOC

4260-80 SS, crm-tn-mott brn ip, vfn-fn grn bcm md grn near base, sb rnd, md srt, arkos w com dk lith grns, cly fill, calc cem, scat SHL, md gr-gr grn, blk-plty, sl frm, non calc, NFSOC

## **FORMATION TOPS**

OPERATOR: FELLOWS ENERGY, LLC  
WELL NAME: CRANE #6-7

FORMATION NAME	SAMPLES		E-LOG		STRUCTURAL COMPARISON – SUTTONS #4-12 SEC. 12-6N-7E
	MEASURED DEPTH	DATUM	MEASURED DEPTH	DATUM	
WASATCH	SURF	6812	SURF	6812	
UNCONFORMITY	1452'	5360	1516'	5296	-122
FRONTIER	1452'	5360	1516'	5296	-122
SPRING VALLEY COAL SECTION	2097'	4715	2098'	4714	+1256
ASPEN SHALE	2234'	4578	2234'	4578	+1224
BEAR RIVER FM.	2614'	4198	2614'	4198	+1226
BEAR RIVER COAL SECTION	4012'	2800	4019'	2793	-757**
**Compared to the Crane #13-8 well located updip and 5000' east in Sec 8-T6N-R8E					

## **GEOLOGICAL SUMMARY AND**

### **ZONES OF INTEREST**

The Fellows Energy, LLC, Crane #6-7 well was spud on April 8, 2004. The well was located approximately six miles west of Evanston, Wyoming along the hanging wall of the Alcock Thrust. The well was designed to locate and core the coals of the lower Frontier and Bear River Formations. The well reached a total depth of 4280 feet in the lower Bear River Formation on May 2, 2004, having achieved all of its objectives.

The primary objectives for the Crane #6-7 well were to core the Spring Valley coal section in the lower portion of the Frontier Formation, and the coal sections in the middle and lower portions of the Bear River Formation. Coring was done with a wireline retrievable coring system so as to collect the most valid coal desorption values possible. Secondary objectives included coring the Chalk Creek coals in the middle portion of the Frontier if gas shows were seen while drilling, coring the interval through the middle of the Bear River Formation that exhibited shows in the Crane #13-8 offset well, and the analysis of a potential updip pinch-out of a thick (70 foot) sand developed at the top of the Bear River Formation in the Suttons #4-12 well. The Quaneco, LLC Suttons #4-12 well in Section 12-T6N-R7E was used for structural comparison.

Geological supervision with gas detection began at a depth of 1300 feet, approximately 150 feet above the regional unconformity. The upper portion of the hole was drilled with water. A KCL-based mud system was initiated around 1000 feet, and continued through total depth. The KCL system was utilized to inhibit the shale as moderate to severe hole washout was seen in the offset wells. The hole was drilled with no major mechanical problems. The caliper logs indicated that the KCL mud system was very successful as the well appeared to have minimal washouts.

Due to hole deviation out from under the surface casing, a conventional BHA and insert bit were used to drill from 714 feet to 1384 feet. The wireline retrievable coring system was run in the hole at 1384 feet, but the PDC bit used with the retrievable coring system did not perform as planned. The hole was therefore conventionally drilled from 1515 feet to first coring depth at which time the coring system was used to core the Spring Valley coal section from 2113 feet to 2255 feet. A conventional BHA was again utilized from 2255 feet to 3510 feet. Continuous cores were cut from 3510 feet to 3746 feet in the upper coal section of Bear River Formation. A conventional BHA was utilized to drill from 3746 feet to 4006 feet. The lower coal section of the Bear River section was cored from 4006 feet to 4186 feet. A conventional BHA was then used to drill the rat hole from 4186 feet to total depth of 4280 feet. In all, 30 cores were cut and recovered from the three cored intervals.

The following are brief summaries of the lithologies encountered in the well. For detailed lithologic descriptions, the reader should refer to either the preceding section or the accompanying geologic log.

Surface casing was pre-set to 525 feet within the Wasatch Formation. From the base of the surface casing to the unconformity at 1452 feet, the well penetrated the expected section of interbedded shale, siltstone and sandstone with minor amounts of limestone. Minor amounts of light gray to white translucent to dark gray opaque chert were noted associated with the limestone intervals. The shale through the section was light gray to gray green to red brown in part, silty to sandy in part and calcareous. No shows were noted in this upper portion of the hole

The Frontier was penetrated directly below the unconformity at a drill depth of 1452 feet (5360 foot datum). In this well, the Frontier to the top of the Spring Valley Coal section was characterized by the typical interbedded sandstone and shale with occasional limestone stringers. The shale in the upper portion of the section down to 1550 feet was light gray to gray green, waxy and bentonitic shale grading into micaceous bentonite. The shales through the remaining section to the top of the Spring Valley Coals were primarily light to medium gray to pale blue gray in color, blocky in character, moderately firm and slightly to moderately calcareous. A few dark gray to dark brown to black carbonaceous shales were noted through the section, usually associated with a sandstone section. These carbonaceous shales were moderately soft and plastic with a brown greasy streak. Coal stringers and inclusions were also noted within these carbonaceous shales.

The sandstone intervals encountered in the Frontier section were similar in appearance, being medium to light gray, fine to very fine grained, detrital in part, i.e. composed of sands, silt, fossil fragments and carbonaceous fragments, and were moderately calcareous with rare very fine grained pyrite. Only a few very minor shows were noted though the upper portion of the Frontier.

The Spring Valley Coal section was penetrated at a drill depth of 2097 feet with a corresponding datum of 4715, 1255 feet high to the Suttons #4-12 comparison well. This interval was characterized by interbedded shale, carbonaceous shale and coal with occasional silty interbeds. The shale was typically medium to dark gray, silty to sandy in part and slightly calcareous with scattered coal inclusions and local zones of fossil hash (brachiopods). The carbonaceous shale was dark gray to black, moderately firm, slightly calcareous and graded to coals that were black, soft to friable, locally vitreous and commonly fractured with local cleats. An interval of sandstone was cored from 2199 feet to 2219 feet. The sandstone was medium to light gray, fine to very fine grained, moderately to slightly calcareous with fossil fragments and minor carbonaceous inclusions.

The Spring Valley Coal section only had 4 thin coal seams developed in this well for an aggregate total of about 8 feet of coal. In comparison, the Suttons #4-12 well exhibited 8 to 10 coal seams with approximately 28 net feet of coal through the same interval. It appears the lower, better-developed coals seen in the Suttons well were missing in this well, having been replaced by the sandstone interval described in the preceeding paragraph. The shows seen through this interval are summarized in the following table:

DEPTH	ROP	BG GAS	PEAK	C <sub>1</sub> (ppm)	C <sub>2</sub> (ppm)	C <sub>3</sub> (ppm)	C <sub>4</sub> (ppm)
2096'-2100'	5.0/0.9/5. 3	2-3 units	49 units	4862	---	---	---
2143'-2157'	20/5.0/50	5-6 units	78 units	7833	---	---	---
2169'-2182'	75/3.0/20	3-5 units	44 units	4454	---	---	---

The Aspen Shale was penetrated at a drill depth of 2234 feet (4578 foot datum), 1224 feet high to the Suttons #4-12 comparison well. The upper portion of the Aspen section down to 2430 feet was characterized by light to medium gray shale that was platy to sub-platy, moderately firm and slightly to moderately calcareous. This interval was also slightly silty in part and exhibited scattered finely disseminated pyrite. From 2430 feet to the top of the Bear River, the shale became predominately dark gray to brown in color, slightly more carbonaceous with a slight increase in pyrite. Thin light gray-white to pale blue gray bentonite intervals were also encountered through this lower portion of the Aspen section.

The Bear River Formation was penetrated at a drill depth of 2614 feet with a corresponding datum of 4198 feet, 1226 feet high to the Suttons #4-12 well. It was initially composed of interbedded shale and carbonaceous shale with occasional silty to sandy interbeds. The shale was medium gray, sub platy, moderately firm, silty and slightly to moderately calcareous and graded locally to carbonaceous shale. The carbonaceous shale was dark gray to black, moderately firm, slightly silty in part and slightly to moderately calcareous. Local stringers were composed of siltstone to sandstone, medium to light gray, very fine grained, moderately to very slightly calcareous. At 2756 feet, the lithology changed to a package of sandstone and siltstone with minor interbedded shale. The sandstone was light gray to white, locally salt and pepper, translucent in part, fine to very fine grained, massive to sub-platy and moderately hard to firm. It graded locally to medium gray brown, light to dark gray siltstone that was firm to moderately hard, locally sandy and slightly calcareous to strongly calcareous in part with calcite veining. The shale interbeds were dark to medium gray, platy to sub-platy, moderately hard and slightly to moderately calcareous. Only minor gas shows were noted through this interval, and are summarized in the table below.

DEPTH	ROP	BG GAS	PEAK	C <sub>1</sub> (ppm)	C <sub>2</sub> (ppm)	C <sub>3</sub> (ppm)	C <sub>4</sub> (ppm)
2688'-2703'	2.0/1.4/1.8	6-8 units	22 units	2244	---	---	---
3025'-3044'	3.0/1.5/4.8	5-6 units	34 units	3402	---	---	---
3066'-3078'	3.5/2.3/3.1	6-8 units	21 units	2125	---	---	---

The middle coal section of the Bear River Formation was continuously cored from 3510 feet to 3746 feet. The interval from 3510 feet to 3660 feet was composed of interbedded sandstone and shale. The sandstone was primarily light gray, very fine grained grading to siltstone in part, sub-angular to sub rounded, well sorted and well cemented with calcite cement. The shale in this section was primarily medium to dark gray, blocky firm and slightly calcareous. It was also silty to sandy in part, and bentonitic in places and fossiliferous in part. The main interval of interest in this upper section was penetrated from 3660 feet to 3740 feet. It was composed predominately of dark gray to black carbonaceous shale with thin interbeds of coal and coal partings incorporated within the shale. The shale was slightly firm to moderately soft, carbonaceous, slightly calcareous to non-calcareous and exhibited beds with abundant fossil shells (probable oyster beds). Thin interbeds of pale gray green bentonite were also present throughout. Only minor amounts of coal were recovered through this section. Much of it was shaley in appearance, and only a few beds exhibited good cleating with associated concoidal fracturing. The table below summarizes the shows noted through this coal section while coring.

DEPTH	ROP	BG GAS	PEAK	C <sub>1</sub> (ppm)	C <sub>2</sub> (ppm)	C <sub>3</sub> (ppm)	C <sub>4</sub> (ppm)
3616'-3618'	10.5/2.4/24	1-3 units	31 units	3050	---	---	---
3652'-3655'	26.5/22/46	5-7 units	21 units	2054	---	---	---
3660'-3682'	25/1.7/9.0	2-3 units	20 units	1944	---	---	---
3697'	8.4/2.9/14.1	8-15 units	41 units	4129	---	---	---
3703'	---	6-10 units	57 units	5679	---	---	---
3710'	---	6-10 units	46 units	4625	---	---	---
3717'	---	5-9 units	37 units	3658	---	---	---
3733'	---	4-6 units	24 units	2362	---	---	---

The interval from 3746 to 4006 feet was conventionally drilled and penetrated a section of interbedded limestone, sandstone and shale. The limestone was primarily tan to medium brown in color, moderately to slightly hard and micro-crystalline with abundant fossil shells. The limestone was also argillaceous to very argillaceous in part grading into very calcareous fossiliferous shale. The uppermost limestone interval from 3800 feet to 3820 feet exhibited a trace show consisting of scattered

black dead stain on fracture faces with no associated fluorescence, and only a faint residual ring cut in chlorothene.

The shale penetrated in this interval was medium to dark gray to occasionally dark gray brown, blocky, slightly firm to moderately soft, carbonaceous and fossiliferous in part. The shale had an earthy to silty appearance and was quite soft in places. The sandstones drilled through this section were tan to light gray to light brown, very fine grained, sub-rounded and well sorted. They were composed primarily of quartz grains with scattered dark gray lithic grains, and were moderately hard to hard and well cemented with calcite and possible quartz overgrowth cement. Numerous minor gas shows were noted through this section, most of which were associated with coal stingers or thin coal beds. These shows are summarized in the table below.

DEPTH	ROP	BG GAS	PEAK	C <sub>1</sub> (ppm)	C <sub>2</sub> (ppm)	C <sub>3</sub> (ppm)	C <sub>4</sub> (ppm)
3754'-3755'	8.4/4.1/7.7	3-5 units	22 units	2230	---	---	---
3784'-3785'	5.2/1.8/5.8	4 units	16 units	1624	---	---	---
3821'-3832'	6.2/2.1/5.4	4-5 units	53 units	5252	---	---	---
3846'-3848'	6.4/1.5/11.5	3-4 units	23 units	2323	---	---	---
3890'-3892'	4.2/2.1/5.0	3-4 units	29 units	2864	---	---	---
3907'-3913'	9.5/3.5/7.4	4-7 units	54 units	5357	---	---	---
3920'-3924'	8.1/5.0/7.0	6-13 units	32 units	3204	---	---	---
3928'-3935'	6.8/3.2/8.2	5-9 units	34 units	3416	---	---	---
3959'-3986'	6.5/2.5/10.4	6 units	32 units	3157	---	---	---

The lower Bear River coal section was continuously cored from 4006 feet to 4185 feet. The uppermost coal was penetrated at a depth of 4012 feet with a corresponding datum of 2800 feet, 757 feet low to the Crane #13-8 well, located 5000 feet east of the #6-7 location. The interval was composed primarily of shale and carbonaceous shale with thin interbedded coal intervals. The shale was tan to brown to medium to dark gray to black, hard to firm, calcareous and very silty in part and displayed occasional fossiliferous intervals. Numerous thin interbedded very calcareous intervals grading to argillaceous limestone were also logged through this interval. Scattered thin cream to tan colored bedded bentonites were also observed in the core. A number of thin coals were encountered through the cored section, and generally displayed a vitreous luster, were soft and slightly pyritic, and shaly in part. The shows encountered from the coals in this interval are summarized in the table below.

DEPTH	ROP	BG GAS	PEAK	C <sub>1</sub> (ppm)	C <sub>2</sub> (ppm)	C <sub>3</sub> (ppm)	C <sub>4</sub>
4008'-4012'	21/1.1/5.2	4-8 units	112 units	11231	---	---	---
4021'-4023'	6.5/1.9/11.4	5-12 units	53 units	5325	---	---	---
4031'-4036'	8.1/1.1/6.5	22-27 units	63 units	6309	---	---	---
4045'-4047'	10/1.7/8.5	17-42 units	64 units	6351	---	---	---
4048'-4050'	8.5/4.5/12.6	42-22 units	66 units	6592	---	---	---
4054'-4058'	13.8/4/35.8	22-23 units	62 units	6190	---	---	---
4111'-4113'	28/2.8/5.5	10 units	35 units	3541	---	---	---
4116'-4120'	5.5/3.3/7.0	10 units	40 units	3995	---	---	---
4136'-4141'	48/4.5/12.5	4-8 units	38 units	3812	---	---	---
4160'-4162'	2.8/1.5/4.0	3-5 units	62 units	6212	---	---	---
4168'-4171'	6.5/0.95/2.7	3-4 units	73 units	7310	---	---	---
4180'-4182'	1.8/0.8/1.5	10-15 units	47 units	4720	---	---	---

A thin carbonaceous shale section with a thin coal stringer was drilled from 4188 feet to 4205 feet below the lower-most cored interval. The interval from 4205 feet to 4250 feet was characterized by interbedded silty shale and calcareous siltstone. This siltstone was tan to light brown, blocky and hard to soft and earthy in texture. It was calcareous to very calcareous grading to a very silty argillaceous limestone in part. The lowermost portion of the hole from 4250 feet to total depth was predominately cream to tan colored sandstone that was very fine to fine grained to medium grained near the base. It was composed quartz and lithic grains and appeared clay filled. It was hard and well cemented with calcite cement. No shows were noted in this interval.

## **DISCUSSION:**

The Crane #6-7 well penetrated the expected section consisting of the Wasatch Formation, then into the Frontier Formation below the unconformity and then into the underlying Aspen and Bear River formations. Total depth was 4280 feet in the lower portion of the Bear River Formation.

The primary objectives of the Crane #6-7 well were to core the prospective coal intervals in the Frontier (Spring Valley Coal section) and the Bear River formations for gas desorption analysis. A wireline core retrieval system by Corion Systems was utilized to reduce the amount of time between cutting the coal and getting them into desorption canisters. The continuous coring system worked very well with close to 100 percent core recovery. Penetration rates ranged from less than one foot per hour to up to ten feet per hour while coring. This slow penetration rate precluded the ability to core as much of the well as originally planned, but still, most if not all the target coals were cored. Ticora Geosciences performed the core and coal desorption analyses. Secondary objectives included coring the Chalk Creek coals in the middle portion of the Frontier if gas shows were seen while drilling, and to analyze the updip pinch-out of the sand at the top of the Bear River encountered in the Suttons #4-12 well.

The few thin coals encountered in the middle portion of the Frontier (Chalk Creek section) exhibited only very minor shows, so no coring was done through this interval.

The Spring Valley coal section in the lower portion of the Frontier formation exhibited much less coal than anticipated based on the Suttons #4-12 comparison well. The Suttons well exhibited 8 to 10 coal seams with approximately 28 net feet of coal while this well had only 4 thin coal seams developed for an aggregate total of about 8 feet of coal. The lower coal section seen in the Suttons well was missing in this well, having been replaced by sandstone. This sandstone interval could reflect a barrier bar system that may have been developed seaward of the coal swamp.

Thin sandstone with a minor gas show was developed near the top of the Bear River Formation. This sand was also present in the Suttons #4-12 comparison well, but located just below the 70 foot thick sand interval. Hence, the objective sand was completely shaled out at this location, but potentially could be encountered in a structurally advantageous position in a well drilled slightly farther to the west.

The section in the middle portion of the Bear River equivalent to that which exhibited shows in the Crane #13-8 well to the east was cored from 3510 feet to 3746 feet. The upper portion of this section was primarily interbedded shale and sandstone with only minor coal development. The interval of interest from 3660 feet to 3746 feet was composed predominately of carbonaceous shale with coal stringers and thin coal beds. This interval in the Crane #13-8 offset well was described as interbedded coal, limestone and shale and had an associated show with methane, ethane and propane noted on the mudlog. The volume of coal expected based on the Crane #13-8 well was not encountered. The intervals interpreted as coal on the Crane #13-8 density log well may simply have been cycle skip as the interval was moderately washed out.

The lower Bear River coal section was cored from 4006 feet to 4185 feet. There was a thin coal near the top of the section with a good associated gas show, and several smaller coal stringers with lesser shows from 4012 feet through 4060 feet. The interval from 4060 feet to 4130 feet was fairly barren of coal or gas shows. The lower coal section from 4130 feet to 4206 feet displayed 5 or 6 thin coal seams with moderate associated gas shows. In all, this lower Bear River section correlated very well with the offset Crane #13-8 well, and displayed a very similar coal section.

### **CONCLUSIONS:**

While the objective of coring the coal intervals was met, the coals encountered were thinner than expected based on offset logs. Numerous gas shows were noted associated with the thin coals and coal stringers within the carbonaceous shale sections. The gas shows were composed entirely of C1 with no heavier fraction, indicating that any production from the coals in this area would be entirely methane, and very likely would not have any associated liquid hydrocarbon production. The coals with their associated gas shows in the lower Bear River section correlated very well with the Crane #13-8 well, but were thinner than expected. This was true for all the coal section cored in this well. This may very well be due to many of the intervals interpreted to be coals in the offset wells actually being carbonaceous shales with coal partings and thin stringers of coal.

The thick sand objective, which was present at the top of the Bear River Formation in the Suttons #4-12 well, was completely shaled out and missing in this well. The thin sand that exhibited a minor show seen near the top of the Bear River section appeared to be very shaly based on the gamma ray signature. It did exhibit 10 feet of porosity on the density/neutron log, but the actual porosity would be considerably less than the indicated 22% when a shale correction is applied. The resistivity of 5 to 8 ohms is indicative of the zone being wet.

As there was considerably less coal developed in both the Spring Valley and Bear River coal sections than anticipated, and a review of the logs indicated no potential in the sand at the top of the Bear River, it was recommended the Crane #6-7 well be plugged as a dry hole.

It may be possible to drill a location west and slightly downdip so as to encounter the sand at the top of the Bear River in an advantageous position. However, prior to drilling another well, it is recommended additional seismic be acquired so as to better map the structure and stratigraphic position of both the coal sections and any potential sand bodies present in the Bear River section.

Jason G. Blake  
AAPG CPG #5633  
Wyoming PG #3295  
Utah RPG #2250  
Consulting Geologist



**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

## SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: NA <u>Fce</u>
2. NAME OF OPERATOR: <b>Fellows Energy Ltd.</b>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NA
3. ADDRESS OF OPERATOR: <b>807N Pinewood Circle</b> CITY <b>Price</b> STATE <b>Ut</b> ZIP <b>84501</b>		7. UNIT or CA AGREEMENT NAME: NA
4. LOCATION OF WELL FOOTAGES AT SURFACE: <u>2,363' FNL 1,970' FWL</u> COUNTY: <u>Rich</u> QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <u>SENW 7 6N 8E</u> STATE: <b>UTAH</b>		8. WELL NAME and NUMBER: <b>Crane 6-7</b> 9. API NUMBER: <b>4303330053</b> 10. FIELD AND POOL, OR WILDCAT: <b>Wildcat</b>
5. PHONE NUMBER: <b>(435) 650-4492</b>		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>5/15/2005</u>	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input checked="" type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: _____
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

This well was P&A May 3, 2004. This location is supposed to be reclaimed by May 3, 2005. It is requested that this date be extended to September 15, 2005. The unusually wet fall and winter and spring leave conditions too wet at this time. The fluids remaining in the reserve pit will begin to be trucked to disposal on or about May 15, 2005 and reclamation will proceed over the summer with seeding occurring by September 15, 2005.

**Approved by the  
Utah Division of  
Oil, Gas and Mining**

Date: May 4, 2005  
By: Lisha Cordova

NAME (PLEASE PRINT) <u>Clifford Murray</u>	TITLE <u>Exploitationist</u>
SIGNATURE <u><i>Clifford Murray</i></u>	DATE <u>5/2/2005</u>

(This space for State use only)

**From:** Lisha Cordova  
**Subject:** Fwd: RE: Fellows Energy

5/5/05 Copy to Cliff Murray  
 Fellows Energy

>>> "Sewell, James" <jsewell@fmc-slc.com> 05/04/05 5:20 PM >>>  
 Lisha,

It is OK by us. We would like to see all of the fluids gone by June 1. Also, I would like to have all of the dirt work done by August 15, as we will have cattle in there after that.

We will use a similar seed mix to the one I proposed for the State Section. The poundage on that will be approximately.

Species	Pounds PLS/Acre
Alfalfa	2.0
Sanfoin	0.5
Small Burnett	0.25
Cicer Milkvetch	0.5
Intermediate Wheatgrass	1.0
Great Basin Wildrye	1.0
NewHy Wheatgrass	1.0
Fourwing Saltbush	0.5
Forage Kochia	0.5
Hobble Creek Sage Brush	0.5
Total - Approx	<del>8.25</del> 7.75

Application Method - fall broadcast (+ 10 per Acre)

Thanks for keeping me in the loop on the Crane 6-7 extension filing. If you have any questions or concerns, let me know.

James Sewell  
 DL&L

-----Original Message-----

From: Lisha Cordova [mailto:lishacordova@utah.gov]  
 Sent: Wednesday, May 04, 2005 10:57 AM  
 To: Sewell, James  
 Subject: Fellows Energy

Hi James,

Fellows has been granted a reclamation extension for the Crane 6-7 well site, see attached sundry. Let me know if you have any concerns. Fellows should be working with you (DL&L) throughout the reclamation process, I plan to visit the site toward the end of May, I will need access so I will contact you when I plan to come out.

Thanks, and take care!



## State of Utah

### Department of Natural Resources

MICHAEL R. STYLER  
*Executive Director*

### Division of Oil, Gas & Mining

JOHN R. BAZA  
*Division Director*

JON M. HUNTSMAN, JR.  
*Governor*

GARY R. HERBERT  
*Lieutenant Governor*

May 31, 2005

Fellows Energy, LTD  
370 Interlocken Blvd, Suite 400  
Boulder, CO 80021

RE: Operator Plugging Bonds #04-006 (CD#353103303510 and  
CD #353103303528)

Dear Sirs or Madams:

The Division of Oil, Gas and Mining (the Division) sent notice via phone calls and e-mail to Steve Prince in July 2004 stating the two CD's would not qualify as a blanket bond for Fellows Energy, LTD (Fellows) until two years audited financial statements and the most current quarter financial statement are provided. (See Rule R649-3-1-6.4 attached) or a surety to meet the requirement of blanket bonding.

To date, you have used \$105,000 of the \$120,000. The Division has not released the 10-33C2 and the Crane 6-7 as reclamation is not completed. Details of the requirements for reclamation can be obtained from Lisha Cordova at (801) 359-5296. Upon completion of the reclamation, Fellows will need to request these two well sites be released from the plugging bond.

The wells now attached to Bond #04-006 are the 11-33C2 @ 1800'; the 12-33C2 @ 2400'; the 10-33C2 @ 1800'; the Crane 6-7 at 5000' and the Bolinder 2-2 @ 3900'.

If you have other questions, please call me at (801) 538-5336.

Sincerely,

Earlene Russell  
Engineering Technician

#### Attachment

cc: Dan Jarvis, DOGM Technical Services  
Lisha Cordova  
Ed Bonner, TLA  
George Young  
Steve Prince  
Cliff Murray

Division of Oil, Gas and Mining  
PHONE CONVERSATION DOCUMENTATION FORM

Route original/copy to:

☒ Well File Crane 6-7

☐ Suspense

☐ Other

(Loc.) Sec 7 Twp 6N Rng 8E

(Return Date) \_\_\_\_\_

(API No.) 43-033-30053

(To-Initials) \_\_\_\_\_

1. Date of Phone Call: 7/20/05 Time: 3:00

2. DOGM Employee (name) L. Cordova ( ☐ Initiated Call)

Talked to:

Name Lorne James ( ☐ Initiated Call) - Phone No. (307) 673-1500 ext. 10  
of (Company/Organization) Phaneco

3. Topic of Conversation: Fellows Energy - Desig. Op, planning to move water from reserve pit & begin site reclamation.

4. Highlights of Conversation: Op. initially planned to move water in 5/2005, site reclamation extension granted to Sept. 2005 on May 4, 2005.

**From:** Lisha Cordova  
**To:** "cliffmurray@fellowenergy.com".mime.MNET  
**Date:** 9/20/2005 10:51:05 AM  
**Subject:** RE: Crane 6-7/43-033-30053

Hi Cliff,

Thanks for the information. Please make sure the reclaim work is conducted in accordance with your landowners agreement, and let me know when the site is ready for inspection.

Thanks & take care!

>>> "Cliff Murray" <cliffmurray@fellowenergy.com> 9/20/2005 10:27 AM >>>  
Lisha, no it is not reclaimed yet but the pit has been emptied and it is ready to reclaim. Steven is sending money to Terry Pruitt today to get him started and I have a call in to him to see when he can start. Thanks.  
Cliff

-----Original Message-----

**From:** Lisha Cordova [<mailto:lishacordova@utah.gov>]  
**Sent:** Monday, September 19, 2005 10:51 AM  
**To:** Clifford Murray  
**Subject:** Crane 6-7/43-033-30053

Hi Cliff,

The Division granted Fellows a reclaim extension for the above referenced site to Sept. 15, 2005. Is the site reclaimed & ready for inspection?

**cc:** jsewell@fmc-slc.com

*9/28/05 Terry Pruitt/DL&L, started reclaim work on 9/27/05,  
will call me when grade & seed is complete for inspection.*

**From:** Lisha Cordova  
**To:** "nonapi@iwworks.com".mime.MNET  
**Date:** 10/13/2005 9:04:12 AM  
**Subject:** RE: Crane 6-7 and 10-33C2

Hi Cliff,

I'll get in touch with Terry Pruitt/DLL to notify me when the site has been seeded before taking a trip out.

Please notify Mark Jones (DOGM Price Office) when the 10-33C2 well site is reclaimed, seeded, and ready for inspection. His phone number is (435) 613-1146/ext. 204 or [markjones@utah.gov](mailto:markjones@utah.gov).

Thank you!

>>> "Cliff Murray" <[nonapi@iwworks.com](mailto:nonapi@iwworks.com)> 10/12/2005 4:52 PM >>>  
Just another note. DLL has probably not reseeded yet.

-----Original Message-----

From: Lisha Cordova [<mailto:lishacordova@utah.gov>]  
Sent: Wednesday, October 12, 2005 4:45 PM  
To: [nonapi@iwworks.com](mailto:nonapi@iwworks.com)  
Subject: Re: Crane 6-7 and 10-33C2

Thank you Cliff, I'll run out & take a look at the reclaim job as soon as I can.

Take care!

>>> "Cliff Murray" <[nonapi@iwworks.com](mailto:nonapi@iwworks.com)> 10/12/2005 4:19 PM >>>  
Ms. Lisha,  
I talked with Terry Pruitt and he said the reclamation is done on the Crane 6-7 so I'll follow up with getting a release from DLL. DLL has already been paid for the seeding.

Garfield County Well:

The 10-33C2 is not reclaimed yet but I received a seeding mix from SITLA today and so reclamation will start shortly. I'll call Clark Howard and see what day he'll be starting and let you know.

Thanks.  
Cliff

**CC:** Dan Jarvis; Mark Jones

## **DESERET LAND AND LIVESTOCK**

PO Box 250, Woodruff, UT 84086, (435) 793-4288

---

### Memo

To: Cliff Murray  
Fellows Energy  
From: James Sewell  
CC: Lisha Cordova  
RE: Crane 6-7 Reclamation / 43-033-30053


---

Cliff,

As of October 21<sup>st</sup>, all of the reclamation work on the Crane 6-7 location has been completed. Terry Pruitt has completed the necessary dirt work. Deseret Land and Livestock has completed re-seeding the location. We used a mix of grasses, forbs, and shrubs, that should blend in well with the native vegetation

As per our agreement, DL&L will assume any future responsibility for re-establishing vegetation on the site. Fellows Energy has fulfilled their obligation to the landowner, in terms of returning the site to an acceptable condition. I will send a copy of this memo to Lisha Cordova, with the Utah Department of Oil, Gas, and Minerals.

Thanks,



James Sewell  
Area Foreman  
Deseret Land and Livestock

**RECEIVED**

**OCT 25 2005**

**DIV. OF OIL, GAS & MINING**

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML48334
2. NAME OF OPERATOR: Fellows Energy Ltd.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NA
3. ADDRESS OF OPERATOR: 807 N pinewood Circle CITY Price STATE Ut ZIP 84501		7. UNIT or CA AGREEMENT NAME: NA
PHONE NUMBER: (435) 650-4492		8. WELL NAME and NUMBER: Crane 6-7
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2,363' FNL 1,970' FWL		9. API NUMBER: 4303330053
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 7 6n 8e S		10. FIELD AND POOL, OR WILDCAT: Wildcat

COUNTY: Rich

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 10/21/2005	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input checked="" type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Well site has been reclaimed and reseeded (see attached letter of release of liability from surface owner Deseret Land and livestock. .

NAME (PLEASE PRINT) Clifford Murray TITLE Exploitationist  
SIGNATURE  DATE 12/15/2005

(This space for State use only)

RECEIVED

DEC 29 2005

DIV. OF OIL, GAS & MINING



## **DESERET LAND AND LIVESTOCK**

PO Box 250, Woodruff, UT 84086, (435) 793-4288

### **Memo**

To: Cliff Murray  
Fellows Energy  
From: James Sewell  
CC: Lisha Cordova  
RE: Crane 6-7 Reclamation


---

Cliff,

As of October 21<sup>st</sup>, all of the reclamation work on the Crane 6-7 location has been completed. Terry Pruitt has completed the necessary dirt work. Deseret Land and Livestock has completed re-seeding the location. We used a mix of grasses, forbs, and shrubs, that should blend in well with the native vegetation

As per our agreement, DL&L will assume any future responsibility for re-establishing vegetation on the site. Fellows Energy has fulfilled their obligation to the landowner, in terms of returning the site to an acceptable condition. I will send a copy of this memo to Lisha Cordova, with the Utah Department of Oil, Gas, and Minerals.

Thanks,



James Sewell  
Area Foreman  
Deseret Land and Livestock